## 21st March 2016

Ref:ha/let1/addendum/stationrd

Your Ref:

Mr C Chapman Clive Chapman Architects 4 Eel Pie Island Twickenham Middlesex TW1 3DY





Please find below a record of the root investigations and our advice.

The tree and trench numbers are provided on the attached plan.

Table 1

Trench No	Soil Type	Root Depth	Observation*	Comment/Recommendation
1	Sandy gravel and fill	120mm- 140mm	1 x 20mmØ 1 x 25mmØ	2 x small, woody to woody roots found just underside concrete
1	As above	120-140	Very fine to small - several	Fibrous rooting within sandy gravel underside of concrete

Note:

## \*Table 2

Root Size/Description	Function	
1-5mmØ – Very fine	Moisture and element absorption	
5-10mm – Small	Moisture and element absorption & some starch storage; conduit and minor anchorage	
10-20 – small woody	Starch storage; Conduit and anchorage	
20-50 - woody	Starch storage; Conduit and anchorage	
>50-100 Large woody	Starch storage; Anchorage, conduit and structural	
>100 Structural/buttress	Starch storage; Anchorage, main conduit and structural	









## **Conclusions and Recommendations**

The above findings demonstrate that root development of the Walnut tree T4 is broadly retained to the tree-side of the boundary. Two roots of 20 and 25mm diameter respectively have grown under the footings of the wall, together with some minor rooting of less than 10mm diameter.

Excavations within soil in which roots have exploited, will need to be carried out under specialist supervision and in conjunction with proper root pruning techniques performed by a professional.

I hope that the above is clear and helpful but if I can be of any further assistance, please do not hesitate to contact me.

Yours sincerely

Hal Appleyard
Dip. Arb. (RFS), F.Arbor.A, MICFor. *Arboricultural Association Registered Consultant* 

Jeff &



