


700mm.




# AQUACELL STORAGE SYSTEM

NOTE
THE COLLECTION SUMP SHOULD NOT BE ALLOWED TO OVERFILL AS THIS WILL LEAD TO SILT CARRY—OVER INTO THE AQUACELL MODULES.

THE COLLECTION SUMP SHOULD NOT BE ALLOWED TO OVERFILL AS THIS WILL LEAD TO SILT CARRY—OVER INTO THE AQUACELL MODULES. THE FREQUENCY AT WHICH THE CATCHPIT SHOULD BE EMPTIED WILL NEED TO BE DETERMINED ON SITE. IT WILL GENERALLY ONLY BE NECESSARY TO ENSURE THE CATCHPIT/SILT TRAP ARE FREE FROM DEBRIS SUCH AS LEAVES OR SEDIMENT. IT IS RECOMMENDED THAT THE SYSTEM BE INSPECTED NO LESS FREQUENTLY THAN AT MONTHLY INTERVALS FOR THE FIRST 3 MONTHS AND THEREAFTER AT 6 MONTH INTERVALS. INDIVIDUAL MAINTENANCE SCHEDULES SHOULD BE DRAWN UP USING THE INFORMATION OBTAINED FROM THE INITIAL INSPECTIONS. IT SHOULD ALSO BE NOTED THAT MORE REGULAR INSPECTIONS MAY BE REQUIRED SHOULD THE CATCHPIT FILL MORE FREQUENTLY AND/OR IF THE INITIAL INSPECTIONS REVEAL THAT MAINTENANCE/CLEANING WILL BE REQUIRED MORE REGULARLY THAN AT SIX MONTH INTERVALS.

FLUSHING OF THE SYSTEM CAN BE ACHIEVED USING A JETTING SYSTEM WITH A 150 BAR PUMP PRESSURE (IE APPROXIMATELY 80 BAR AT THE NOZZLE) AT A DISCHARGE FLOW OF 300 L/MIN. THE SILT SHOULD BE FLUSHED TO THE AQUACELL CATCHPIT MANHOLE AND REMOVED FROM THERE.



DETAIL A AQUACELL AIR VENT SCALE 1:20

DO NOT SCALE HARD COPIES OF THIS DRAWING OR INTERROGATE CAD VERSIONS. ONLY STATED DIMENSIONS
AND COORDINATES ARE TO BE RELIED UPON

COPYRIGHT RESERVED

### GENERAL NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE ARCHITECTS, SPECIALISTS AND ENGINEERS DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ARCHITECT/ENGINEER IMMEDIATELY.

2. REFER TO RLT PRIVATE DRAINAGE LAYOUT DRAWING 1509/03/01-02 FOR LOCATION, SIZES & LEVELS OF AQUACELL UNITS.

#### NOTE


IMPERMEABLE MEMBRANE SHOWN WRAPPED AROUND THE AQUACELL UNITS AS THE TANK MUST BE KEPT SEPARATE FROM THE SURROUNDING GROUNDWATER.

THE GROUNDWATER WILL FLOW UP TO APPROXIMATELY 1.0M SURROUNDING THE SIDES OF THE TANK. IN THE PERMANENT STATE THE WEIGHT OF 1.8M DEPTH OF OVERLYING SOIL ON THE TANK WILL BE SUFFICIENT IN PREVENTING ANY BUOYANCY OF THE TANK.

IN THE TEMPORARY STATE WHEN THE CELLS ARE EMPTY DURING CONSTRUCTION 0.525M BULK OF SANDS & GRAVEL MUST BE LAID OVER THE CELLS TO PREVENT ANY POTENTIAL BUOYANCY.

# TENDER ISSUE

LATEST REVISIONS ARE 'TAGGED' WITH THIS INDICATOR. HOWEVER, ALL USERS OF THIS DRAWING MUST SATISFY THEMSELVES OF ALL REVISIONS TO ANY PREVIOUS ISSUES, BY COMPARISON OF THIS DRAWING AGAINST OTHER ISSUES, AS IT CANNOT BE GUARANTEED



### LATCHMERE HOUSE

AQUACELL DETAILS

BERKELEY HOMES (WEST LONDON) LIMITED

Architect

**BROOKES ARCHITECTS** 

RLT ENGINEERING CONSULTANTS LTD CIVIL AND STRUCTURAL 2 ST PETER'S COURT MIDDLEBOROUGH COLCHESTER, ESSEX,

ISO 9001 T: 01206 768655 F: 01206 768656 REGISTERED FIRM E: email@rltengcon.co.uk

Dwg No. 1509/03/09

Rev: -

Scales: 1:20 @ A1