- Removal of bench and/or associated concrete plinth. New seating to be provided as per drawing 581_PL_L_04 (Furniture Plan)
- 2. Remove timber palisade fencing
- 3. Demolition of former toilet block in Woodland Quarter
- Removal of clipped hedge and fence around Grotto - new planting to improve setting as per drawing 581_PL_L_01 (Illustrative Landscape Plan)
- 5. Demolition of Chinese style shelter
- 6. Removal of bench and/or associated concrete plinth. New play area seating to be provided as per drawing 581_PL_L_04 (Furniture Plan)
- 7. Removal of speed restriction hump to enable access to new service yard entrance
- 8. Demolition of raised lawns in front of the Stable Block to improve setting
- 9. Demolition of timber storage shed
- Removal of existing patches of hard standing and replace with new service yard surfacing
- 11. Demolition of east section of brick wall
- 12. Relocation of 3no. cylce stands
- 13. Removal of picket fence around existing cafe terrace
- 14. Removal of speed restriction humps to improve access to courtyard



