

- Do not scale from this drawing, use only written dimensions.
- All dimensions are drawn in mm unless otherwise noted.
- All dimensions must be checked on site and any discrepancies verified with landscape architect.
- Landscape drawing only to be read in conjunction with architect and engineers
- drawings.

 All materials/items used to be as specified or alternatives to be approved by landscape architect.
- For detailed tree specification see LUC drawing 6377 LD PLN 431.
 Melcourt 'mini mulch' pine mulch. Finished
- level of mulch to be 70mm below adjacent
- Imported topsoil to Q28.
- Rootball guying kit: Platypus RF2RDMP or similar, to installation manual.
- Mona Link irrigation system by green-tech using 4nr mona link 24 tanks joined with unperforated jointing pipe, complete with airpipe, level indicator and vent cap.

 6. 350mm ripped subgrade
- All tree planting to be undertaken in accordance with BS5387:2012 Trees in Relation to Design, Demolition and Construction' and BS8545 'Trees from nursery to independance in the landscape'. All semi-mature trees to be root prepared and
- transplanted to BS4043 'Recommendations for transplanting root-balled trees'.

 All standard trees to be secured with 2nr.
- stakes of 50mm dia softwood, peeled chestnut, larch or oak, straight and free from projections and large or edge knots and with pointed lower end with nails to BS1202.
- Backfill with ameliorant (1m3 per 10m3 topsoil) and fertilizer as Q28. Refer to LUC drawing 6377 LD PLN 431 and
- to the outline landscape management plan for further details.



43 Chalton Street London, NW1 1JD T: 020 7383 5784 F: 020 7383 4798 london@landuse.co.uk www.landuse.co.uk

Richmond Upon Thames College

Sports Centre

Client Atkins

Tree Pit Detail

1:20@A3 for Planning 6377 LD DET 634

Do not scale from this drawing © Drawing & design copyright of LUC