



INTERIOR FIRST FLOOR

All drawings are to be read in conjunction with 'Works' as described in the Analysis of Fabric.

Unless otherwise stated:

- A. Remove all mechanical and electrical services throughout.
- B. Installation of new mechanical and electrical services throughout.
- C. Remove all sanitary and kitchen fittings throughout.
- D. Upgrade fire rating of existing doors using Envirograph Intumescent paper subject to further detailed discussions with statutory authorities: F/1/1 D1, D2; F/1/3 D1; F/1/4 D1; F/1/5 D1; F/1/7 D1; F/1/9 D1; F/1/11 D1, D3; F/1/13 D1, D2; F/1/14 D1; F/1/15 D1; F/1/16 D1; F/1/19 D1, D2; F/2/1 D1.

F/1/1 Breakfast Room / Tented Room

F/1/2 Green Closet

- Restorations
- 200. Remove bathrooms and raised floor to restore original volume.
- 200A. Restore ceiling.
- 201. Restore cupboards by blocking up 1861 doorway F/1/3 D2. Rehang as door F/1/2 D2. New door F/1/2 D3 to match construction detail of F/1/2 D2.
- 202. Dismantle 1950s fish-scale leaded lights to restore decorative glazing to F/1/2 W1 and W2 subject to further detailed research.
- 202A. Uncover and unblock chimneypiece.

F/1/3 Blue Bedchamber

- Restorations
- 203. Remove 1972 fibrous plaster cornice. Replacement cornice subject to further research and opening up.
- 204. Block up F/1/3 D3 to restore original arrangement.
- 205. Remove 1972 casement windows to restore horizontal sliding sash windows and shutters to F/1/3 W1, W2 and W3 to match F/1/2 W1.
- 206. Unblock chimneypiece.

F/1/4 Red Bedchamber

- Restorations
- 207. Remove 1990 dado rail to restore original wall plane.
- 208. Unblock chimneypiece. Take out 1890s cast iron register grate and store.
- 208A. Restore window and shutters following 1980 photograph and details from F/1/2 W2.

F/1/5 Star Chamber

- Restorations
- 209. Restore missing door F/1/5 D1 to match original F/1/4 D1 based upon documentary and archaeological evidence.
- 210. Restore missing two doors F/1/5 D2 to match original F/1/4 D1 and F/1/8 D2 to match F/1/9 D1 based upon documentary and archaeological evidence.

F/1/6 Library

- Restorations
- 211. Restore horizontal sliding end sashes and centre fixed sash to F/1/6 W1 based upon C18 views.
- 212. Remove the 1958 cupboard height doors to each bay flanking the chimneypiece.
- 213. Remove 1930 tilework to restore open fireplace. Alteration
- 214. New trench heater below window W1.
- 214A. Remove later C19 mirror plates to restore 1754 folio cases.

F/1/7 Staircase and Armoury

- F/1/8 Trunk Cloed Passage
- Restorations
- 215. Remove modern plywood ramp leading to F/1/9 Great North Bedchamber to restore step into F/1/9.
- Alterations
- 216. New fire rated glazed panel above decorative laylight F/1/8 RL1.

F/1/9 Holbein Room

- Restorations
- 217. Block up F/1/9 D2 to 1861 bathroom.
- 218. F/1/9 W1 - W3: Take out upper lancet glazing bars (1984) to restore decorative glazing panels based upon documentary evidence.
- Alterations
- 219. Remove bathroom floor, ceiling and roof structure to construct new disabled lift and service riser. Construct new ceiling/floor structure for new bathroom above.
- 220. Take out fixed panel F/1/10 D1. Widen doorway to facilitate disabled access. New architraves to match existing F/1/9 D1.

F/1/11 Gallery

- Restorations
- 221. Restore double doors F/1/11 D2 as shown on the 1922 Country Life photographs and as drawn.
- 222. Take out 1856 glazing bars to all sashes F/1/11 W1-W5 to restore original pattern based upon C18 drawing and decorative glazing based upon Revd Cole 1762 drawings and documentary research.
- 223. Restore mantle shelf with shields to chimneypiece based upon Sandby and Edwards 1783 view and photographic evidence.
- 223A. Remove post 1872 radiator
- 223B. Reinstate tracery to dado based on archaeology and survival example adjacent.

F/1/12 Lobby to Round Room

- Restorations
- 224. Restore partition and door F/1/12 D1 to former China Closet to match original F/1/14 D1 opposite.

F/1/13 Round Room

- Restoration
- 225. Restore tracery to Lobby side of F/1/13 D1 to match original on Round Room side as F/1/13 D1.
- Alteration
- 226. New trench heater in bay window F/1/13 W1.

F/1/14 Back Stairs

- Restoration
- 227. Remove all 1980 partitions to restore original volume of staircase landing and Tudor arch to the lobby to Beaucherc Closet.

F/1/14.1 Lobby to Beaucherc Closet

- F/1/15 Beaucherc Closet
- Restorations
- 228. Block up niche with sink. Remove 1958 Gothic lancet door F/1/15 D2. Relocate sink to G/2/3 toilets.
- 229. Restore plain and coloured glass leaded lights to original arrangement based upon 1922 Country Life photographic evidence. Reinstate decorative glazing based upon documentary evidence.

F/1/16 Tribune Passage

- Restorations
- 230. Remove modern dropped ceiling to east compartment to restore original volume.
- 231. New door F/1/16 D4 to match original F/1/16 D2.
- 232. Reinstate original door swing to F/1/16 D1 and F/1/16 D3.

F/1/17 Tribune

- Restorations
- 233. Restore glazing to laylight based upon Edwards 1783 watercolour.
- 234. Restore vertical sliding sash windows to F/1/17 W1 - W3 to their original configuration as shown on 1922 photograph, glazing bar profiles to match drawn and photographic models. Restore shutters to F/1/17 W1 - W3 based on photographic and archaeological evidence. Restore decorative glazing patterns to each window based upon pictorial and documentary research.

F/1/18 Small Closet

F/1/19 Great North Bedchamber

- F/1/20 Glazed Closet
- Restoration
- 235. Restore decorative glass to window F/1/20 W1 based upon photographic evidence and documentary research.

06/1626/LBG

RECEIVED
12 MAR 2008
PLANNING

RECONSTRUCTION

ALTERATION

REINCORPORATION

STRIP OUT

DATE		REVISION	COMMENT	AUTHOR	APPROVED
08.05.08			LISTED BUILDING CONSENT	JP	SG

THIS DRAWING IS COPYRIGHT PETER INSKIP + PETER JENKINS ARCHITECTS LTD AND MUST NOT BE USED FOR PURPOSES OTHER THAN IN RELATION TO THIS PROJECT UNLESS AUTHORIZED BY THE PRACTICE. THIS DRAWING MUST NOT BE SCALED - WORK TO FIGURED DIMENSIONS ONLY. THIS DRAWING MUST BE READ IN CONJUNCTION WITH THE SPECIFICATION.

STRAWBERRY HILL HOUSE

TITLE
FIRST FLOOR AS PROPOSED

DWG NO SHT GA 015 SCALE 1:100 @A2 DATE FEB 2006

H:\Strawberry Hill\Strawberry phase 1\General Arrangement\PROPOSEDPlans\SH GA 015.dgn

PETER INSKIP + PETER JENKINS ARCHITECTS LTD
19 - 23 WHITE LION STREET LONDON N1 9PD
TELEPHONE 020 7833 4002 FAX 020 7278 5343