


DO NOT SCALE THIS DRAWING USE DIMENSIONS ONLY
 VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING ANY WORK OR SHOP DRAWINGS
 INFORM THE ARCHITECT BEFORE ANY WORK STARTS IF THIS DRAWING EXCEEDS THE QUANTITIES IN ANY WAY

ISSUE STATUS:

Revision	Date	Change of layout
A	19/03/18	Change of layout
B	30/07/18	Addition of notes
C	16/08/18	Addition of doors and minor note changes
D	25/10/18	Removal of shower and changing room changes.



Key

- New walling Type I
- New walling Type II
- New partitions
- Raised sanitary fitting (in green)
- New sanitary fitting (in blue)
- Raised door (in green)
- New door (in blue)
- Identified asbestos; refer to asbestos report

HAZARD Asbestos

Asbestos is present within this building; refer to the asbestos report.

- Notes**
- External doors; refurbished (or new to match existing) and fitted with new entrance and escape ironmongery. Public to enter via DG12 and DG13 when sports users are not using the changing rooms.
 - Existing Railing Boot Scrapers; reset to suit the new paving level.
 - New External Tap; for cleaning mud from wheelchair wheels.
 - Redecorate external shutters.
 - New Accessible WC for use by members of the public when and sports building users.
 - To the left of the door; the kerb to the road is to be removed to allow equal access for users who come to the Sports Building via the access road.
 - New step to resolve change in level between the new ramped surface and the maintenance yard.
 - New external window; style to match existing. This is to allow this changing room to be converted to an office or store. If it is to remain as a changing room an obscuring film will be applied to the glass or the window will not be installed.
 - Existing window fitted with opaque film.
 - New blockwork partition to separate the WCs and Urinals in Area A & Area B.
 - Ramp; pair of ramps and raised section of paving providing level access from the fire escape doors away from the building. The ramps will be minimum 1:21 and 1.8 m wide.
 - Main Entrance Area; paving lifted and relaid to a minimum 1:25 fall to provide level access to the main entrance.
 - 5no. New WCs; these are for use by members of the public and Sports Building users.
 - New robust internal door to allow shower area to be locked off from the WCs and to allow the WCs to be used by the public when the sports building is not in use.

CLIENT
 English Heritage
 Estates Department

PROJECT
 Marble Hill Sports Building
 Refurbishment

TITLE
 Ground Floor Plan
 As Proposed

SCALE
 1:50 @ A1

DATE
 November 2017

JOB N°
 17-146

DRAWN
 HS

DRAWING N°
 210 D

Acanthus House
 57 Hightown Road
 Banbury • Oxfordshire
 OX16 9BE
 Tel: 01295 702600
 Fax: 01295 702601
 architects@acanthusclews.co.uk
 www.acanthusclews.co.uk