

- Notes:

  To be confirmed by Building Control before work commencing
- before work commencing

  -All dimensions to be confirmed on site
  -Supports based on assumption of solid
  masonry walls

  -Adequacy of existing lintels to be confir on site by Building control officer

  -Adequacy of existing foundation to be confirmed on site by Building control of

  Boos and proficients to be stem tied to

- commend on size by Eustain control or -Floor and not joists to be strap tied to via steel straps at 600cc.
  -All floor and root joists to have nogging at 600cc for lateral support.
  -Joists under stud walls, around stairs and
- around velux to be doubled.
- Drawing to be read in conjunction with Architects drawings.