



Note:

All fire door to be 30minutes Fire rated
 Interlinked Fire Alarm to all landings Entrance hall and Kitchen to hard wired connected to main and to have battery back up installed and commissioned by a approved registered installer.
 All dimensions to be varified on site prior to construction
 First floor ceiling to be minimum 30 minutes fire rated
 Load bearing elements of structure incl. new steel beams to have minimum of 30 minutes Fire resistance protection.

PROPOSE LOFT FLOOR PLAN
 HIP VALLEY DETAIL



		PROPOSED ROOF HIP VALLEY DETAIL			
		148 Percy Road TWICKEHAM TW2 6JF			
DRAWN	DEVAN MISTRY	DATE	09/02/21	SIZE	A3
CHECKED				FSCM NO.	DWG NO.
DESIGN				SCALE	1:100
					REV 0
					SHEET