

- It is possible that harm could arise to a designated receptor from an identified hazard, but it is likely that this harm, if realised, would at worst normally be mild. Limited investigation recommended.

Negligible Risk (NR)

- There is a minimal possibility that harm could arise to a receptor. In the event of such harm being realised it is high likely to not be severe. Investigation not deemed necessary.

---

## Appendix 7 – Exploratory Hole Logs

Borehole Logs  
(BH01A, 01B, BH1, BH2)

Windowless Sample Hole Logs  
(WS1A to 3B, WS4)

Hand Dug Pit Logs  
(HA01 to HA03A)

Trial Pit (Infiltration pit) Logs  
(TP/SK1 to TP/SK2)

**CLIENT: LB of Richmond Upon Thames**      **PROJECT: Twickenham Riverside**      **GROUND LEVEL 8.1m**      **HOLE No. BH01**  
 LOGGED BY: DT      CHECKED BY: JD      EXCAVATION METHOD: Cable Percussion (shell and auger)      Grid Reference:      SHEET 1 OF 3  
 FIELDWORK BY: DTX      DATE: 10/11/2020      200mm cased from 0.0 to 10.0m      DATES 24/08/2020 - 25/08/2020      PROJECT NO. 4955,SI  
 TEMPLATE REF: GEL AGS BH BETA      150mm cased from 10.0 to 25.0m

Date/Time and Depth	Depth of Casing	Depth* of Water	Piez.	Description of Strata	Strata		Graphical Representation				Sampling/In-Situ Testing				Laboratory Testing						Additional Tests and Notes	
					Leg	Reduced Level	Depth	SPT 'N' Value				Depths	Type	No.	Blows	SPT N	<425 %	WC %	PL %	LL %		ρ Mg/m <sup>3</sup>
				MADE GROUND (Dark brown and grey, speckled orange, gravelly clayey SAND (fine to medium). Gravel is fine to coarse angular to subangular flint and brick; rare concrete and brick cobbles)		0.00					0											Hand dug starter pit from ground level to 1.2m
				Dark yellow-ish and orange-brown gravelly fine to medium SAND. Gravel is fine to coarse subangular to rounded flint and chert		1.70					1.20	D	1	11 10 12	4							
											2.00	D	2	10 11 44	10							
											3.00	D	3	24 5 10 10 14	39							
											4.00	D	4	12 5 6 6 6	23							
											5.00	D	5	11	9							
											5.00-5.40	B	6	22 32								
				Brown silty CLAY Stiff to very stiff grey silty fissured CLAY		5.50 5.60					5.40	D	7	11 12 5 6	14							
											7.50	U100	8									
											8	U100	9									
											9.00	D	10	13 2 5 6 6	19							

GEL AGS BH BETA 4955,SI TWICKENHAM RIVERSIDE.GPJ GINT STD AGS 3 1.GDT 13/11/20

\*WATER Standing water level    PIEZOMETER  
 Water strikes

Upper seal    Response zone    Lower seal

**SAMPLE AND TEST KEY**

D	Small disturbed sample	S	Standard penetration test	Blows	SPT blows for each 75mm increment
B	Bulk disturbed sample	C	Cone penetration test	SPT N	(35) Undisturbed sample blow count
U	Undisturbed sample	K	Permeability test		N = SPT N value (blows after seating)
P	Piston sample				N*120 = Total blows/penetration including seating
J	Disturbed jar sample				<425 Sample % passing 425 micron sieve
ES	Environmental soil sample				
W	Water Sample				

DEPTH All depths, level and thicknesses in metres

Geosphere Environmental Ltd  
 Unit 11 Brightwell Barns  
 Brightwell, Ipswich, IP10 0BJ  
 Telephone: 01603 298 076

**PROJECT No**  
4955,SI

**SHEET**  
1 OF 3

**HOLE No.**  
BH01





















<b>CLIENT: LB of Richmond Upon Thames</b>		<b>PROJECT: Twickenham Riverside</b>			<b>GROUND LEVEL m</b>			<b>HOLE No. WS02</b>		
LOGGED BY: PC FIELDWORK BY: GEL TEMPLATE REF: GEL AGS BH BETA		CHECKED BY: JD DATE: 13/11/2020		EXCAVATION METHOD: Windowless sampler Uncased to 1.0 m			Grid Reference:			SHEET 1 OF 1
							DATES 27/08/2020 -			PROJECT NO. 4955,SI

Date/Time and Depth	Depth of Casing	Depth* of Water	Piez.	Description of Strata	Strata		Graphical Representation				Sampling/In-Situ Testing				Laboratory Testing					Additional Tests and Notes	
					Leg	Reduced Level	Depth	SPT 'N' Value			Depths	Type	No.	Blows	SPT N	<425 %	WC %	PL %	LL %		ρ Mg/m <sup>3</sup>
				Dark brown silty gravelly fine and medium organic SAND with active roots. Gravel is fine to coarse subangular and subrounded flint (TOPSOIL)		0.00						0									
				MADE GROUND (Brown gravelly fine and medium SAND. Gravel is fine to coarse subangular and subrounded flint with occasional brick and active roots)		0.30						0.20	J	1							
				MADE GROUND (Greyish brown sandy GRAVEL of angular to subrounded concrete and flint with occasional brick)		0.65						0.50	J	2							
						1.00						1									

Borehole terminated at 1.0m due to refusal

GEL AGS BH BETA 4955,SI TWICKENHAM RIVERSIDE.GPJ GINT STD AGS 3 1.GDT 13/11/20

*WATER	▽ Standing water level	PIEZOMETER	Upper seal	SAMPLE AND TEST KEY	D Small disturbed sample	S Standard penetration test	Blows	SPT blows for each 75mm increment
	▽ Water strikes		Response zone		B Bulk disturbed sample	C Cone penetration test		(35) Undisturbed sample blow count
			Lower seal		U Undisturbed sample	K Permeability test	SPT N	N = SPT N value (blows after seating)
					P Piston sample			N*120 = Total blows/penetration including seating
					J Disturbed jar sample			Sample % passing 425 micron sieve
					ES Environmental soil sample			
					W Water Sample			

DEPTH All depths, level and thicknesses in metres

**GEO**  
 Geosphere Environmental Ltd  
 Unit 11 Brightwell Barns  
 Brightwell, Ipswich, IP10 0BJ  
 Telephone: 01603 298 076

**PROJECT No**  
4955,SI  
**SHEET**  
1 OF 1  
**HOLE No.**  
WS02

<b>CLIENT: LB of Richmond Upon Thames</b>		<b>PROJECT: Twickenham Riverside</b>			<b>GROUND LEVEL m</b>			<b>HOLE No. WS02A</b>		
LOGGED BY: PC FIELDWORK BY: GEL TEMPLATE REF: GEL AGS BH BETA		CHECKED BY: JD DATE: 13/11/2020		EXCAVATION METHOD: Windowless sampler Uncased to 1.0 m			Grid Reference:			SHEET 1 OF 1
							DATES 27/08/2020 -			PROJECT NO. 4955,SI

Date/Time and Depth	Depth of Casing	Depth* of Water	Piez.	Description of Strata	Strata		Graphical Representation				Sampling/In-Situ Testing				Laboratory Testing					Additional Tests and Notes		
					Leg	Reduced Level	Depth	SPT 'N' Value				Depths	Type	No.	Blows	SPT N	<425 %	WC %	PL %		LL %	ρ Mg/m <sup>3</sup>
				Dark brown silty gravelly fine and medium organic SAND with active roots. Gravel is fine to coarse subangular and subrounded flint (TOPSOIL)		0.00																
				MADE GROUND (Brown gravelly fine and medium SAND. Gravel is fine to coarse subangular and subrounded flint with occasional brick and active roots)		0.30																
				MADE GROUND (Greyish brown sandy GRAVEL of angular to subrounded concrete and flint with occasional brick)		0.65																
						1.00																

Borehole terminated at 1.0m due to refusal

GEL AGS BH BETA 4955,SI TWICKENHAM RIVERSIDE.GPJ GINT STD\_AGS 3 1.GDT 13/11/20

*WATER	Standing water level	PIEZOMETER	Upper seal	SAMPLE	D Small disturbed sample	S Standard penetration test	Blows	SPT blows for each 75mm increment
∇	Water strikes		Response zone	AND	B Bulk disturbed sample	C Cone penetration test	N	(35) Undisturbed sample blow count
			Lower seal	TEST	U Undisturbed sample	K Permeability test	N	= SPT N value (blows after seating)
				KEY	P Piston sample		N*	*120 = Total blows/penetration including seating
					J Disturbed jar sample		<425	Sample % passing 425 micron sieve
					ES Environmental soil sample			
					W Water Sample			

DEPTH All depths, level and thicknesses in metres

**GEO**  
 Geosphere Environmental Ltd  
 Unit 11 Brightwell Barns  
 Brightwell, Ipswich, IP10 0BJ  
 Telephone: 01603 298 076

**PROJECT No**  
4955,SI  
**SHEET**  
1 OF 1  
**HOLE No.**  
WS02A

<b>CLIENT: LB of Richmond Upon Thames</b>		<b>PROJECT: Twickenham Riverside</b>			<b>GROUND LEVEL m</b>			<b>HOLE No. WS02B</b>		
LOGGED BY: PC FIELDWORK BY: GEL TEMPLATE REF: GEL AGS BH BETA		CHECKED BY: JD DATE: 13/11/2020		EXCAVATION METHOD: Windowless sampler Uncased to 1.0 m			Grid Reference:			SHEET 1 OF 1
							DATES 27/08/2020 -			PROJECT NO. 4955,SI

Date/Time and Depth	Depth of Casing	Depth* of Water	Piez.	Description of Strata	Strata		Graphical Representation				Sampling/In-Situ Testing				Laboratory Testing					Additional Tests and Notes		
					Leg	Reduced Level	Depth	SPT 'N' Value				Depths	Type	No.	Blows	SPT N	<425 %	WC %	PL %		LL %	ρ Mg/m <sup>3</sup>
				Dark brown silty gravelly fine and medium organic SAND with active roots. Gravel is fine to coarse subangular and subrounded flint (TOPSOIL)		0.00																
				MADE GROUND (Brown gravelly fine and medium SAND. Gravel is fine to coarse subangular and subrounded flint with occasional brick and active roots)		0.30																
				MADE GROUND (Greyish brown sandy GRAVEL of angular to subrounded concrete and flint with occasional brick)		0.65																
						1.00																

Borehole terminated at 1.0m due to refusal

GEL AGS BH BETA 4955,SI TWICKENHAM RIVERSIDE.GPJ GINT STD\_AGS 3 1.GDT 13/11/20

*WATER	▽ Standing water level	PIEZOMETER		Upper seal	SAMPLE	D Small disturbed sample	S Standard penetration test	Blows	SPT blows for each 75mm increment
	▽ Water strikes			Response zone	AND	B Bulk disturbed sample	C Cone penetration test	SPT N	(35) Undisturbed sample blow count
				Lower seal	TEST	U Undisturbed sample	K Permeability test		N = SPT N value (blows after seating)
					KEY	P Piston sample			N*120 = Total blows/penetration including seating
						J Disturbed jar sample			Sample % passing 425 micron sieve
						ES Environmental soil sample			
						W Water Sample			

DEPTH All depths, level and thicknesses in metres

**GEO**  
 Geosphere Environmental Ltd  
 Unit 11 Brightwell Barns  
 Brightwell, Ipswich, IP10 0BJ  
 Telephone: 01603 298 076

**PROJECT No**  
4955,SI  
**SHEET**  
1 OF 1  
**HOLE No.**  
WS02B












Geosphere Environmental Ltd  
 Unit 11 Brightwell Barns  
 Brightwell, Ipswich, IP10 0BJ  
 Telephone: 01603 298 076

### TRIAL PIT LOG

Project <b>Twickenham Riverside</b>		Client <b>LB of Richmond Upon Thames</b>		TRIAL PIT No <b>HP01</b>
Job No <b>4955,SI</b>	Date <b>25-08-20</b>	Ground Level (m)	Grid Reference ( )	
Fieldwork By <b>GEL</b>		Logged By <b>PC</b>		Sheet <b>1 of 1</b>

Depth	DESCRIPTION	Legend	Depth	No	Remarks/Tests
0.00-0.25	MADE GROUND (Dark brown silty gravelly fine and medium SAND. Gravel is fine to coarse subangular to subrounded flint and brick)		0.00-0.25	1WAC	
0.25-1.20	MADE GROUND (Yellowish brown gravelly fine and medium SAND. Gravel is fine to coarse subangular to subrounded flint with occasional brick fragments)		0.25-1.20	2WAC	

GEL AGS TP BETA 4955,SI TWICKENHAM RIVERSIDE.GPJ GINT STD AGS 3\_1.GDT 13/11/20



Shoring/Support: None  
 Stability: Stable

All dimensions in metres Scale 1:12.5	Method Hand Pit	Plant Used HAND	Checked By <b>JD</b>
--	-----------------	-----------------	-------------------------




### TRIAL PIT LOG

Project <b>Twickenham Riverside</b>		Client <b>LB of Richmond Upon Thames</b>		TRIAL PIT No <b>HP02</b>
Job No <b>4955,SI</b>	Date <b>25-08-20</b>	Ground Level (m)	Grid Reference ( )	
Fieldwork By <b>GEL</b>		Logged By <b>PC</b>		Sheet <b>1 of 1</b>

Depth	DESCRIPTION	Legend	Depth	No	Remarks/Tests
0.00-0.20	MADE GROUND (Flexible surfacing)				
0.20-0.70	MADE GROUND (Brown and yellowish brown very gravelly fine and medium SAND. Gravel is whole and partial red brick, concrete, yellow and purple brick)				
0.70-0.80	CONCRETE (Assumed foundation)				
					Hand dug pit terminated at 0.8m due to concrete obstruction

GEL.AGS.TP.BETA.4955.SI.TWICKENHAM.RIVERSIDE.GPJ.GINT.STD.AGS.3.1.GDT.13/11/20



Shoring/Support: None  
 Stability: Stable

All dimensions in metres Scale 1:12.5	Method Hand Pit	Plant Used HAND	Checked By <b>JD</b>
--	-----------------	-----------------	-------------------------




Geosphere Environmental Ltd  
 Unit 11 Brightwell Barns  
 Brightwell, Ipswich, IP10 0BJ  
 Telephone: 01603 298 076

### TRIAL PIT LOG

Project <b>Twickenham Riverside</b>		Client <b>LB of Richmond Upon Thames</b>		TRIAL PIT No <b>HP02A</b>
Job No <b>4955,SI</b>	Date <b>25-08-20</b>	Ground Level (m)	Grid Reference ( )	
Fieldwork By <b>GEL</b>		Logged By <b>PC</b>		Sheet <b>1 of 1</b>

Depth	DESCRIPTION	Legend	Depth	No	Remarks/Tests
0.00-0.10	MADE GROUND (Flexible surfacing)				
0.10-0.40	Concrete and brick layer				
0.40-0.80	Brown slightly gravelly sandy CLAY. Gravel is subangular fine and medium flint with active rootlets				
					Hand dug pit completed at 0.8m

GEL.AGS.TP.BETA.4955.SI.TWICKENHAM.RIVERSIDE.GPJ.GINT.STD.AGS.3.1.GDT.13/11/20



Shoring/Support: None  
 Stability: Stable

All dimensions in metres Scale 1:12.5	Method Hand Pit	Plant Used HAND	Checked By <b>JD</b>
--	-----------------	-----------------	-------------------------




### TRIAL PIT LOG

Project <b>Twickenham Riverside</b>		Client <b>LB of Richmond Upon Thames</b>		TRIAL PIT No <b>HP03</b>
Job No <b>4955,SI</b>	Date <b>28-08-20</b>	Ground Level (m)	Grid Reference ( )	
Fieldwork By <b>GEL</b>		Logged By <b>PC</b>		Sheet <b>1 of 1</b>

Depth	DESCRIPTION	Legend	Depth	No	Remarks/Tests
0.00-0.10	MADE GROUND (Asphalt)				Hand dug pit terminated due to void
0.10-0.12	CONCRETE with rebar				

GEL AGS TP BETA 4955,SI TWICKENHAM RIVERSIDE.GPJ GINT STD AGS 3\_1.GDT 13/11/20



Shoring/Support: None  
 Stability: Stable

All dimensions in metres Scale 1:12.5	Method Hand Pit	Plant Used HAND	Checked By <b>JD</b>
--	-----------------	-----------------	-------------------------




### TRIAL PIT LOG

Project <b>Twickenham Riverside</b>		Client <b>LB of Richmond Upon Thames</b>		TRIAL PIT No <b>TP101</b>
Job No <b>4955,SI</b>	Date <b>26-08-20</b>	Ground Level (m) <b>8.10</b>	Grid Reference ( )	
Fieldwork By <b>GEL</b>		Logged By <b>PC</b>		Sheet <b>1 of 1</b>

Depth	DESCRIPTION	Legend	Depth	No	Remarks/Tests
0.00-0.10	MADE GROUND (Flexible surfacing)				
0.10-0.30	MADE GROUND (Red brick)				
0.30-1.10	MADE GROUND (Dark brown gravelly clayey fine and medium SAND. Gravel is fine to coarse flint and red brick)				
1.10-1.40	Dark yellowish brown gravelly fine and medium SAND				
1.40-2.20	Yellowish brown gravelly fine and medium SAND. Gravel is fine to coarse subangular to rounded flint				
					Trial pit completed at 2.2m. Infiltration testing undertaken

GEL AGS TP BETA 4955,SI TWICKENHAM RIVERSIDE.GPJ GINT STD AGS 3\_1.GDT 13/11/20



Shoring/Support: None  
 Stability: Stable

All dimensions in metres Scale 1:25	Method Trial Pit/trench	Plant Used MECHANICAL EXCAVATOR	Checked By JD
--	-------------------------	------------------------------------	------------------




Geosphere Environmental Ltd  
 Unit 11 Brightwell Barns  
 Brightwell, Ipswich, IP10 0BJ  
 Telephone: 01603 298 076

### TRIAL PIT LOG

Project <b>Twickenham Riverside</b>		Client <b>LB of Richmond Upon Thames</b>		TRIAL PIT No <b>TP102</b>
Job No <b>4955,SI</b>	Date <b>26-08-20</b>	Ground Level (m) <b>7.20</b>	Grid Reference ( )	
Fieldwork By <b>GEL</b>		Logged By <b>PC</b>		Sheet <b>1 of 1</b>

Depth	DESCRIPTION	Legend	Depth	No	Remarks/Tests
0.00-1.70	MADE GROUND (Dark brown and grey, speckled orange, gravelly clayey SAND (fine to medium). Gravel is fine to coarse angular to subangular flint and brick; rare concrete and brick cobbles)				
1.70-2.30	Dark yellow-ish and orange-brown gravelly fine to medium SAND. Gravel is fine to coarse subangular to rounded flint and chert				
					Trial pit completed at 2.3m. Infiltration testing undertaken

GEL.AGS.TP.BETA.4955.SI.TWICKENHAM.RIVERSIDE.GPJ.GINT.STD.AGS.3.1.GDT.13/11/20



Shoring/Support: None  
 Stability: Stable

All dimensions in metres Scale 1:25	Method Trial Pit/trench	Plant Used MECHANICAL EXCAVATOR	Checked By JD
--	-------------------------	------------------------------------	------------------

---

# Appendix 8 – Infiltration Test Results













---

# Appendix 9 – Gas and Groundwater Monitoring Data

# GROUND GAS AND GROUNDWATER MONITORING DATA



**Project Number:** 4955,SI

**Project Name:** Twickenham Riverside, Diamond Jubilee Gardens, Twickenham

**Date:** 08.12.20



Exploratory Hole Location		BH01 (Shallow install'n)										Date of Installation		26/08/2020	
Return Visit #	Monitoring Date	Atmospheric Pressure (mb)	Methane Content (% v/v) (% LEL)		Carbon Dioxide (% v/v)	Oxygen (% v/v)	Flow Rate (l/hr)	H2S (ppm)	CO (ppm)	VOC (ppm)	Water Level (mbgl)	Base of Well (mbgl)	Weather Conditions	Comments / Pressure Rise or Fall	
1st visit	17/09/2020	1028	<0.1	<2	1.1	19.1	<0.1	0	0	2	5.30	6.30	warm, cloudy, dry, breezy	falling	
2nd visit	02/12/2020	1013	<0.1	<2	2.5	17.1	-0.4	0	0	0	4.96	6.30	Cool, cloudy, overcast, dry, calm	falling	

**Instruments Used:** GFM436 gas analyser / PID MultiRAE lite

**NOTE:** n/a Not applicable

**REMARKS:** Groundwater samples taken using bailer during first visit

nm Not measured



# GROUND GAS AND GROUNDWATER MONITORING DATA



**Project Number:** 4955,SI

**Project Name:** Twickenham Riverside, Diamond Jubilee Gardens, Twickenham

**Date:** 08.12.20



Exploratory Hole Location		BH01 (deep install'n)										Date of Installation		26/08/2020	
Return Visit #	Monitoring Date	Atmospheric Pressure (mb)	Methane Content (% v/v) (% LEL)		Carbon Dioxide (% v/v)	Oxygen (% v/v)	Flow Rate (l/hr)	H2S (ppm)	CO (ppm)	VOC (ppm)	Water Level (mbgl)	Base of Well (mbgl)	Weather Conditions	Comments / Pressure Rise or Fall	
1st visit	17/09/2020	1028	<0.1	<2	0.8	19.1	<0.1	0	0	1	5.05	20.35	warm, cloudy, dry, breezy	falling	
2nd visit	02/12/2020	1013	<0.1	<2	2.0	16.1	-0.4	0	0	2	5.36	20.30	Cool, cloudy, overcast, dry, calm	falling	

**Instruments Used:** GFM436 gas analyser / PID MultiRAE lite

**NOTE:** n/a Not applicable

**REMARKS:** Groundwater samples taken using bailer during first visit

nm Not measured



# GROUND GAS AND GROUNDWATER MONITORING DATA



**Project Number:** 4955,SI

**Project Name:** Twickenham Riverside, Diamond Jubilee Gardens, Twickenham

**Date:** 08.12.20



Exploratory Hole Location		BH02 (Shallow install'n)										Date of Installation		28/08/2020
Return Visit #	Monitoring Date	Atmospheric Pressure (mb)	Methane Content		Carbon Dioxide	Oxygen	Flow Rate (l/hr)	H2S (ppm)	CO (ppm)	VOC (ppm)	Water Level (mbgl)	Base of Well (mbgl)	Weather Conditions	Comments / Pressure Rise or Fall
			(% v/v)	(% LEL)	(% v/v)	(% v/v)								
1st visit	17/09/2020	1030	<0.1	<2	0.6	18.8	<0.1	0	0	0	2.47	4.21	warm, cloudy, dry, breezy	falling
2nd visit	02/12/2020	1015	<0.1	<2	0.6	19.7	<0.1	0	0	0	2.44	4.21	Cool, cloudy, overcast, dry, calm	falling

**Instruments Used:** GFM436 gas analyser / PID MultiRAE lite

**NOTE:** n/a Not applicable

**REMARKS:** Groundwater samples taken using bailer during first visit

nm Not measured



# GROUND GAS AND GROUNDWATER MONITORING DATA



**Project Number:** 4955,SI

**Project Name:** Twickenham Riverside, Diamond Jubilee Gardens, Twickenham

**Date:** 08.12.20



Exploratory Hole Location		BH02 (deep install'n)										Date of Installation		28/08/2020	
Return Visit #	Monitoring Date	Atmospheric Pressure (mb)	Methane Content		Carbon Dioxide	Oxygen	Flow Rate (l/hr)	H2S (ppm)	CO (ppm)	VOC (ppm)	Water Level (mbgl)	Base of Well (mbgl)	Weather Conditions	Comments / Pressure Rise or Fall	
			(% v/v)	(% LEL)	(% v/v)	(% v/v)									
1st visit	17/09/2020	1030	<0.1	<2	0.1	19.3	0.4	0	0	1	12.24	20.72	warm, cloudy, dry, breezy	falling	
2nd visit	02/12/2020	1015	<0.1	<2	0.4	19.7	<0.1	0	0	0	2.76	20.70	Cool, cloudy, overcast, dry, calm	falling	

**Instruments Used:** GFM436 gas analyser / PID MultiRAE lite

**NOTE:** n/a Not applicable

**REMARKS:** Groundwater samples taken using bailer during first visit

nm Not measured





---

# Appendix 10 – Environmental Laboratory Test Results



Jim Dawson  
Geosphere Environmental Ltd  
Brightwell Barns  
Ipswich Road  
Brightwell  
Suffolk  
IP10 0BJ

**DETS Ltd**  
Unit 1  
Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Kent  
ME17 2JN  
t: 01622 850410

## **DETS Report No: 20-10290**

**Site Reference:** Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS

**Project / Job Ref:** 4955, SI

**Order No:** 4955, GI (id)

**Sample Receipt Date:** 02/09/2020

**Sample Scheduled Date:** 08/09/2020

**Report Issue Number:** 1

**Reporting Date:** 16/09/2020

**Authorised by:**

A handwritten signature in black ink, appearing to read "Dave Ashworth".

Dave Ashworth  
Technical Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Soil Analysis Certificate</b>						
<b>DETS Report No: 20-10290</b>	<b>Date Sampled</b>	25/08/20	25/08/20	25/08/20		
<b>Geosphere Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied		
<b>Site Reference: Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS</b>	<b>TP / BH No</b>	HP01 WAC2	WS01A and WS2, J1 Combined	WS01A J2		
<b>Project / Job Ref: 4955, SI</b>	<b>Additional Refs</b>	None Supplied	None Supplied	None Supplied		
<b>Order No: 4955, GI (jd)</b>	<b>Depth (m)</b>	0.25 - 1.20	0.20	0.60		
<b>Reporting Date: 16/09/2020</b>	<b>DETS Sample No</b>	497061	497062	497063		

<b>Determinand</b>	<b>Unit</b>	<b>RL</b>	<b>Accreditation</b>				
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025	Not Detected	Not Detected	Not Detected	
pH	pH Units	N/a	MCERTS	8.1	7.6	8.2	
Total Cyanide	mg/kg	< 2	NONE	< 2	2	< 2	
Complex Cyanide	mg/kg	< 2	NONE	< 2	2	< 2	
Free Cyanide	mg/kg	< 2	NONE	< 2	< 2	< 2	
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS	12	16	15	
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS	0.01	0.02	0.01	
Organic Matter	%	< 0.1	MCERTS	0.9	6	1.8	
Arsenic (As)	mg/kg	< 2	MCERTS	16	11	16	
Barium (Ba)	mg/kg	< 2.5	MCERTS	35	58	63	
Beryllium (Be)	mg/kg	< 0.5	MCERTS	0.6	< 0.5	0.6	
W/S Boron	mg/kg	< 1	NONE	< 1	< 1	< 1	
Cadmium (Cd)	mg/kg	< 0.2	MCERTS	< 0.2	< 0.2	< 0.2	
Chromium (Cr)	mg/kg	< 2	MCERTS	20	15	21	
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2	< 2	< 2	
Copper (Cu)	mg/kg	< 4	MCERTS	15	20	19	
Lead (Pb)	mg/kg	< 3	MCERTS	51	70	72	
Mercury (Hg)	mg/kg	< 1	MCERTS	< 1	< 1	< 1	
Molybdenum (Mo)	mg/kg	< 1	MCERTS	< 1	1	< 1	
Nickel (Ni)	mg/kg	< 3	MCERTS	14	9	15	
Selenium (Se)	mg/kg	< 2	MCERTS	< 3	< 3	< 3	
Vanadium (V)	mg/kg	< 1	MCERTS	42	30	44	
Zinc (Zn)	mg/kg	< 3	MCERTS	45	67	83	

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



**Soil Analysis Certificate - Speciated PAHs**

<b>DETS Report No: 20-10290</b>	<b>Date Sampled</b>	25/08/20	25/08/20	25/08/20	
<b>Geosphere Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied	
<b>Site Reference: Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS</b>	<b>TP / BH No</b>	HP01 WAC2	WS01A and WS2, J1 Combined	WS01A J2	
<b>Project / Job Ref: 4955, SI</b>	<b>Additional Refs</b>	None Supplied	None Supplied	None Supplied	
<b>Order No: 4955, GI (jd)</b>	<b>Depth (m)</b>	0.25 - 1.20	0.20	0.60	
<b>Reporting Date: 16/09/2020</b>	<b>DETS Sample No</b>	497061	497062	497063	

Determinand	Unit	RL	Accreditation				
Naphthalene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Acenaphthylene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Acenaphthene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Fluorene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Phenanthrene	mg/kg	< 0.1	MCERTS	< 0.1	0.27	0.11	
Anthracene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	0.76	0.32	
Pyrene	mg/kg	< 0.1	MCERTS	< 0.1	0.69	0.28	
Benzo(a)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	0.48	0.18	
Chrysene	mg/kg	< 0.1	MCERTS	< 0.1	0.40	0.17	
Benzo(b)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	0.66	0.24	
Benzo(k)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	0.22	< 0.1	
Benzo(a)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	0.50	0.18	
Indeno(1,2,3-cd)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	0.31	0.11	
Dibenz(a,h)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Benzo(ghi)perylene	mg/kg	< 0.1	MCERTS	< 0.1	0.30	0.11	
Total EPA-16 PAHs	mg/kg	< 1.6	MCERTS	< 1.6	4.6	1.7	



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - TPH CWG Banded					
DETS Report No: 20-10290	Date Sampled	25/08/20	25/08/20	25/08/20	
Geosphere Environmental Ltd	Time Sampled	None Supplied	None Supplied	None Supplied	
Site Reference: Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS	TP / BH No	HP01 WAC2	WS01A and WS2, J1 Combined	WS01A J2	
Project / Job Ref: 4955, S1	Additional Refs	None Supplied	None Supplied	None Supplied	
Order No: 4955, GI (jd)	Depth (m)	0.25 - 1.20	0.20	0.60	
Reporting Date: 16/09/2020	DETS Sample No	497061	497062	497063	

Determinand	Unit	RL	Accreditation				
Aliphatic >C5 - C6	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01	
Aliphatic >C6 - C8	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05	
Aliphatic >C8 - C10	mg/kg	< 2	MCERTS	< 2	< 2	< 2	
Aliphatic >C10 - C12	mg/kg	< 2	MCERTS	< 2	< 2	< 2	
Aliphatic >C12 - C16	mg/kg	< 3	MCERTS	< 3	< 3	< 3	
Aliphatic >C16 - C21	mg/kg	< 3	MCERTS	< 3	< 3	< 3	
Aliphatic >C21 - C34	mg/kg	< 10	MCERTS	< 10	< 10	< 10	
Aliphatic (C5 - C34)	mg/kg	< 21	NONE	< 21	< 21	< 21	
Aromatic >C5 - C7	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01	
Aromatic >C7 - C8	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05	
Aromatic >C8 - C10	mg/kg	< 2	MCERTS	< 2	< 2	< 2	
Aromatic >C10 - C12	mg/kg	< 2	MCERTS	< 2	< 2	< 2	
Aromatic >C12 - C16	mg/kg	< 2	MCERTS	< 2	< 2	< 2	
Aromatic >C16 - C21	mg/kg	< 3	MCERTS	< 3	< 3	< 3	
Aromatic >C21 - C35	mg/kg	< 10	MCERTS	< 10	< 10	< 10	
Aromatic (C5 - C35)	mg/kg	< 21	NONE	< 21	< 21	< 21	
Total >C5 - C35	mg/kg	< 42	NONE	< 42	< 42	< 42	



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - BTEX / MTBE					
DETS Report No: 20-10290	Date Sampled	25/08/20	25/08/20	25/08/20	
Geosphere Environmental Ltd	Time Sampled	None Supplied	None Supplied	None Supplied	
Site Reference: Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS	TP / BH No	HP01 WAC2	WS01A and WS2, J1 Combined	WS01A J2	
Project / Job Ref: 4955, SI	Additional Refs	None Supplied	None Supplied	None Supplied	
Order No: 4955, GI (jd)	Depth (m)	0.25 - 1.20	0.20	0.60	
Reporting Date: 16/09/2020	DETS Sample No	497061	497062	497063	

Determinand	Unit	RL	Accreditation				
Benzene	ug/kg	< 2	MCERTS	< 2	< 2	< 2	
Toluene	ug/kg	< 5	MCERTS	< 5	< 5	< 5	
Ethylbenzene	ug/kg	< 2	MCERTS	< 2	< 2	< 2	
p & m-xylene	ug/kg	< 2	MCERTS	< 2	< 2	< 2	
o-xylene	ug/kg	< 2	MCERTS	< 2	< 2	< 2	
MTBE	ug/kg	< 5	MCERTS	< 5	< 5	< 5	



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Waste Acceptance Criteria Analytical Certificate - BS EN 12457/2																																				
DETS Report No: 20-10290		Date Sampled	25/08/20		<table border="1"> <thead> <tr> <th colspan="3">Landfill Waste Acceptance Criteria Limits</th> </tr> <tr> <th>Inert Waste Landfill</th> <th>Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill</th> <th>Hazardous Waste Landfill</th> </tr> </thead> <tbody> <tr> <td>3%</td> <td>5%</td> <td>6%</td> </tr> <tr> <td>--</td> <td>--</td> <td>10%</td> </tr> <tr> <td>6</td> <td>--</td> <td>--</td> </tr> <tr> <td>1</td> <td>--</td> <td>--</td> </tr> <tr> <td>500</td> <td>--</td> <td>--</td> </tr> <tr> <td>100</td> <td>--</td> <td>--</td> </tr> <tr> <td>--</td> <td>&gt;6</td> <td>--</td> </tr> <tr> <td>--</td> <td>To be evaluated</td> <td>To be evaluated</td> </tr> </tbody> </table>		Landfill Waste Acceptance Criteria Limits			Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill	3%	5%	6%	--	--	10%	6	--	--	1	--	--	500	--	--	100	--	--	--	>6	--	--	To be evaluated	To be evaluated
Landfill Waste Acceptance Criteria Limits																																				
Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill																																		
3%	5%	6%																																		
--	--	10%																																		
6	--	--																																		
1	--	--																																		
500	--	--																																		
100	--	--																																		
--	>6	--																																		
--	To be evaluated	To be evaluated																																		
Geosphere Environmental Ltd		Time Sampled	None Supplied																																	
Site Reference: Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS		TP / BH No	HP01 WAC2																																	
Project / Job Ref: 4955, SI		Additional Refs	None Supplied																																	
Order No: 4955, GI (jd)		Depth (m)	0.25 - 1.20																																	
Reporting Date: 16/09/2020		DETS Sample No	497061																																	
Determinand	Unit	MDL																																		
TOC <sup>MU</sup>	%	< 0.1	0.5																																	
Loss on Ignition	%	< 0.01	1.80																																	
BTEX <sup>MU</sup>	mg/kg	< 0.05	< 0.05																																	
Sum of PCBs	mg/kg	< 0.1	< 0.1																																	
Mineral Oil <sup>MU</sup>	mg/kg	< 10	< 10																																	
Total PAH <sup>MU</sup>	mg/kg	< 1.7	< 1.7																																	
pH <sup>MU</sup>	pH Units	N/a	8.1																																	
Acid Neutralisation Capacity	mol/kg (+/-)	< 1	1.1																																	
Eluate Analysis			10:1 mg/l	Cumulative 10:1 mg/kg	Limit values for compliance leaching test using BS EN 12457-3 at L/S 10 l/kg (mg/kg)																															
Arsenic <sup>U</sup>		< 0.01		< 0.1	0.5	2	25																													
Barium <sup>U</sup>		< 0.02		< 0.2	20	100	300																													
Cadmium <sup>U</sup>		< 0.0005		< 0.005	0.04	1	5																													
Chromium <sup>U</sup>		< 0.005		< 0.05	0.5	10	70																													
Copper <sup>U</sup>		< 0.01		< 0.1	2	50	100																													
Mercury <sup>U</sup>		< 0.0005		< 0.005	0.01	0.2	2																													
Molybdenum <sup>U</sup>		0.005		0.05	0.5	10	30																													
Nickel <sup>U</sup>		< 0.007		< 0.07	0.4	10	40																													
Lead <sup>U</sup>		< 0.005		< 0.05	0.5	10	50																													
Antimony <sup>U</sup>		< 0.005		< 0.05	0.06	0.7	5																													
Selenium <sup>U</sup>		< 0.005		< 0.05	0.1	0.5	7																													
Zinc <sup>U</sup>		< 0.005		< 0.05	4	50	200																													
Chloride <sup>U</sup>		2.1		21	800	15000	25000																													
Fluoride <sup>U</sup>		< 0.5		< 5	10	150	500																													
Sulphate <sup>U</sup>		1.7		17	1000	20000	50000																													
TDS		51		510	4000	60000	100000																													
Phenol Index		< 0.01		< 0.1	1	-	-																													
DOC		8.4		83.6	500	800	1000																													
Leach Test Information																																				
Sample Mass (kg)		0.09																																		
Dry Matter (%)		96.4																																		
Moisture (%)		3.8																																		
Stage 1																																				
Volume Eluate L10 (litres)		0.90																																		

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion  
 Stated limits are for guidance only and DETS Ltd cannot be held responsible for any discrepancies with current legislation  
 M Denotes MCERTS accredited test  
 U Denotes ISO17025 accredited test







DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions	
DETS Report No: 20-10290	
Geosphere Environmental Ltd	
Site Reference: Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS	
Project / Job Ref: 4955, SI	
Order No: 4955, GI (jd)	
Reporting Date: 16/09/2020	

DETS Sample No	TP / BH No	Additional Refs	Depth (m)	Moisture Content (%)	Sample Matrix Description
\$ 497061	HP01 WAC2	None Supplied	0.25 - 1.20	3.7	Light brown sandy clay with stones
\$ 497062	WS01A and WS2, J1 Combined	None Supplied	0.20	7.4	Black loamy sand with stones and vegetation
\$ 497063	WS01A J2	None Supplied	0.60	3.1	Brown sandy clay with stones and concrete

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample <sup>1/5</sup>

Unsuitable Sample <sup>1/5</sup>

\$ samples exceeded recommended holding times



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



<b>Soil Analysis Certificate - Methodology &amp; Miscellaneous Information</b>
<b>DETS Report No: 20-10290</b>
<b>Geosphere Environmental Ltd</b>
<b>Site Reference: Diamond Jubilee Gardens and Twickenham Riverside, Wharf Lane, TW1 4QS</b>
<b>Project / Job Ref: 4955, SI</b>
<b>Order No: 4955, GI (jd)</b>
<b>Reporting Date: 16/09/2020</b>

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphenylcarbazide followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 - C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCs	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

D Dried  
 AR As Received

Parameter	Matrix Type	Suite Reference	Expanded Uncertainty Measurement	Unit
TOC	Soil	BS EN 12457	13.49	%
Loss on Ignition	Soil	BS EN 12457	17	%
BTEX	Soil	BS EN 12457	14	%
Sum of PCBs	Soil	BS EN 12457	23	%
Mineral Oil	Soil	BS EN 12457	9	%
Total PAH	Soil	BS EN 12457	20	%
pH	Soil	BS EN 12457	0.399	Units
Acid Neutralisation Capacity	Soil	BS EN 12457	18	%
Arsenic	Leachate	BS EN 12457	16.63	%
Barium	Leachate	BS EN 12457	14.29	%
Cadmium	Leachate	BS EN 12457	14.44	%
Chromium	Leachate	BS EN 12457	18.06	%
Copper	Leachate	BS EN 12457	21.27	%
Mercury	Leachate	BS EN 12457	24.13	%
Molybdenum	Leachate	BS EN 12457	12.55	%
Nickel	Leachate	BS EN 12457	20.08	%
Lead	Leachate	BS EN 12457	13.43	%
Antimony	Leachate	BS EN 12457	18.85	%
Selenium	Leachate	BS EN 12457	18.91	%
Zinc	Leachate	BS EN 12457	13.71	%
Chloride	Leachate	BS EN 12457	16	%
Fluoride	Leachate	BS EN 12457	19.4	%
Sulphate	Leachate	BS EN 12457	19.63	%
TDS	Leachate	BS EN 12457	12	%
Phenol Index	Leachate	BS EN 12457	14	%
DOC	Leachate	BS EN 12457	10	%
Clay Content	Soil	BS 3882: 2015	15	%
Silt Content	Soil	BS 3882: 2015	14	%
Sand Content	Soil	BS 3882: 2015	13	%
Loss on Ignition	Soil	BS 3882: 2015	17	%
pH	Soil	BS 3882: 2015	0.399	Units
Carbonate	Soil	BS 3882: 2015	16	%
Total Nitrogen	Soil	BS 3882: 2015	12	%
Phosphorus (Extractable)	Soil	BS 3882: 2015	24	%
Potassium (Extractable)	Soil	BS 3882: 2015	20	%
Magnesium (Extractable)	Soil	BS 3882: 2015	26	%
Zinc	Soil	BS 3882: 2015	14.9	%
Copper	Soil	BS 3882: 2015	16	%
Nickel	Soil	BS 3882: 2015	17.7	%
Available Sodium	Soil	BS 3882: 2015	23	%
Available Calcium	Soil	BS 3882: 2015	23	%
Electrical Conductivity	Soil	BS 3882: 2015	10	%



Jim Dawson  
Geosphere Environmental Ltd  
Brightwell Barns  
Ipswich Road  
Brightwell  
Suffolk  
IP10 0BJ

**DETS Ltd**  
Unit 1  
Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Kent  
ME17 2JN  
t: 01622 850410

## **DETS Report No: 20-10989**

**Site Reference:** Twickenham Riverside

**Project / Job Ref:** 4955,SI

**Order No:** 4955,SI (JD)

**Sample Receipt Date:** 22/09/2020

**Sample Scheduled Date:** 22/09/2020

**Report Issue Number:** 1

**Reporting Date:** 02/10/2020

**Authorised by:**

Kevin Old  
General Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate						
DETS Report No: 20-10989	Date Sampled	25/08/20	25/08/20	25/08/20	25/08/20	27/08/20
Geosphere Environmental Ltd	Time Sampled	None Supplied				
Site Reference: Twickenham Riverside	TP / BH No	BH1	BH1	BH1	BH1	BH2
Project / Job Ref: 4955,SI	Additional Refs	Disturbed	Disturbed	Disturbed	Disturbed	Disturbed
Order No: 4955,SI (JD)	Depth (m)	4.00	10.50	18.00	24.00	2.00
Reporting Date: 02/10/2020	DETS Sample No	500425	500426	500427	500428	500429

Determinand	Unit	RL	Accreditation					
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025					
pH	pH Units	N/a	MCERTS	8.4	8.1	8.8	8.2	8.6
Total Cyanide	mg/kg	< 2	NONE					
Complex Cyanide	mg/kg	< 2	NONE					
Free Cyanide	mg/kg	< 2	NONE					
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS	< 10	604	218	440	321
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS	< 0.01	0.60	0.22	0.44	0.32
Organic Matter	%	< 0.1	MCERTS					
Arsenic (As)	mg/kg	< 2	MCERTS					
Barium (Ba)	mg/kg	< 2.5	MCERTS					
Beryllium (Be)	mg/kg	< 0.5	MCERTS					
W/S Boron	mg/kg	< 1	NONE					
Cadmium (Cd)	mg/kg	< 0.2	MCERTS					
Chromium (Cr)	mg/kg	< 2	MCERTS					
Chromium (hexavalent)	mg/kg	< 2	NONE					
Copper (Cu)	mg/kg	< 4	MCERTS					
Lead (Pb)	mg/kg	< 3	MCERTS					
Mercury (Hg)	mg/kg	< 1	MCERTS					
Molybdenum (Mo)	mg/kg	< 1	MCERTS					
Nickel (Ni)	mg/kg	< 3	MCERTS					
Selenium (Se)	mg/kg	< 2	MCERTS					
Vanadium (V)	mg/kg	< 1	MCERTS					
Zinc (Zn)	mg/kg	< 3	MCERTS					
EPH (C10 - C40)	mg/kg	< 6	MCERTS					

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate						
DETS Report No: 20-10989	Date Sampled	27/08/20	27/08/20	27/08/20	27/08/20	27/08/20
Geosphere Environmental Ltd	Time Sampled	None Supplied				
Site Reference: Twickenham Riverside	TP / BH No	BH2	BH2	BH2	BH1 + BH2	BH01A + BH01B
Project / Job Ref: 4955,SI	Additional Refs	Disturbed	Disturbed	Disturbed	Composite	Composite
Order No: 4955,SI (JD)	Depth (m)	7.50	13.50	19.50	2.0 - 24.0	0.20 - 0.80
Reporting Date: 02/10/2020	DETS Sample No	500430	500431	500432	500433	500434

Determinand	Unit	RL	Accreditation					
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025				Not Detected	Not Detected
pH	pH Units	N/a	MCERTS	8.1	8.4	8.8	8.1	8.3
Total Cyanide	mg/kg	< 2	NONE				< 2	< 2
Complex Cyanide	mg/kg	< 2	NONE				< 2	< 2
Free Cyanide	mg/kg	< 2	NONE				< 2	< 2
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS	485	319	460	365	79
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS	0.48	0.32	0.46	0.36	0.08
Organic Matter	%	< 0.1	MCERTS				0.9	0.8
Arsenic (As)	mg/kg	< 2	MCERTS				9	15
Barium (Ba)	mg/kg	< 2.5	MCERTS				50	71
Beryllium (Be)	mg/kg	< 0.5	MCERTS				0.9	0.7
W/S Boron	mg/kg	< 1	NONE				2.3	< 1
Cadmium (Cd)	mg/kg	< 0.2	MCERTS				< 0.2	< 0.2
Chromium (Cr)	mg/kg	< 2	MCERTS				31	19
Chromium (hexavalent)	mg/kg	< 2	NONE				< 2	< 2
Copper (Cu)	mg/kg	< 4	MCERTS				19	20
Lead (Pb)	mg/kg	< 3	MCERTS				10	207
Mercury (Hg)	mg/kg	< 1	MCERTS				< 1	< 1
Molybdenum (Mo)	mg/kg	< 1	MCERTS				< 1	< 1
Nickel (Ni)	mg/kg	< 3	MCERTS				29	16
Selenium (Se)	mg/kg	< 2	MCERTS				< 3	< 3
Vanadium (V)	mg/kg	< 1	MCERTS				54	38
Zinc (Zn)	mg/kg	< 3	MCERTS				78	68
EPH (C10 - C40)	mg/kg	< 6	MCERTS					< 6

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate					
DETS Report No: 20-10989	Date Sampled	27/08/20			
Geosphere Environmental Ltd	Time Sampled	None Supplied			
Site Reference: Twickenham Riverside	TP / BH No	BH2			
Project / Job Ref: 4955,SI	Additional Refs	Disturbed			
Order No: 4955,SI (JD)	Depth (m)	1.20			
Reporting Date: 02/10/2020	DETS Sample No	500435			

Determinand	Unit	RL	Accreditation				
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025	Not Detected			
pH	pH Units	N/a	MCERTS	8.3			
Total Cyanide	mg/kg	< 2	NONE	< 2			
Complex Cyanide	mg/kg	< 2	NONE	< 2			
Free Cyanide	mg/kg	< 2	NONE	< 2			
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS	44			
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS	0.04			
Organic Matter	%	< 0.1	MCERTS	1			
Arsenic (As)	mg/kg	< 2	MCERTS	15			
Barium (Ba)	mg/kg	< 2.5	MCERTS	55			
Beryllium (Be)	mg/kg	< 0.5	MCERTS	0.6			
W/S Boron	mg/kg	< 1	NONE	< 1			
Cadmium (Cd)	mg/kg	< 0.2	MCERTS	< 0.2			
Chromium (Cr)	mg/kg	< 2	MCERTS	16			
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2			
Copper (Cu)	mg/kg	< 4	MCERTS	17			
Lead (Pb)	mg/kg	< 3	MCERTS	111			
Mercury (Hg)	mg/kg	< 1	MCERTS	< 1			
Molybdenum (Mo)	mg/kg	< 1	MCERTS	< 1			
Nickel (Ni)	mg/kg	< 3	MCERTS	13			
Selenium (Se)	mg/kg	< 2	MCERTS	< 3			
Vanadium (V)	mg/kg	< 1	MCERTS	36			
Zinc (Zn)	mg/kg	< 3	MCERTS	38			
EPH (C10 - C40)	mg/kg	< 6	MCERTS	< 6			

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



Soil Analysis Certificate - Speciated PAHs						
<b>DETS Report No: 20-10989</b>	<b>Date Sampled</b>	27/08/20	27/08/20	27/08/20		
<b>Geosphere Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied		
<b>Site Reference: Twickenham Riverside</b>	<b>TP / BH No</b>	BH1 + BH2	BH01A + BH01B	BH2		
<b>Project / Job Ref: 4955,SI</b>	<b>Additional Refs</b>	Composite	Composite	Disturbed		
<b>Order No: 4955,SI (JD)</b>	<b>Depth (m)</b>	2.0 - 24.0	0.20 - 0.80	1.20		
<b>Reporting Date: 02/10/2020</b>	<b>DETS Sample No</b>	500433	500434	500435		

Determinand	Unit	RL	Accreditation				
Naphthalene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Acenaphthylene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Acenaphthene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Fluorene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Phenanthrene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Anthracene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	0.17	< 0.1	
Pyrene	mg/kg	< 0.1	MCERTS	< 0.1	0.12	< 0.1	
Benzo(a)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	0.30	< 0.1	
Chrysene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Benzo(b)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	0.52	< 0.1	
Benzo(k)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	0.13	< 0.1	
Benzo(a)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	0.28	< 0.1	
Indeno(1,2,3-cd)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	0.38	< 0.1	
Dibenz(a,h)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	< 0.1	< 0.1	
Benzo(ghi)perylene	mg/kg	< 0.1	MCERTS	< 0.1	0.21	< 0.1	
Total EPA-16 PAHs	mg/kg	< 1.6	MCERTS	< 1.6	2.1	< 1.6	



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



**Soil Analysis Certificate - TPH CWG Banded**

<b>DETS Report No: 20-10989</b>	<b>Date Sampled</b>	27/08/20				
<b>Geosphere Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied				
<b>Site Reference: Twickenham Riverside</b>	<b>TP / BH No</b>	BH1 + BH2				
<b>Project / Job Ref: 4955,SI</b>	<b>Additional Refs</b>	Composite				
<b>Order No: 4955,SI (JD)</b>	<b>Depth (m)</b>	2.0 - 24.0				
<b>Reporting Date: 02/10/2020</b>	<b>DETS Sample No</b>	500433				

Determinand	Unit	RL	Accreditation				
Aliphatic >C5 - C6	mg/kg	< 0.01	NONE	< 0.01			
Aliphatic >C6 - C8	mg/kg	< 0.05	NONE	< 0.05			
Aliphatic >C8 - C10	mg/kg	< 2	MCERTS	7			
Aliphatic >C10 - C12	mg/kg	< 2	MCERTS	14			
Aliphatic >C12 - C16	mg/kg	< 3	MCERTS	15			
Aliphatic >C16 - C21	mg/kg	< 3	MCERTS	< 3			
Aliphatic >C21 - C34	mg/kg	< 10	MCERTS	< 10			
Aliphatic (C5 - C34)	mg/kg	< 21	NONE	36			
Aromatic >C5 - C7	mg/kg	< 0.01	NONE	< 0.01			
Aromatic >C7 - C8	mg/kg	< 0.05	NONE	< 0.05			
Aromatic >C8 - C10	mg/kg	< 2	MCERTS	< 2			
Aromatic >C10 - C12	mg/kg	< 2	MCERTS	< 2			
Aromatic >C12 - C16	mg/kg	< 2	MCERTS	< 2			
Aromatic >C16 - C21	mg/kg	< 3	MCERTS	< 3			
Aromatic >C21 - C35	mg/kg	< 10	MCERTS	< 10			
Aromatic (C5 - C35)	mg/kg	< 21	NONE	< 21			
Total >C5 - C35	mg/kg	< 42	NONE	< 42			



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - BTEX / MTBE						
DETS Report No: 20-10989	Date Sampled	27/08/20				
Geosphere Environmental Ltd	Time Sampled	None Supplied				
Site Reference: Twickenham Riverside	TP / BH No	BH1 + BH2				
Project / Job Ref: 4955,SI	Additional Refs	Composite				
Order No: 4955,SI (JD)	Depth (m)	2.0 - 24.0				
Reporting Date: 02/10/2020	DETS Sample No	500433				

Determinand	Unit	RL	Accreditation				
Benzene	ug/kg	< 2	MCERTS	< 2			
Toluene	ug/kg	< 5	MCERTS	< 5			
Ethylbenzene	ug/kg	< 2	MCERTS	< 2			
p & m-xylene	ug/kg	< 2	MCERTS	4			
o-xylene	ug/kg	< 2	MCERTS	3			
MTBE	ug/kg	< 5	MCERTS	< 5			

<b>Waste Acceptance Criteria Analytical Certificate - BS EN 12457/2</b>									
<b>DETS Report No: 20-10989</b>		<b>Date Sampled</b>		27/08/20		<b>Landfill Waste Acceptance Criteria Limits</b>			
<b>Geosphere Environmental Ltd</b>		<b>Time Sampled</b>		None Supplied					
<b>Site Reference: Twickenham Riverside</b>		<b>TP / BH No</b>		BH1 + BH2					
<b>Project / Job Ref: 4955,SI</b>		<b>Additional Refs</b>		Composite					
<b>Order No: 4955,SI (JD)</b>		<b>Depth (m)</b>		2.0 - 24.0					
<b>Reporting Date: 02/10/2020</b>		<b>DETS Sample No</b>		500433					
<b>Determinand</b>		<b>Unit</b>		<b>MDL</b>					
TOC <sup>MU</sup>		%		< 0.1    0.5					
Loss on Ignition		%		< 0.01    0.60					
BTEX <sup>MU</sup>		mg/kg		< 0.05    < 0.05					
Sum of PCBs		mg/kg		< 0.1    < 0.1					
Mineral Oil <sup>MU</sup>		mg/kg		< 10    31					
Total PAH <sup>MU</sup>		mg/kg		< 1.7    < 1.7					
pH <sup>MU</sup>		pH Units		N/a    8.1					
Acid Neutralisation Capacity		mol/kg (+/-)		< 1    < 1					
<b>Eluate Analysis</b>				<b>10:1 mg/l</b>		<b>Cumulative 10:1 mg/kg</b>		<b>Limit values for compliance leaching test using BS EN 12457-3 at L/S 10 l/kg (mg/kg)</b>	
Arsenic <sup>U</sup>				< 0.01		< 0.1		0.5    2    25	
Barium <sup>U</sup>				< 0.02		< 0.2		20    100    300	
Cadmium <sup>U</sup>				< 0.0005		< 0.005		0.04    1    5	
Chromium <sup>U</sup>				< 0.005		< 0.05		0.5    10    70	
Copper <sup>U</sup>				0.01		0.1		2    50    100	
Mercury <sup>U</sup>				< 0.0005		< 0.005		0.01    0.2    2	
Molybdenum <sup>U</sup>				0.002		0.02		0.5    10    30	
Nickel <sup>U</sup>				< 0.007		< 0.07		0.4    10    40	
Lead <sup>U</sup>				< 0.005		< 0.05		0.5    10    50	
Antimony <sup>U</sup>				< 0.005		< 0.05		0.06    0.7    5	
Selenium <sup>U</sup>				0.023		0.23		<b>0.1</b> 0.5    7	
Zinc <sup>U</sup>				< 0.005		< 0.05		4    50    200	
Chloride <sup>U</sup>				4.0		40		800    15000    25000	
Fluoride <sup>U</sup>				< 0.5		< 5		10    150    500	
Sulphate <sup>U</sup>				47.7		477		1000    20000    50000	
TDS				123		1230		4000    60000    100000	
Phenol Index				< 0.01		< 0.1		1    -    -	
DOC				4.4		43.7		500    800    1000	
<b>Leach Test Information</b>									
Sample Mass (kg)				0.10					
Dry Matter (%)				87.5					
Moisture (%)				14.2					
<b>Stage 1</b>									
Volume Eluate L10 (litres)				0.89					
Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion									
Stated limits are for guidance only and DETS Ltd cannot be held responsible for any discrepancies with current legislation									
M Denotes MCERTS accredited test									
U Denotes ISO17025 accredited test									



**DETS Ltd**  
 : 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Waste Acceptance Criteria Analytical Certificate - BS EN 12457/2																																							
<b>DETS Report No: 20-10989</b>		<b>Date Sampled</b>	27/08/20		<table border="1"> <thead> <tr> <th colspan="3">Landfill Waste Acceptance Criteria Limits</th> </tr> <tr> <th>Inert Waste Landfill</th> <th>Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill</th> <th>Hazardous Waste Landfill</th> </tr> </thead> <tbody> <tr> <td>3%</td> <td>5%</td> <td>6%</td> </tr> <tr> <td>--</td> <td>--</td> <td>10%</td> </tr> <tr> <td>6</td> <td>--</td> <td>--</td> </tr> <tr> <td>1</td> <td>--</td> <td>--</td> </tr> <tr> <td>500</td> <td>--</td> <td>--</td> </tr> <tr> <td>100</td> <td>--</td> <td>--</td> </tr> <tr> <td>--</td> <td>&gt;6</td> <td>--</td> </tr> <tr> <td>--</td> <td>To be evaluated</td> <td>To be evaluated</td> </tr> </tbody> </table>					Landfill Waste Acceptance Criteria Limits			Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill	3%	5%	6%	--	--	10%	6	--	--	1	--	--	500	--	--	100	--	--	--	>6	--	--	To be evaluated	To be evaluated
Landfill Waste Acceptance Criteria Limits																																							
Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill																																					
3%	5%	6%																																					
--	--	10%																																					
6	--	--																																					
1	--	--																																					
500	--	--																																					
100	--	--																																					
--	>6	--																																					
--	To be evaluated	To be evaluated																																					
<b>Geosphere Environmental Ltd</b>		<b>Time Sampled</b>	None Supplied																																				
<b>Site Reference: Twickenham Riverside</b>		<b>TP / BH No</b>	BH01A + BH01B																																				
<b>Project / Job Ref: 4955,SI</b>		<b>Additional Refs</b>	Composite																																				
<b>Order No: 4955,SI (JD)</b>		<b>Depth (m)</b>	0.20 - 0.80																																				
<b>Reporting Date: 02/10/2020</b>		<b>DETS Sample No</b>	500434																																				
<b>Determinand</b>	<b>Unit</b>	<b>MDL</b>																																					
TOC <sup>MU</sup>	%	< 0.1	0.5																																				
Loss on Ignition	%	< 0.01	1.90																																				
BTEX <sup>MU</sup>	mg/kg	< 0.05	< 0.05																																				
Sum of PCBs	mg/kg	< 0.1	< 0.1																																				
Mineral Oil <sup>MU</sup>	mg/kg	< 10	< 10																																				
Total PAH <sup>MU</sup>	mg/kg	< 1.7	2.1																																				
pH <sup>MU</sup>	pH Units	N/a	8.3																																				
Acid Neutralisation Capacity	mol/kg (+/-)	< 1	< 1																																				
<b>Eluate Analysis</b>			<b>10:1 mg/l</b>			<b>Cumulative 10:1 mg/kg</b>	<b>Limit values for compliance leaching test using BS EN 12457-3 at L/S 10 l/kg (mg/kg)</b>																																
Arsenic <sup>U</sup>		< 0.01				< 0.1	0.5	2	25																														
Barium <sup>U</sup>		< 0.02				< 0.2	20	100	300																														
Cadmium <sup>U</sup>		< 0.0005				< 0.005	0.04	1	5																														
Chromium <sup>U</sup>		< 0.005				< 0.05	0.5	10	70																														
Copper <sup>U</sup>		0.01				0.1	2	50	100																														
Mercury <sup>U</sup>		< 0.0005				< 0.005	0.01	0.2	2																														
Molybdenum <sup>U</sup>		0.003				0.03	0.5	10	30																														
Nickel <sup>U</sup>		< 0.007				< 0.07	0.4	10	40																														
Lead <sup>U</sup>		< 0.005				< 0.05	0.5	10	50																														
Antimony <sup>U</sup>		< 0.005				< 0.05	0.06	0.7	5																														
Selenium <sup>U</sup>		< 0.005				< 0.05	0.1	0.5	7																														
Zinc <sup>U</sup>		< 0.005				< 0.05	4	50	200																														
Chloride <sup>U</sup>		5.4				54	800	15000	25000																														
Fluoride <sup>U</sup>		< 0.5				< 5	10	150	500																														
Sulphate <sup>U</sup>		13.4				134	1000	20000	50000																														
TDS		104				1040	4000	60000	100000																														
Phenol Index		< 0.01				< 0.1	1	-	-																														
DOC		6				59.5	500	800	1000																														
<b>Leach Test Information</b>																																							
Sample Mass (kg)		0.10																																					
Dry Matter (%)		94.4																																					
Moisture (%)		6																																					
<b>Stage 1</b>																																							
Volume Eluate L10 (litres)		0.90																																					
Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion																																							
Stated limits are for guidance only and DETS Ltd cannot be held responsible for any discrepancies with current legislation																																							
M Denotes MCERTS accredited test																																							
U Denotes ISO17025 accredited test																																							



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions	
DETS Report No: 20-10989	
Geosphere Environmental Ltd	
Site Reference: Twickenham Riverside	
Project / Job Ref: 4955,SI	
Order No: 4955,SI (JD)	
Reporting Date: 02/10/2020	

DETS Sample No	TP / BH No	Additional Refs	Depth (m)	Moisture Content (%)	Sample Matrix Description
\$ 500425	BH1	Disturbed	4.00	10.4	Light brown sand with stones
\$ 500426	BH1	Disturbed	10.50	16.3	Brown clay
\$ 500427	BH1	Disturbed	18.00	15.3	Brown clay
\$ 500428	BH1	Disturbed	24.00	9.5	Brown clay
\$ 500429	BH2	Disturbed	2.00	10.9	Brown sandy clay
\$ 500430	BH2	Disturbed	7.50	13.7	Brown sandy clay
\$ 500431	BH2	Disturbed	13.50	11.3	Brown clay
\$ 500432	BH2	Disturbed	19.50	14.8	Brown sandy clay
\$ 500433	BH1 + BH2	Composite	2.0 - 24.0	12.5	Brown sandy clay
\$ 500434	BH01A + BH01B	Composite	0.20 - 0.80	5.6	Brown sandy gravel with stones
\$ 500435	BH2	Disturbed	1.20	12.8	Brown sandy clay with stones and concrete

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample <sup>1/5</sup>

& samples received in inappropriate containers for hydrocarbon analysis

\$ samples exceeded recommended holding times



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Soil Analysis Certificate - Methodology &amp; Miscellaneous Information</b>	
<b>DETS Report No: 20-10989</b>	
<b>Geosphere Environmental Ltd</b>	
<b>Site Reference: Twickenham Riverside</b>	
<b>Project / Job Ref: 4955,SI</b>	
<b>Order No: 4955,SI (JD)</b>	
<b>Reporting Date: 02/10/2020</b>	

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphénylcarbazine followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 - C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCs	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

**D Dried**  
**AR As Received**

Parameter	Matrix Type	Suite Reference	Expanded Uncertainty Measurement	Unit
TOC	Soil	BS EN 12457	13.49	%
Loss on Ignition	Soil	BS EN 12457	17	%
BTEX	Soil	BS EN 12457	14	%
Sum of PCBs	Soil	BS EN 12457	23	%
Mineral Oil	Soil	BS EN 12457	9	%
Total PAH	Soil	BS EN 12457	20	%
pH	Soil	BS EN 12457	0.399	Units
Acid Neutralisation Capacity	Soil	BS EN 12457	18	%
Arsenic	Leachate	BS EN 12457	16.63	%
Barium	Leachate	BS EN 12457	14.29	%
Cadmium	Leachate	BS EN 12457	14.44	%
Chromium	Leachate	BS EN 12457	18.06	%
Copper	Leachate	BS EN 12457	21.27	%
Mercury	Leachate	BS EN 12457	24.13	%
Molybdenum	Leachate	BS EN 12457	12.55	%
Nickel	Leachate	BS EN 12457	20.08	%
Lead	Leachate	BS EN 12457	13.43	%
Antimony	Leachate	BS EN 12457	18.85	%
Selenium	Leachate	BS EN 12457	18.91	%
Zinc	Leachate	BS EN 12457	13.71	%
Chloride	Leachate	BS EN 12457	16	%
Fluoride	Leachate	BS EN 12457	19.4	%
Sulphate	Leachate	BS EN 12457	19.63	%
TDS	Leachate	BS EN 12457	12	%
Phenol Index	Leachate	BS EN 12457	14	%
DOC	Leachate	BS EN 12457	10	%
Clay Content	Soil	BS 3882: 2015	15	%
Silt Content	Soil	BS 3882: 2015	14	%
Sand Content	Soil	BS 3882: 2015	13	%
Loss on Ignition	Soil	BS 3882: 2015	17	%
pH	Soil	BS 3882: 2015	0.399	Units
Carbonate	Soil	BS 3882: 2015	16	%
Total Nitrogen	Soil	BS 3882: 2015	12	%
Phosphorus (Extractable)	Soil	BS 3882: 2015	24	%
Potassium (Extractable)	Soil	BS 3882: 2015	20	%
Magnesium (Extractable)	Soil	BS 3882: 2015	26	%
Zinc	Soil	BS 3882: 2015	14.9	%
Copper	Soil	BS 3882: 2015	16	%
Nickel	Soil	BS 3882: 2015	17.7	%
Available Sodium	Soil	BS 3882: 2015	23	%
Available Calcium	Soil	BS 3882: 2015	23	%
Electrical Conductivity	Soil	BS 3882: 2015	10	%



4041

**Jim Dawson**

Geosphere Environmental Ltd  
Unit 11 Brightwell Barns  
Ipswich Road  
Brightwell  
Suffolk  
IP10 0BJ



i2 Analytical Ltd.  
7 Woodshots Meadow,  
Croxley Green  
Business Park,  
Watford,  
Herts,  
WD18 8YS

**t:** 01923 225404

**f:** 01923 237404

**e:** reception@i2analytical.com

**e:** jim@geosphere-environmental.co.uk

## Analytical Report Number : 20-30535

<b>Project / Site name:</b>	Twickenham Riverside - Diamond Jubilee Gardens, Twickenham	<b>Samples received on:</b>	17/09/2020
<b>Your job number:</b>	4955,SI	<b>Samples instructed on/ Analysis started on:</b>	18/09/2020
<b>Your order number:</b>	5218.CO V1-JD	<b>Analysis completed by:</b>	24/09/2020
<b>Report Issue Number:</b>	1	<b>Report issued on:</b>	24/09/2020
<b>Samples Analysed:</b>	4 water samples		

**Signed:** *Karolina Marek*

Karolina Marek  
PL Head of Reporting Team  
**For & on behalf of i2 Analytical Ltd.**

Standard Geotechnical, Asbestos and Chemical Testing Laboratory located at: ul. Pionierów 39, 41 -711 Ruda Śląska, Poland.

Accredited tests are defined within the report, opinions and interpretations expressed herein are outside the scope of accreditation.

Standard sample disposal times, unless otherwise agreed with the laboratory, are :	soils	- 4 weeks from reporting
	leachates	- 2 weeks from reporting
	waters	- 2 weeks from reporting
	asbestos	- 6 months from reporting

Excel copies of reports are only valid when accompanied by this PDF certificate.

Any assessments of compliance with specifications are based on actual analytical results with no contribution from uncertainty of measurement. Application of uncertainty of measurement would provide a range within which the true result lies. An estimate of measurement uncertainty can be provided on request.



Analytical Report Number: 20-30535

Project / Site name: Twickenham Riverside - Diamond Jubilee Gardens, Twickenham

Your Order No: 5218.CO V1-JD

Lab Sample Number	1622471			1622472			1622473			1622474		
Sample Reference	BH01 (shallow)			BH01 (deep)			BH02 (shallow)			BH02 (deep)		
Sample Number	None Supplied			None Supplied			None Supplied			None Supplied		
Depth (m)	5.50			6.00			2.50			12.50		
Date Sampled	17/09/2020			17/09/2020			17/09/2020			17/09/2020		
Time Taken	1225			1225			1225			1225		
Analytical Parameter (Water Analysis)	Units	Limit of detection	Accreditation Status									

#### General Inorganics

Parameter	Units	Limit	ISO 17025	1622471	1622472	1622473	1622474
pH	pH Units	N/A	ISO 17025	7.4	-	7.2	7.9
Temperature on Receipt	°C	0.1	NONE	9.1	9.1	9.1	9.1
Total Cyanide (Low Level 1 µg/l)	µg/l	1	ISO 17025	< 1.0	-	< 1.0	< 1.0
Free Cyanide (Low Level 1 µg/l)	µg/l	1	ISO 17025	< 1	-	< 1	< 1
Chloride	mg/l	0.15	ISO 17025	39	36	50	300

Dissolved Oxygen	mg/l	1	NONE	2.7	4.1	1.8	2.4
------------------	------	---	------	-----	-----	-----	-----

#### Total Phenols

Total Phenols (monohydric)	µg/l	10	ISO 17025	< 10	-	< 10	< 10
----------------------------	------	----	-----------	------	---	------	------

#### Speciated PAHs

Parameter	Units	Limit	ISO 17025	1622471	1622472	1622473	1622474
Naphthalene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Acenaphthylene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Acenaphthene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Fluorene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Phenanthrene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Anthracene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Fluoranthene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Pyrene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Benzo(a)anthracene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Chrysene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Benzo(b)fluoranthene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Benzo(k)fluoranthene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Benzo(a)pyrene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Indeno(1,2,3-cd)pyrene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Dibenz(a,h)anthracene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01
Benzo(ghi)perylene	µg/l	0.01	ISO 17025	< 0.01	-	< 0.01	< 0.01

#### Total PAH

Total EPA-16 PAHs	µg/l	0.16	ISO 17025	< 0.16	-	< 0.16	< 0.16
-------------------	------	------	-----------	--------	---	--------	--------

#### Heavy Metals / Metalloids

Boron (dissolved)	µg/l	10	ISO 17025	240	-	140	1100
Chromium (hexavalent)	µg/l	5	ISO 17025	< 5.0	-	< 5.0	< 5.0

Arsenic (dissolved)	µg/l	0.15	ISO 17025	< 0.15	-	0.37	2.82
Barium (dissolved)	µg/l	0.06	ISO 17025	44	-	72	72
Beryllium (dissolved)	µg/l	0.1	ISO 17025	< 0.1	-	< 0.1	< 0.1
Cadmium (dissolved)	µg/l	0.02	ISO 17025	0.03	-	0.03	0.03
Chromium (dissolved)	µg/l	0.2	ISO 17025	5.3	-	9.9	3
Copper (dissolved)	µg/l	0.5	ISO 17025	0.6	-	3.5	2.2
Lead (dissolved)	µg/l	0.2	ISO 17025	< 0.2	-	0.3	< 0.2
Mercury (dissolved)	µg/l	0.05	ISO 17025	< 0.05	-	< 0.05	< 0.05
Molybdenum (dissolved)	µg/l	0.05	ISO 17025	2.4	-	3.9	7.5
Nickel (dissolved)	µg/l	0.5	ISO 17025	7.8	-	6	4.2
Selenium (dissolved)	µg/l	0.6	ISO 17025	4.5	-	8.4	22
Vanadium (dissolved)	µg/l	0.2	ISO 17025	< 0.2	-	< 0.2	3.8
Zinc (dissolved)	µg/l	0.5	ISO 17025	6.2	-	6.8	8



Analytical Report Number: 20-30535

Project / Site name: Twickenham Riverside - Diamond Jubilee Gardens, Twickenham

Your Order No: 5218.CO V1-JD

Lab Sample Number				1622471	1622472	1622473	1622474
Sample Reference				BH01 (shallow)	BH01 (deep)	BH02 (shallow)	BH02 (deep)
Sample Number				None Supplied	None Supplied	None Supplied	None Supplied
Depth (m)				5.50	6.00	2.50	12.50
Date Sampled				17/09/2020	17/09/2020	17/09/2020	17/09/2020
Time Taken				1225	1225	1225	1225
Analytical Parameter (Water Analysis)	Units	Limit of detection	Accreditation Status				
<b>Petroleum Hydrocarbons</b>							
TPH1 (C10 - C40)	µg/l	10	NONE	< 10	-	< 10	< 10

U/S = Unsuitable Sample I/S = Insufficient Sample



Analytical Report Number : 20-30535

Project / Site name: Twickenham Riverside - Diamond Jubilee Gardens, Twickenham

Water matrix abbreviations: Surface Water (SW) Potable Water (PW) Ground Water (GW)

Analytical Test Name	Analytical Method Description	Analytical Method Reference	Method number	Wet / Dry Analysis	Accreditation Status
Metals in water by ICP-MS (dissolved)	Determination of metals in water by acidification followed by ICP-MS. Accredited Matrices: SW, GW, PW except B=SW,GW, Hg=SW,PW, Al=SW,PW.	In-house method based on USEPA Method 6020 & 200.8 "for the determination of trace elements in water by ICP-MS.	L012-PL	W	ISO 17025
Boron in water	Determination of boron in water by acidification followed by ICP-OES. Accredited matrices: SW PW GW	In-house method based on MEWAM	L039-PL	W	ISO 17025
Complex cyanide (Low level) in water	Determination of complex cyanide by calculation. Accredited matrices SW, PW, GW.	In-house method based on Examination of Water and Wastewater 20th Edition: Clesceri, Greenberg & Eaton (Skalar)	L080-PL	W	ISO 17025
Hexavalent chromium in water	Determination of hexavalent chromium in water by acidification, addition of 1,5 diphenylcarbazide followed by colorimetry.	In-house method by continuous flow analyser. Accredited Matrices SW, GW, PW.	L080-PL	W	ISO 17025
Monohydric phenols in water	Determination of phenols in water by continuous flow analyser. Accredited matrices: SW PW GW	In-house method based on Examination of Water and Wastewater 20th Edition: Clesceri, Greenberg & Eaton (skalar)	L080-PL	W	ISO 17025
Dissolved Oxygen in water	Determination of dissolved oxygen.	In-house method	L086-PL	W	NONE
Speciated EPA-16 PAHs in water	Determination of PAH compounds in water by extraction in dichloromethane followed by GC-MS with the use of surrogate and internal standards. Accredited matrices: SW PW GW	In-house method based on USEPA 8270	L102B-PL	W	ISO 17025
TPH1 (Waters)	Determination of dichloromethane extractable hydrocarbons in water by GC-MS.	In-house method	L070-PL	W	NONE
Low level total cyanide in water	Determination of total cyanide by distillation followed by colorimetry. Accredited matrices: SW PW GW	In-house method based on Examination of Water and Wastewater 20th Edition: Clesceri, Greenberg & Eaton (Skalar)	L080-PL	W	ISO 17025
pH at 20oC in water (automated)	Determination of pH in water by electrometric measurement. Accredited matrices: SW PW GW	In house method.	L099-PL	W	ISO 17025
Free cyanide (low level) in water	Determination of free cyanide by distillation followed by colorimetry. Accredited matrices SW, GW, PW.	In-house method based on Examination of Water and Wastewater 20th Edition: Clesceri, Greenberg & Eaton (Skalar)	L080-PL	W	ISO 17025
Temperature on Receipt (water)	Temperature of water upon receipt.	In-house method	L019-UK	W	NONE
Chloride in water	Determination of Chloride colorimetrically by discrete analyser.	In house based on MEWAM Method ISBN 0117516260. Accredited matrices: SW, PW, GW.	L082-PL	W	ISO 17025

For method numbers ending in 'UK' analysis have been carried out in our laboratory in the United Kingdom.

For method numbers ending in 'PL' analysis have been carried out in our laboratory in Poland.

Soil analytical results are expressed on a dry weight basis. Where analysis is carried out on as-received the results obtained are multiplied by a moisture correction factor that is determined gravimetrically using the moisture content which is carried out at a maximum of 30oC.

---

## Appendix 11 – Geotechnical Laboratory Test Results



**TEST REPORT**  
ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998

<b>Contract</b>	Twickenham Riverside		
<b>Serial No.</b>	37489_1		
<b>Client:</b>	<i>Soil Property Testing Ltd</i>		
Geosphere Environmental Ltd	15, 16, 18 Halcyon Court, St Margaret's Way, Stukeley Meadows, Huntingdon, Cambridgeshire, PE29 6DG		
Head Office Brightwell Barns Ipswich Road Brightwell Suffolk IP10 0BJ	Tel: 01480 455579 Email: <a href="mailto:enquiries@soilpropertytesting.com">enquiries@soilpropertytesting.com</a> Website: <a href="http://www.soilpropertytesting.com">www.soilpropertytesting.com</a>		
<b>Samples Submitted By:</b>	<b>Approved Signatories:</b>		
Geosphere Environmental Ltd	<input checked="" type="checkbox"/> <b>J.C. Garner B.Eng (Hons) FGS</b> Technical Director & Quality Manager		
<b>Samples Labelled:</b>	<input type="checkbox"/> <b>S.P. Townend</b> Chairman		
Twickenham Riverside	<input type="checkbox"/> <b>W. Johnstone</b> Materials Lab Manager		
	<input type="checkbox"/> <b>D. Sabnis</b> Operations Manager 		
<b>Date Received:</b>	14/09/2020	<b>Samples Tested Between:</b>	14/09/2020 and 29/09/2020
<b>Remarks:</b>	For the attention of Jim Dawson Your Reference No: 4955,SI		
<b>Notes:</b>	<ol style="list-style-type: none"><li>1 All remaining samples or remnants from this contract will be disposed of after 21 days from today, unless we are notified to the contrary.</li><li>2 (a) UKAS - United Kingdom Accreditation Service. (b) Opinions and interpretations expressed herein are outside the scope of UKAS accreditation.</li><li>3 Tests marked "NOT UKAS ACCREDITED" in this test report are not included in the UKAS Accreditation Schedule for this testing laboratory.</li><li>4 This test report may not be reproduced other than in full except with the prior written approval of the issuing laboratory.</li></ol>		





# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## SUMMARY OF WATER CONTENT, LIQUID LIMIT, PLASTIC LIMIT, PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole /Pit No.	Depth (m)	Type	Ref.	Water Content (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	Liquidity Index	Sample Preparation			Description	Class	
									Method	Ret'd 0.425mm (%)	Corr'd W/C <0.425mm			Curing Time (hrs)
BH1	7.55	D	9	28.5	76	26	50	0.05	From Natural	0 (A)		67	Very stiff fissured dark greyish brown CLAY.	CV
BH1	13.55	D	15	25.2	72	24	48	0.03	From Natural	0 (A)		68	Very stiff fissured dark greyish brown CLAY.	CV
BH1	19.55	D	21	26.6	75	26	49	0.01	From Natural	0 (A)		68	Very stiff fissured dark greyish brown CLAY.	CV
BH2	4.00	D	4	31.5	79	27	52	0.09	From Natural	0 (A)		68	Stiff dark greyish brown CLAY.	CV
BH2	10.55	D	13	27.2	70	25	45	0.05	From Natural	0 (A)		67	Very stiff fissured dark greyish brown CLAY.	CH/CV
BH2	16.55	D	19	27.4	74	25	49	0.05	From Natural	0 (A)		68	Very stiff fissured dark greyish brown CLAY.	CV

Method Of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2:1990:4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2:1990:3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments:

Table Notation: Ret'd 0.425mm: (A) = Assumed, (M) = Measured



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### PLOT OF PLASTICITY INDEX AGAINST LIQUID LIMIT USING CASAGRANDE CLASSIFICATION CHART

Plasticity				
Low	Medium	High	Very High	Extremely High



High	NHBC Volume Change Potential
Medium	
Low	

Plasticity Chart BS5930: 2015: Figure 8

Method of Preparation:	BS 1377: Part 2: 1990: 4.2
Method of Test:	BS1377: Part 2: 3.2, 4.4, 5.3, 5.4
Type of Sample Key:	U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter
Comments:	Volume Change Potential: NHBC Standards Chapter 4.2 Unmodified Plasticity Index



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
BH1	7.55	D	9	28.5	Very stiff fissured dark greyish brown CLAY.	

<b>PREPARATION</b>			Liquid Limit	76 %	
Method of preparation			From natural	Plastic Limit	26 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	50 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.05	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	67 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
BH1	13.55	D	15	25.2	Very stiff fissured dark greyish brown CLAY.	

<b>PREPARATION</b>			Liquid Limit	72 %	
Method of preparation			From natural	Plastic Limit	24 %
Sample retained 0.425mm sieve (Assumed)			0 %	Plasticity Index	48 %
Corrected water content for material passing 0.425mm				Liquidity Index	0.03
Sample retained 2mm sieve (Assumed)			0 %	NHBC Modified (I'p)	n/a
Curing time	68 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
BH1	19.55	D	21	26.6	Very stiff fissured dark greyish brown CLAY.	

<b>PREPARATION</b>			Liquid Limit	75 %	
Method of preparation			From natural	Plastic Limit	26 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	49 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.01	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	68 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
BH2	4.00	D	4	31.5	Stiff dark greyish brown CLAY.	

<b>PREPARATION</b>			Liquid Limit	79 %	
Method of preparation		From natural	Plastic Limit	27 %	
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	52 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.09	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	68 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
BH2	10.55	D	13	27.2	Very stiff fissured dark greyish brown CLAY.	

<b>PREPARATION</b>			Liquid Limit	70 %	
Method of preparation			From natural	Plastic Limit	25 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	45 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.05	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	67 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
BH2	16.55	D	19	27.4	Very stiff fissured dark greyish brown CLAY.	

<b>PREPARATION</b>			Liquid Limit	74 %	
Method of preparation			From natural	Plastic Limit	25 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	49 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.05	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	68 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

### DETERMINATION OF PARTICLE SIZE DISTRIBUTION

Borehole / Pit No.	Depth (m)	Sample		Description	Remarks
		Type	Reference		
BH1	5.00 - 5.40	B	6	Yellowish brown slightly silty SAND and black, brown and white angular to subrounded chert with occasional yellowish brown and white quartzite GRAVEL	

Method of Test: **Wet Sieve**      Method of Pretreatment: **Not required**



CLAY	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	COBBLES	BOULDERS
	SILT			SAND			GRAVEL				

Hydrometer	Particle Size (mm)	Passing (%)	Silt by Dry Mass (%)	

		Clay by Dry Mass (%)

Sieve Size (mm)	Passing (%)	Sand By Dry Mass (%)
2.00	47	<b>46</b>
1.18	43	
0.600	32	
0.425	20	
0.300	11	
0.212	6	
0.150	3	
0.063	1	

Sieve Size (mm)	Passing (%)	2mm+ By Dry Mass (%)
300		<b>53</b>
125		
90		
63	96	
50	96	
37.5	90	
28	81	
20	74	
14	62	
10	58	
6.3	54	
5	52	

Fines By Dry Mass (%)	
<0.063mm	<b>1</b>

Method of Preparation: BS1377: Part 1: 2016: 8.3 & 8.4.5  
 Method of test: BS1377: Part 2: 1990: 9.2  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF DENSITY, WATER CONTENT AND UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )	Lateral Pressure (kPa)	Deviator Stress (kPa)	Shear Stress (kPa)	Mohr's Circle Analysis		Description
										Cu (kPa)	Ø degrees	
BH1	7.59	U	8	31.0	1.95	1.49	147	196	98			Stiff (high strength) fissured dark greyish brown CLAY with rare silt pockets
BH1	13.61	U	14	25.4	2.02	1.61	261	276	138			Stiff (high strength) fissured dark greyish brown CLAY with rare shell/fossil fragments
BH1	16.58	U	17	27.0	2.02	1.59	320	300	150			Very stiff (very high strength) fissured dark greyish brown CLAY with rare silt pockets and iron pyrite fragments
BH1	24.12	U	25	26.5	2.00	1.58	473	517	259			Very stiff (very high strength) fissured dark greyish brown CLAY with rare silt pockets
BH2	5.11	U	5	29.1	2.00	1.55	106	184	92			Stiff (high strength) fissured dark greyish brown CLAY
BH2	10.58	U	12	25.8	2.02	1.61	200	417	209			Very stiff (very high strength) fissured dark greyish CLAY
BH2	16.59	U	18	28.5	1.96	1.53	316	160	80			Very stiff (high strength) fissured dark greyish brown CLAY with rare silt pockets

Method of Preparation: BS 1377: Part 1: 1990: 7.4.2 & 8, Part 2: 1990: 7.2, Part 7: 1990: 8.3  
 Method of Test: BS 1377: Part 2: 1990:3 Determination of Moisture Content, Part2: 1990:7 Determination of Density, Part 7: 1990: 8 Undrained Shear Strength, 9 Multistage Loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments:  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998

<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF DENSITY, WATER CONTENT AND UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )	Lateral Pressure (kPa)	Deviator Stress (kPa)	Shear Stress (kPa)	Mohrs Circle Analysis		Description
										Cu (kPa)	Ø degrees	
BH2	19.61	U	21	27.7	1.97	1.54	370	269	135			Stiff (high strength) fissured dark greyish brown CLAY
BH2	24.08	U	25	26.9	1.99	1.57	466	603	302			Hard (extremely high strength) fissured dark greyish brown CLAY

Method of Preparation: BS 1377: Part 1: 1990: 7.4.2 & 8, Part 2: 1990: 7.2, Part 7: 1990: 8.3  
 Method of Test: BS 1377: Part 2: 1990:3 Determination of Moisture Content, Part2: 1990:7 Determination of Density, Part 7: 1990: 8 Undrained Shear Strength, 9 Multistage Loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments:  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT


ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998

Contract	Twickenham Riverside
Serial No.	37489_1

## SHEAR STRENGTH VS DEPTH BELOW GROUND LEVEL



Method of Preparation:	BS 1377: Part 1: 1990
Method of Test:	BS 1377: Part7: 1990:8 Definitive Method, 1990:9 Multi-stage loading
Type of Sample Key:	U - Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter
Comments:	
Remarks to Include:	Sample disturbance, loss of water, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH1	7.50	U	8	Stiff (high strength) fissured dark greyish brown CLAY with rare silt pockets	

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>7.59</b>	199.2	102.5	3204	<b>31.0</b>	<b>1.95</b>	<b>1.49</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>147</b>	6.5	0.5	\	196	<b>98</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH1	13.50	U	14	Stiff (high strength) fissured dark greyish brown CLAY with rare shell/fossil fragments	Premature failure at 3.3% strain.

Initial Specimen		Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
	Depth of Top of Specimen (m)	199.4	103.0	3354	25.4	2.02	1.61
	13.61						

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	261	3.3	0.3	\	276	138		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH1	16.50	U	17	Very stiff (very high strength) fissured dark greyish brown CLAY with rare silt pockets and iron pyrite fragments	Premature failure at 3.1% strain.

Initial Specimen		Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
	Depth of Top of Specimen (m)	169.6	102.7	2832	27.0	2.02	1.59
	16.58						

<b>TEST INFORMATION</b>	Rate of Strain <b>0.9</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	320	3.1	0.3	\	300	150		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH1	24.00	U	25	Very stiff (very high strength) fissured dark greyish brown CLAY with rare silt pockets	Premature failure at 4.3% strain.

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>24.12</b>	169.8	102.7	2815	<b>26.5</b>	<b>2.00</b>	<b>1.58</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>0.9</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>473</b>	<b>4.3</b>	<b>0.3</b>	\	<b>517</b>	<b>259</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH2	5.00	U	5	Stiff (high strength) fissured dark greyish brown CLAY	

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>5.11</b>	150.4	102.0	2459	29.1	2.00	1.55

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	106	8.3	0.6	\	184	92		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020



0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH2	10.50	U	12	Very stiff (very high strength) fissured dark greyish brown CLAY	

Initial Specimen		Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
	Depth of Top of Specimen (m) <b>10.58</b>	199.7	102.4	3313	<b>25.8</b>	<b>2.02</b>	<b>1.61</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>200</b>	5.9	0.5	\	417	<b>209</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>


## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH2	16.50	U	18	Very stiff (high strength) fissured dark greyish brown CLAY with rare silt pockets	Premature failure at 2.7% strain.

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>16.59</b>	199.4	102.7	3243	<b>28.5</b>	<b>1.96</b>	<b>1.53</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>316</b>	2.7	0.2	\	160	<b>80</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>


## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH2	19.50	U	21	Stiff (high strength) fissured dark greyish brown CLAY	

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>19.61</b>	199.4	102.9	3265	27.7	1.97	1.54

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	370	7.5	0.5	\	269	135		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 29/09/2020




0998


<b>Contract</b>	<b>Twickenham Riverside</b>
<b>Serial No.</b>	<b>37489_1</b>

## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
BH2	24.00	U	25	Hard (extremely high strength) fissured dark greyish brown CLAY	

Initial Specimen		Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
	Depth of Top of Specimen (m) <b>24.08</b>	170.0	101.9	2751	<b>26.9</b>	<b>1.99</b>	<b>1.57</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>0.9</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>466</b>	6.9	0.5	\	603	<b>302</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C

---

## Appendix 12 – Photographs

**Photograph 1**



**Photograph 2**



**Photograph 3**



**Photograph 4**



**DESCRIPTION**

**Photograph 1**

BH1B service-inspection pit with blue-painted concrete at 1mbgl

**Photograph 2**

Foundation inspection pit HDP03

**Photograph 3**

Foundation inspection pit HDP02

**Photograph 4**

WS02a drilling

**PROJECT**

Diamond Jubilee Gardens/ Wharf Lane /  
The Embankment, Twickenham  
Riverside

**PROJECT NUMBER**

4955,SI

**TITLE**

**Selected Photographs of Ground  
Investigation**

**DATE**

16/09/2020

**PAGE NO.**

1 of 2

**Photograph 5**



**Photograph 6**



**DESCRIPTION**

**Photograph 5**

WS 3 to 3B drilling area

**Photograph 6**

WS4 drilling and service inspection pit arisings

**Photograph 7**

WS4 excavation and probe to base (obstruction at 1.4mbgl)

**Photograph 7**



**Photograph 8**



**Photograph 8**

BH2 drilling

**PROJECT**

Diamond Jubilee Gardens/ Wharf Lane /  
The Embankment, Twickenham  
Riverside

**PROJECT NUMBER**

4955,SI

**TITLE**

**Selected Photographs of Ground  
Investigation**

**DATE**

16/09/2020

**PAGE NO.**

2 of 2

---

## Appendix 13 – UXO Preliminary Report



# **Express Preliminary UXO Risk Assessment**

<b>Client</b>	Geosphere Environmental
<b>Project</b>	Twickenham Riverside
<b>Site Address</b>	4955 Twickenham Riverside, Twickenham
<b>Report Reference</b>	EP11494-00
<b>Date</b>	01/07/20
<b>Originator</b>	WH

## **Assessment Objective**

This preliminary risk assessment is a qualitative screening exercise to assess the likely potential of encountering unexploded ordnance (UXO) at the Twickenham Riverside site. The assessment involves the consideration of the basic factors that affect the potential for UXO to be present at a site as outlined in Stage One of the UXO risk management process.

## **Background**

This assessment uses the sources of information available in-house to 1<sup>st</sup> Line Defence Ltd to enable the placement of a development site in context with events that may have led to the presence of German air-delivered or Allied military UXO. The report will identify any immediate necessity for risk mitigation or additional research in the form of a Detailed UXO Risk Assessment. It makes use of 1<sup>st</sup> Line Defence’s extensive historical archives, library and unique geo-databases, as well as internet resources, and is researched and compiled by UXO specialists and graduate researchers.

The assessment directly follows CIRIA C681 guidelines “Unexploded Ordnance, a Guide for the Construction Industry”. The document will therefore assess the following factors:

- Basic Site Data
- Previous Military Use
- Indicators of potential aerial delivered UXO threat
- Consideration of any Mitigating Factors
- Extent of Proposed Intrusive Works
- Any requirement for Further Work

It should be noted that the vast majority of construction sites in the UK will have a low or negligible risk of encountering UXO and should be able to be screened out at this preliminary stage. The report is meant as a common sense ‘first step’ in the UXO risk management process. The content of the report and conclusions drawn are based on basic, preliminary research using the information available to 1<sup>st</sup> Line Defence at the time this report was produced. It should be noted that the only way to entirely negate risk from UXO to a project would be to support the works proposed with appropriate UXO risk mitigation measures. It is rarely possible to state that there is absolutely ‘no’ risk from UXO to a project.





Risk Assessment Considerations	
<p>Site location and description/current use</p>	<p>The site is located in Twickenham, within south-west London.</p> <p>The site partially comprises two roadways, with a collection of structures in the north. The south of the site comprises hardstanding ground, interspersed with vegetation and a play area. A small section of the River Thames is encompassed by the site in the south-east. It is bound by King Street to the north, structures on Water Lane to the east, the River Thames to the south and structures on Wharf Lane to the west.</p> <p>The site is approximately centred on the OS grid reference: <b>TQ 16272 73165</b>.</p> 
<p>Are there any indicators of current/historical military activity on/close to the site?</p>	<p>In-house records do not indicate that the site footprint had any former military use. No features such as WWII defensive positions, encampments or firing ranges are recorded to have been located at or in the immediate vicinity of the site. In addition, no information of ordnance being stored, produced, or disposed of within the proposed site boundary could be found.</p> <p>The closest recorded Heavy Anti-Aircraft (HAA) battery was situated approximately 4.2km to the east of the site. The conditions in which unexploded anti-aircraft ordnance may have fallen unrecorded within the proposed site are analogous to that of aurally delivered Luftwaffe bombs.</p>
<p>What was the pre- and post-WWII history of the site?</p>	<p>Pre-WWII OS mapping, dated 1934, indicates that the site comprised a series of structures in the north, with a <i>Public House</i> in the north-east. The south comprised areas of hardstanding with a <i>Swimming Bath</i>. Various smaller structures, likely associated with the <i>Swimming Bath</i>, are located within the centre and south of the site.</p> <p>Post-WWII OS mapping, dated 1959, shows minor structural alterations on site, with an area of open ground now present in the south-east, while a structure to the east of the site is no longer present. An area to the north of the aforementioned <i>Swimming Bath</i> is now recorded as <i>Swimming Pool</i>, while a <i>Paddling Pool</i> and <i>Lavatory</i> are recorded to the east. The <i>Public House</i> remains in the north-east of the site.</p>
<p>Was the area subject to bombing during WWII?</p>	<p>During WWII, the site was situated within the Municipal Borough of Twickenham which was subject to an overall moderate density of bombing, according to official Home Office statistics, with an average of 82.8 items of ordnance per 1,000 acres. This consisted of 505 HE (high explosive) bombs, two parachute mines, 25 oil bombs, 21 phosphorus bombs, 27 V-1 pilotless aircraft, and one V-2 long-range rockets, resulting in a total of 581 items of ordnance over 7,013 acres.</p> <p>Consolidated bomb census mapping records a bomb approximately 20m north of the site, with a further bomb located approximately 40m east of the site. Weekly bomb census mapping records one incendiary shower over the site, with a high explosive bomb recorded approximately 130m west of the site. London V-1 pilotless aircraft mapping records a V-1 pilotless aircraft in the south-eastern section of the site.</p>





Is there any evidence of bomb damage on/close to the site?	Post-WWII OS mapping records an area of open ground in the south-east of the site which was previously occupied by a structure. MCC War Damage mapping does record several structures adjacent to the east of the site as having sustained damage ranging from "Border line areas, uncertain whether repairs possible, might have to be demolished" to "Total damage, building to be demolished".
To what degree would the site have been subject to access?	Due to the fact that the site was bound by one roadway and comprised two others, in conjunction with the fact that it housed a Public House and Swimming Baths in an urban area, it is anticipated that at the outbreak of war, access would have been very high. Following the recorded V-1 strike in the south-east of the site, access is considered to have been significantly reduced for a period while repairs and or evacuation took place. This increases the chances that items of UXO could have gone unnoticed and unreported.
To what degree has the site been developed post-WWII?	Sections in the east of the site now appear to be occupied by hardstanding, while the central section which housed the Swimming Pools is now occupied by hardstanding and vegetation.
What is the nature and extent of the intrusive works proposed?	The nature and extent of works proposed was not available at the time of writing.

**Summary and Conclusions**

The site was situated within the Municipal Borough of Twickenham during WWII, which sustained a moderate density of bombing at 82.8 items per 1,000 acres. London bomb census mapping indicates that a V-1 bomb fell within the south-eastern section of the site during the war. Several bombs also fell within the general vicinity of the site.

No damage was recorded on site on MCC War Damage mapping, despite the fact that a V-1 flying bomb was recorded as falling within the south-eastern section of the site. Given the recorded bombing on site, it is anticipated that access on site would have been impeded until it was deemed safe to return, increasing the likelihood that items of UXO would have gone unnoticed and unreported.

**Recommendations**

Following the findings of this preliminary report, it is recommended that **further action** is taken in the form of a **Detailed UXO Risk Assessment**.

Further research would include visits to local and national archives, and the acquisition of local bombing records and other archival material. Following this, a more precise assessment on the risk presented from items of UXO can be made. In addition, high-resolution aerial photography of the site would be obtained in order to understand if the site appeared damaged following the recorded incident in the south-eastern section of the site.

**Prior to or in lieu of a Detailed Assessment, it is recommended that appropriate UXO Risk Mitigation Measures are provided for intrusive works proposed.**

If the client has any anecdotal or empirical evidence of UXO risk on site, please contact 1<sup>st</sup> Line Defence.



---

## Appendix 14 – Soil Waste Classification Report

## Waste Classification Report



8AH6V-L8EXD-HMN6U

### Job name

4955,SI Twickenham Riverside

### Description/Comments

Localised ground investigation data from GI report 4955

### Project

4955,SI, Twickenham Riverside

### Site

4955,SI: Diamond Jubilee Gardens, Wharf Lane, The Embankment (Twickenham Riverside project)

### Related Documents

#	Name	Description
1	20-10290.1.hwol	.hwol file used to create the Job
2	20-10989.1.hwol	.hwol file for the job
3	20-10989.1.pdf	soil analysis dataset 1/2
4	20-10290.1.pdf	soil analysis dataset 2/2

### Waste Stream Template

GEL HWOL 05 2020

### Classified by

Name: <b>Jim Dawson</b>	Company: <b>Geosphere Environmental Ltd</b> <b>Brightwell Barns, Ipswich Road</b>	HazWasteOnline™ Training Record:	
Date: <b>19 Nov 2020 13:50 GMT</b>	<b>Ipswich Road</b>	<b>Course</b>	<b>Date</b>
Telephone: <b>01603 298076</b>	<b>Brightwell</b> <b>IP10 0BJ</b>	Hazardous Waste Classification	10 Mar 2020
		Advanced Hazardous Waste Classification	11 Mar 2020

### Report

Created by: Jim Dawson  
Created date: 19 Nov 2020 13:50 GMT

### Job summary

#	Sample Name	Depth [m]	Classification Result	Hazard properties	Page
1	BH1 + BH2	2.0 - 24.0	Non Hazardous		3
2	BH01A + BH01B	0.20 - 0.80	Non Hazardous		6
3	BH2	1.2	Non Hazardous		9
4	HP01 WAC2	0.25 - 1.20	Non Hazardous		12
5	WS01A and WS2, J1 Combined	0.2	Non Hazardous		15
6	WS01A J2	0.6	Non Hazardous		18

---

Appendices	Page
Appendix A: Classifier defined and non CLP determinands	21
Appendix B: Rationale for selection of metal species	22
Appendix C: Version	23

---

**Classification of sample: BH1 + BH2**

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

**Sample details**

Sample Name:	LoW Code:	
<b>BH1 + BH2</b>	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
<b>2.0 - 24.0 m</b>		
Moisture content:		
<b>12.5%</b>		
(no correction)		

**Hazard properties**

None identified

**Determinands**

Moisture content: 12.5% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				9 mg/kg	1.32	11.883 mg/kg	0.00119 %		
	033-003-00-0	215-481-4	1327-53-3							
2	barium { barium sulphide }				50 mg/kg	1.233	61.675 mg/kg	0.00617 %		
	016-002-00-X	244-214-4	21109-95-5							
3	beryllium { beryllium oxide }				0.9 mg/kg	2.775	2.498 mg/kg	0.00025 %		
	004-003-00-8	215-133-1	1304-56-9							
4	boron { diboron trioxide; boric oxide }				2.3 mg/kg	3.22	7.406 mg/kg	0.000741 %		
	005-008-00-8	215-125-8	1303-86-2							
5	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0							
6	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				31 mg/kg	1.462	45.308 mg/kg	0.00453 %		
		215-160-9	1308-38-9							
7	chromium in chromium(VI) compounds { chromium(VI) oxide }				<2 mg/kg	1.923	<3.846 mg/kg	<0.000385 %		<LOD
	024-001-00-0	215-607-8	1333-82-0							
8	copper { dicopper oxide; copper (I) oxide }				19 mg/kg	1.126	21.392 mg/kg	0.00214 %		
	029-002-00-X	215-270-7	1317-39-1							
9	lead { lead chromate }			1	10 mg/kg	1.56	15.598 mg/kg	0.001 %		
	082-004-00-2	231-846-0	7758-97-6							
10	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
11	nickel { nickel chromate }				29 mg/kg	2.976	86.312 mg/kg	0.00863 %		
	028-035-00-7	238-766-5	14721-18-7							
12	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<3 mg/kg	1.405	<4.215 mg/kg	<0.000422 %		<LOD
	034-002-00-8									
13	vanadium { divanadium pentaoxide; vanadium pentoxide }				54 mg/kg	1.785	96.4 mg/kg	0.00964 %		
	023-001-00-8	215-239-8	1314-62-1							
14	zinc { zinc chromate }				78 mg/kg	2.774	216.383 mg/kg	0.0216 %		
	024-007-00-3	236-878-9	13530-65-9							

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
15	TPH (C6 to C40) petroleum group				<42	mg/kg		<42	mg/kg	<0.0042 %		<LOD
			TPH									
16	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
17	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
18	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
19	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									
20	xylene				<4	mg/kg		<4	mg/kg	<0.0004 %		<LOD
	601-022-00-9	202-422-2 [1] 203-396-5 [2] 203-576-3 [3] 215-535-7 [4]	95-47-6 [1] 106-42-3 [2] 108-38-3 [3] 1330-20-7 [4]									
21	cyanides { salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex }				<2	mg/kg	1.884	<3.768	mg/kg	<0.000377 %		<LOD
	006-007-00-5											
22	pH				8.1	pH		8.1	pH	8.1 pH		
			PH									
23	naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3									
24	acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8									
25	acenaphthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9									
26	fluorene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7									
27	phenanthrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8									
28	anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7									
29	fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-912-4	206-44-0									
30	pyrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-927-3	129-00-0									
31	benzo[a]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-033-00-9	200-280-6	56-55-3									
32	chrysene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9									
33	benzo[b]fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-034-00-4	205-911-9	205-99-2									
34	benzo[k]fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9									
35	benzo[a]pyrene; benzo[def]chrysene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-032-00-3	200-028-5	50-32-8									
36	indeno[123-cd]pyrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-893-2	193-39-5									
37	dibenz[a,h]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3									
38	benzo[ghi]perylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-883-8	191-24-2									
Total:										0.0634 %		

Key

---

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<b>&lt;LOD</b>	Below limit of detection
<b>ND</b>	Not detected
CLP: Note 1	Only the metal concentration has been used for classification

**Classification of sample: BH01A + BH01B**

 **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

**Sample details**

Sample Name:	<b>BH01A + BH01B</b>	LoW Code:	
Sample Depth:	<b>0.20 - 0.80 m</b>	Chapter:	<b>17: Construction and Demolition Wastes (including excavated soil from contaminated sites)</b>
Moisture content:	<b>5.6%</b> (no correction)	Entry:	<b>17 05 04 (Soil and stones other than those mentioned in 17 05 03)</b>

**Hazard properties**

None identified

**Determinands**

Moisture content: **5.6% No Moisture Correction applied (MC)**

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number								
1	arsenic { arsenic trioxide }				15 mg/kg	1.32	19.805 mg/kg	0.00198 %			
	033-003-00-0	215-481-4	1327-53-3								
2	barium { barium sulphide }				71 mg/kg	1.233	87.578 mg/kg	0.00876 %			
	016-002-00-X	244-214-4	21109-95-5								
3	beryllium { beryllium oxide }				0.7 mg/kg	2.775	1.943 mg/kg	0.000194 %			
	004-003-00-8	215-133-1	1304-56-9								
4	boron { diboron trioxide; boric oxide }				<1 mg/kg	3.22	<3.22 mg/kg	<0.000322 %			<LOD
	005-008-00-8	215-125-8	1303-86-2								
5	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %			<LOD
	048-002-00-0	215-146-2	1306-19-0								
6	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				19 mg/kg	1.462	27.77 mg/kg	0.00278 %			
		215-160-9	1308-38-9								
7	chromium in chromium(VI) compounds { chromium(VI) oxide }				<2 mg/kg	1.923	<3.846 mg/kg	<0.000385 %			<LOD
	024-001-00-0	215-607-8	1333-82-0								
8	copper { dicopper oxide; copper (I) oxide }				20 mg/kg	1.126	22.518 mg/kg	0.00225 %			
	029-002-00-X	215-270-7	1317-39-1								
9	lead { lead chromate }			1	207 mg/kg	1.56	322.882 mg/kg	0.0207 %			
	082-004-00-2	231-846-0	7758-97-6								
10	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %			<LOD
	080-010-00-X	231-299-8	7487-94-7								
11	nickel { nickel chromate }				16 mg/kg	2.976	47.62 mg/kg	0.00476 %			
	028-035-00-7	238-766-5	14721-18-7								
12	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<3 mg/kg	1.405	<4.215 mg/kg	<0.000422 %			<LOD
	034-002-00-8										
13	vanadium { divanadium pentaoxide; vanadium pentoxide }				38 mg/kg	1.785	67.837 mg/kg	0.00678 %			
	023-001-00-8	215-239-8	1314-62-1								
14	zinc { zinc chromate }				68 mg/kg	2.774	188.642 mg/kg	0.0189 %			
	024-007-00-3	236-878-9	13530-65-9								

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
15	TPH (C6 to C40) petroleum group				<6	mg/kg		<6	mg/kg	<0.0006 %		<LOD
			TPH									
16	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
17	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
18	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
19	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									
20	xylene				<4	mg/kg		<4	mg/kg	<0.0004 %		<LOD
	601-022-00-9	202-422-2 [1] 203-396-5 [2] 203-576-3 [3] 215-535-7 [4]	95-47-6 [1] 106-42-3 [2] 108-38-3 [3] 1330-20-7 [4]									
21	cyanides { salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex }				<2	mg/kg	1.884	<3.768	mg/kg	<0.000377 %		<LOD
	006-007-00-5											
22	pH				8.3	pH		8.3	pH	8.3 pH		
			PH									
23	naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3									
24	acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8									
25	acenaphthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9									
26	fluorene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7									
27	phenanthrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8									
28	anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7									
29	fluoranthene				0.17	mg/kg		0.17	mg/kg	0.000017 %		
		205-912-4	206-44-0									
30	pyrene				0.12	mg/kg		0.12	mg/kg	0.000012 %		
		204-927-3	129-00-0									
31	benzo[a]anthracene				0.3	mg/kg		0.3	mg/kg	0.00003 %		
	601-033-00-9	200-280-6	56-55-3									
32	chrysene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9									
33	benzo[b]fluoranthene				0.52	mg/kg		0.52	mg/kg	0.000052 %		
	601-034-00-4	205-911-9	205-99-2									
34	benzo[k]fluoranthene				0.13	mg/kg		0.13	mg/kg	0.000013 %		
	601-036-00-5	205-916-6	207-08-9									
35	benzo[a]pyrene; benzo[def]chrysene				0.28	mg/kg		0.28	mg/kg	0.000028 %		
	601-032-00-3	200-028-5	50-32-8									
36	indeno[123-cd]pyrene				0.38	mg/kg		0.38	mg/kg	0.000038 %		
		205-893-2	193-39-5									
37	dibenz[a,h]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3									
38	benzo[ghi]perylene				0.21	mg/kg		0.21	mg/kg	0.000021 %		
		205-883-8	191-24-2									
Total:										0.0714 %		

Key

---

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<b>&lt;LOD</b>	Below limit of detection
<b>ND</b>	Not detected
CLP: Note 1	Only the metal concentration has been used for classification

## Classification of sample: BH2

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

## Sample details

Sample Name:	<b>BH2</b>	LoW Code:	
Sample Depth:	<b>1.2 m</b>	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Moisture content:	<b>12.8%</b> (no correction)	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)

## Hazard properties

None identified

## Determinands

Moisture content: **12.8%** No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				15 mg/kg	1.32	19.805 mg/kg	0.00198 %		
	033-003-00-0	215-481-4	1327-53-3							
2	barium { barium sulphide }				55 mg/kg	1.233	67.842 mg/kg	0.00678 %		
	016-002-00-X	244-214-4	21109-95-5							
3	beryllium { beryllium oxide }				0.6 mg/kg	2.775	1.665 mg/kg	0.000167 %		
	004-003-00-8	215-133-1	1304-56-9							
4	boron { diboron trioxide; boric oxide }				<1 mg/kg	3.22	<3.22 mg/kg	<0.000322 %		<LOD
	005-008-00-8	215-125-8	1303-86-2							
5	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0							
6	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				16 mg/kg	1.462	23.385 mg/kg	0.00234 %		
		215-160-9	1308-38-9							
7	chromium in chromium(VI) compounds { chromium(VI) oxide }				<2 mg/kg	1.923	<3.846 mg/kg	<0.000385 %		<LOD
	024-001-00-0	215-607-8	1333-82-0							
8	copper { dicopper oxide; copper (I) oxide }				17 mg/kg	1.126	19.14 mg/kg	0.00191 %		
	029-002-00-X	215-270-7	1317-39-1							
9	lead { lead chromate }			1	111 mg/kg	1.56	173.139 mg/kg	0.0111 %		
	082-004-00-2	231-846-0	7758-97-6							
10	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
11	nickel { nickel chromate }				13 mg/kg	2.976	38.691 mg/kg	0.00387 %		
	028-035-00-7	238-766-5	14721-18-7							
12	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<3 mg/kg	1.405	<4.215 mg/kg	<0.000422 %		<LOD
	034-002-00-8									
13	vanadium { divanadium pentaoxide; vanadium pentoxide }				36 mg/kg	1.785	64.267 mg/kg	0.00643 %		
	023-001-00-8	215-239-8	1314-62-1							
14	zinc { zinc chromate }				38 mg/kg	2.774	105.418 mg/kg	0.0105 %		
	024-007-00-3	236-878-9	13530-65-9							

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
15	TPH (C6 to C40) petroleum group				<6	mg/kg		<6	mg/kg	<0.0006 %		<LOD
			TPH									
16	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
17	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
18	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
19	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									
20	xylene				<4	mg/kg		<4	mg/kg	<0.0004 %		<LOD
	601-022-00-9	202-422-2 [1] 203-396-5 [2] 203-576-3 [3] 215-535-7 [4]	95-47-6 [1] 106-42-3 [2] 108-38-3 [3] 1330-20-7 [4]									
21	cyanides { salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex }				<2	mg/kg	1.884	<3.768	mg/kg	<0.000377 %		<LOD
	006-007-00-5											
22	pH				8.3	pH		8.3	pH	8.3 pH		
			PH									
23	naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3									
24	acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8									
25	acenaphthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9									
26	fluorene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7									
27	phenanthrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8									
28	anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7									
29	fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-912-4	206-44-0									
30	pyrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-927-3	129-00-0									
31	benzo[a]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-033-00-9	200-280-6	56-55-3									
32	chrysene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9									
33	benzo[b]fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-034-00-4	205-911-9	205-99-2									
34	benzo[k]fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9									
35	benzo[a]pyrene; benzo[def]chrysene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-032-00-3	200-028-5	50-32-8									
36	indeno[123-cd]pyrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-893-2	193-39-5									
37	dibenz[a,h]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3									
38	benzo[ghi]perylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-883-8	191-24-2									
Total:										0.0493 %		

Key

---

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<b>&lt;LOD</b>	Below limit of detection
<b>ND</b>	Not detected
CLP: Note 1	Only the metal concentration has been used for classification

**Classification of sample: HP01 WAC2**

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

**Sample details**

Sample Name: <b>HP01 WAC2</b>	LoW Code: Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth: <b>0.25 - 1.20 m</b>	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
Moisture content: <b>3.7%</b> (no correction)		

**Hazard properties**

None identified

**Determinands**


Moisture content: 3.7% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number								
1	arsenic { arsenic trioxide }				16 mg/kg	1.32	21.125 mg/kg	0.00211 %			
	033-003-00-0	215-481-4	1327-53-3								
2	barium { barium sulphide }				35 mg/kg	1.233	43.172 mg/kg	0.00432 %			
	016-002-00-X	244-214-4	21109-95-5								
3	beryllium { beryllium oxide }				0.6 mg/kg	2.775	1.665 mg/kg	0.000167 %			
	004-003-00-8	215-133-1	1304-56-9								
4	boron { diboron trioxide; boric oxide }				<1 mg/kg	3.22	<3.22 mg/kg	<0.000322 %			<LOD
	005-008-00-8	215-125-8	1303-86-2								
5	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %			<LOD
	048-002-00-0	215-146-2	1306-19-0								
6	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				20 mg/kg	1.462	29.231 mg/kg	0.00292 %			
		215-160-9	1308-38-9								
7	chromium in chromium(VI) compounds { chromium(VI) oxide }				<2 mg/kg	1.923	<3.846 mg/kg	<0.000385 %			<LOD
	024-001-00-0	215-607-8	1333-82-0								
8	copper { dicopper oxide; copper (I) oxide }				15 mg/kg	1.126	16.888 mg/kg	0.00169 %			
	029-002-00-X	215-270-7	1317-39-1								
9	lead { lead chromate }			1	51 mg/kg	1.56	79.551 mg/kg	0.0051 %			
	082-004-00-2	231-846-0	7758-97-6								
10	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %			<LOD
	080-010-00-X	231-299-8	7487-94-7								
11	nickel { nickel chromate }				14 mg/kg	2.976	41.668 mg/kg	0.00417 %			
	028-035-00-7	238-766-5	14721-18-7								
12	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<3 mg/kg	1.405	<4.215 mg/kg	<0.000422 %			<LOD
	034-002-00-8										
13	vanadium { divanadium pentaoxide; vanadium pentoxide }				42 mg/kg	1.785	74.978 mg/kg	0.0075 %			
	023-001-00-8	215-239-8	1314-62-1								
14	zinc { zinc chromate }				45 mg/kg	2.774	124.837 mg/kg	0.0125 %			
	024-007-00-3	236-878-9	13530-65-9								

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
15	TPH (C6 to C40) petroleum group				<42	mg/kg		<42	mg/kg	<0.0042 %		<LOD
			TPH									
16	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
17	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
18	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
19	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									
20	xylene				<4	mg/kg		<4	mg/kg	<0.0004 %		<LOD
	601-022-00-9	202-422-2 [1] 203-396-5 [2] 203-576-3 [3] 215-535-7 [4]	95-47-6 [1] 106-42-3 [2] 108-38-3 [3] 1330-20-7 [4]									
21	cyanides { salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex }				<2	mg/kg	1.884	<3.768	mg/kg	<0.000377 %		<LOD
	006-007-00-5											
22	pH				8.1	pH		8.1	pH	8.1 pH		
			PH									
23	naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3									
24	acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8									
25	acenaphthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9									
26	fluorene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7									
27	phenanthrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8									
28	anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7									
29	fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-912-4	206-44-0									
30	pyrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-927-3	129-00-0									
31	benzo[a]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-033-00-9	200-280-6	56-55-3									
32	chrysene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9									
33	benzo[b]fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-034-00-4	205-911-9	205-99-2									
34	benzo[k]fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9									
35	benzo[a]pyrene; benzo[def]chrysene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-032-00-3	200-028-5	50-32-8									
36	indeno[123-cd]pyrene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-893-2	193-39-5									
37	dibenz[a,h]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3									
38	benzo[ghi]perylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-883-8	191-24-2									
Total:										0.0483 %		

Key

---

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<b>&lt;LOD</b>	Below limit of detection
<b>ND</b>	Not detected
CLP: Note 1	Only the metal concentration has been used for classification

### Classification of sample: WS01A and WS2, J1 Combined

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

### Sample details

Sample Name:	LoW Code:	
<b>WS01A and WS2, J1 Combined</b>	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
<b>0.2 m</b>		
Moisture content:		
<b>7.4%</b>		
(no correction)		

### Hazard properties

None identified

### Determinands

Moisture content: 7.4% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				11 mg/kg	1.32	14.524 mg/kg	0.00145 %		
	033-003-00-0	215-481-4	1327-53-3							
2	barium { barium sulphide }				58 mg/kg	1.233	71.543 mg/kg	0.00715 %		
	016-002-00-X	244-214-4	21109-95-5							
3	beryllium { beryllium oxide }				<0.5 mg/kg	2.775	<1.388 mg/kg	<0.000139 %		<LOD
	004-003-00-8	215-133-1	1304-56-9							
4	boron { diboron trioxide; boric oxide }				<1 mg/kg	3.22	<3.22 mg/kg	<0.000322 %		<LOD
	005-008-00-8	215-125-8	1303-86-2							
5	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0							
6	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				15 mg/kg	1.462	21.923 mg/kg	0.00219 %		
		215-160-9	1308-38-9							
7	chromium in chromium(VI) compounds { chromium(VI) oxide }				<2 mg/kg	1.923	<3.846 mg/kg	<0.000385 %		<LOD
	024-001-00-0	215-607-8	1333-82-0							
8	copper { dicopper oxide; copper (I) oxide }				20 mg/kg	1.126	22.518 mg/kg	0.00225 %		
	029-002-00-X	215-270-7	1317-39-1							
9	lead { lead chromate }			1	70 mg/kg	1.56	109.187 mg/kg	0.007 %		
	082-004-00-2	231-846-0	7758-97-6							
10	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
11	nickel { nickel chromate }				9 mg/kg	2.976	26.786 mg/kg	0.00268 %		
	028-035-00-7	238-766-5	14721-18-7							
12	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<3 mg/kg	1.405	<4.215 mg/kg	<0.000422 %		<LOD
	034-002-00-8									
13	vanadium { divanadium pentaoxide; vanadium pentoxide }				30 mg/kg	1.785	53.556 mg/kg	0.00536 %		
	023-001-00-8	215-239-8	1314-62-1							
14	zinc { zinc chromate }				67 mg/kg	2.774	185.868 mg/kg	0.0186 %		
	024-007-00-3	236-878-9	13530-65-9							

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
15	TPH (C6 to C40) petroleum group				<42	mg/kg		<42	mg/kg	<0.0042 %		<LOD
			TPH									
16	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
17	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
18	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
19	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									
20	xylene				<4	mg/kg		<4	mg/kg	<0.0004 %		<LOD
	601-022-00-9	202-422-2 [1] 203-396-5 [2] 203-576-3 [3] 215-535-7 [4]	95-47-6 [1] 106-42-3 [2] 108-38-3 [3] 1330-20-7 [4]									
21	cyanides { salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex }				<2	mg/kg	1.884	<3.768	mg/kg	<0.000377 %		<LOD
	006-007-00-5											
22	pH				7.6	pH		7.6	pH	7.6 pH		
			PH									
23	naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3									
24	acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8									
25	acenaphthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9									
26	fluorene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7									
27	phenanthrene				0.27	mg/kg		0.27	mg/kg	0.000027 %		
		201-581-5	85-01-8									
28	anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7									
29	fluoranthene				0.76	mg/kg		0.76	mg/kg	0.000076 %		
		205-912-4	206-44-0									
30	pyrene				0.69	mg/kg		0.69	mg/kg	0.000069 %		
		204-927-3	129-00-0									
31	benzo[a]anthracene				0.48	mg/kg		0.48	mg/kg	0.000048 %		
	601-033-00-9	200-280-6	56-55-3									
32	chrysene				0.4	mg/kg		0.4	mg/kg	0.00004 %		
	601-048-00-0	205-923-4	218-01-9									
33	benzo[b]fluoranthene				0.66	mg/kg		0.66	mg/kg	0.000066 %		
	601-034-00-4	205-911-9	205-99-2									
34	benzo[k]fluoranthene				0.22	mg/kg		0.22	mg/kg	0.000022 %		
	601-036-00-5	205-916-6	207-08-9									
35	benzo[a]pyrene; benzo[def]chrysene				0.5	mg/kg		0.5	mg/kg	0.00005 %		
	601-032-00-3	200-028-5	50-32-8									
36	indeno[123-cd]pyrene				0.31	mg/kg		0.31	mg/kg	0.000031 %		
		205-893-2	193-39-5									
37	dibenz[a,h]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3									
38	benzo[ghi]perylene				0.3	mg/kg		0.3	mg/kg	0.00003 %		
		205-883-8	191-24-2									
Total:										0.055 %		

Key

---

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<b>&lt;LOD</b>	Below limit of detection
<b>ND</b>	Not detected
CLP: Note 1	Only the metal concentration has been used for classification

**Classification of sample: WS01A J2**

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

**Sample details**

Sample Name:	<b>WS01A J2</b>	LoW Code:	
Sample Depth:	<b>0.6 m</b>	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Moisture content:	<b>3.1%</b> (no correction)	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)

**Hazard properties**

None identified

**Determinands**


Moisture content: 3.1% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number								
1	arsenic { arsenic trioxide }				16 mg/kg	1.32	21.125	mg/kg	0.00211 %		
	033-003-00-0	215-481-4	1327-53-3								
2	barium { barium sulphide }				63 mg/kg	1.233	77.71	mg/kg	0.00777 %		
	016-002-00-X	244-214-4	21109-95-5								
3	beryllium { beryllium oxide }				0.6 mg/kg	2.775	1.665	mg/kg	0.000167 %		
	004-003-00-8	215-133-1	1304-56-9								
4	boron { diboron trioxide; boric oxide }				<1 mg/kg	3.22	<3.22	mg/kg	<0.000322 %		<LOD
	005-008-00-8	215-125-8	1303-86-2								
5	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228	mg/kg	<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0								
6	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				21 mg/kg	1.462	30.693	mg/kg	0.00307 %		
		215-160-9	1308-38-9								
7	chromium in chromium(VI) compounds { chromium(VI) oxide }				<2 mg/kg	1.923	<3.846	mg/kg	<0.000385 %		<LOD
	024-001-00-0	215-607-8	1333-82-0								
8	copper { dicopper oxide; copper (I) oxide }				19 mg/kg	1.126	21.392	mg/kg	0.00214 %		
	029-002-00-X	215-270-7	1317-39-1								
9	lead { lead chromate }			1	72 mg/kg	1.56	112.307	mg/kg	0.0072 %		
	082-004-00-2	231-846-0	7758-97-6								
10	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353	mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7								
11	nickel { nickel chromate }				15 mg/kg	2.976	44.644	mg/kg	0.00446 %		
	028-035-00-7	238-766-5	14721-18-7								
12	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<3 mg/kg	1.405	<4.215	mg/kg	<0.000422 %		<LOD
	034-002-00-8										
13	vanadium { divanadium pentaoxide; vanadium pentoxide }				44 mg/kg	1.785	78.548	mg/kg	0.00785 %		
	023-001-00-8	215-239-8	1314-62-1								
14	zinc { zinc chromate }				83 mg/kg	2.774	230.254	mg/kg	0.023 %		
	024-007-00-3	236-878-9	13530-65-9								

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
15	TPH (C6 to C40) petroleum group				<42	mg/kg		<42	mg/kg	<0.0042 %		<LOD
			TPH									
16	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
17	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
18	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
19	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									
20	xylene				<4	mg/kg		<4	mg/kg	<0.0004 %		<LOD
	601-022-00-9	202-422-2 [1] 203-396-5 [2] 203-576-3 [3] 215-535-7 [4]	95-47-6 [1] 106-42-3 [2] 108-38-3 [3] 1330-20-7 [4]									
21	cyanides { salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex }				<2	mg/kg	1.884	<3.768	mg/kg	<0.000377 %		<LOD
	006-007-00-5											
22	pH				8.2	pH		8.2	pH	8.2 pH		
			PH									
23	naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3									
24	acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8									
25	acenaphthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9									
26	fluorene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7									
27	phenanthrene				0.11	mg/kg		0.11	mg/kg	0.000011 %		
		201-581-5	85-01-8									
28	anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7									
29	fluoranthene				0.32	mg/kg		0.32	mg/kg	0.000032 %		
		205-912-4	206-44-0									
30	pyrene				0.28	mg/kg		0.28	mg/kg	0.000028 %		
		204-927-3	129-00-0									
31	benzo[a]anthracene				0.18	mg/kg		0.18	mg/kg	0.000018 %		
	601-033-00-9	200-280-6	56-55-3									
32	chrysene				0.17	mg/kg		0.17	mg/kg	0.000017 %		
	601-048-00-0	205-923-4	218-01-9									
33	benzo[b]fluoranthene				0.24	mg/kg		0.24	mg/kg	0.000024 %		
	601-034-00-4	205-911-9	205-99-2									
34	benzo[k]fluoranthene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9									
35	benzo[a]pyrene; benzo[def]chrysene				0.18	mg/kg		0.18	mg/kg	0.000018 %		
	601-032-00-3	200-028-5	50-32-8									
36	indeno[123-cd]pyrene				0.11	mg/kg		0.11	mg/kg	0.000011 %		
		205-893-2	193-39-5									
37	dibenz[a,h]anthracene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3									
38	benzo[ghi]perylene				0.11	mg/kg		0.11	mg/kg	0.000011 %		
		205-883-8	191-24-2									
Total:										0.0657 %		

Key

---

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<b>&lt;LOD</b>	Below limit of detection
<b>ND</b>	Not detected
CLP: Note 1	Only the metal concentration has been used for classification

## Appendix A: Classifier defined and non CLP determinands

- **barium sulphide** (EC Number: 244-214-4, CAS Number: 21109-95-5)

CLP index number: 016-002-00-X

Description/Comments:

Data source: Regulation 1272/2008/EC - Classification, labelling and packaging of substances and mixtures. (CLP)

Additional Hazard Statement(s): EUH031 >= 0.8 %

Reason for additional Hazards Statement(s):

14 Dec 2015 - EUH031 >= 0.8 % hazard statement sourced from: WM3, Table C12.2

- **chromium(III) oxide (worst case)** (EC Number: 215-160-9, CAS Number: 1308-38-9)

Conversion factor: 1.462

Description/Comments: Data from C&L Inventory Database

Data source: <https://echa.europa.eu/information-on-chemicals/cl-inventory-database/-/discli/details/33806>

Data source date: 17 Jul 2015

Hazard Statements: Acute Tox. 4 H332 , Acute Tox. 4 H302 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315 , Resp. Sens. 1 H334 , Skin Sens. 1 H317 , Repr. 1B H360FD , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

- **TPH (C6 to C40) petroleum group** (CAS Number: TPH)

Description/Comments: Hazard statements taken from WM3 1st Edition 2015; Risk phrases: WM2 3rd Edition 2013

Data source: WM3 1st Edition 2015

Data source date: 25 May 2015

Hazard Statements: Flam. Liq. 3 H226 , Asp. Tox. 1 H304 , STOT RE 2 H373 , Muta. 1B H340 , Carc. 1B H350 , Repr. 2 H361d , Aquatic Chronic 2 H411

- **ethylbenzene** (EC Number: 202-849-4, CAS Number: 100-41-4)

CLP index number: 601-023-00-4

Description/Comments:

Data source: Commission Regulation (EU) No 605/2014 – 6th Adaptation to Technical Progress for Regulation (EC) No 1272/2008. (ATP6)

Additional Hazard Statement(s): Carc. 2 H351

Reason for additional Hazards Statement(s):

03 Jun 2015 - Carc. 2 H351 hazard statement sourced from: IARC Group 2B (77) 2000

- **salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex**

CLP index number: 006-007-00-5

Description/Comments: Conversion factor based on a worst case compound: sodium cyanide

Data source: Commission Regulation (EC) No 790/2009 - 1st Adaptation to Technical Progress for Regulation (EC) No 1272/2008. (ATP1)

Additional Hazard Statement(s): EUH032 >= 0.2 %

Reason for additional Hazards Statement(s):

14 Dec 2015 - EUH032 >= 0.2 % hazard statement sourced from: WM3, Table C12.2

- **pH** (CAS Number: PH)

Description/Comments: Appendix C4

Data source: WM3 1st Edition 2015

Data source date: 25 May 2015

Hazard Statements: None.

- **acenaphthylene** (EC Number: 205-917-1, CAS Number: 208-96-8)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 17 Jul 2015

Hazard Statements: Acute Tox. 4 H302 , Acute Tox. 1 H330 , Acute Tox. 1 H310 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315

- **acenaphthene** (EC Number: 201-469-6, CAS Number: 83-32-9)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 17 Jul 2015

Hazard Statements: Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410 , Aquatic Chronic 2 H411

• **fluorene** (EC Number: 201-695-5, CAS Number: 86-73-7)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 06 Aug 2015  
Hazard Statements: Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

• **phenanthrene** (EC Number: 201-581-5, CAS Number: 85-01-8)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 06 Aug 2015  
Hazard Statements: Acute Tox. 4 H302 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Carc. 2 H351 , Skin Sens. 1 H317 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410 , Skin Irrit. 2 H315

• **anthracene** (EC Number: 204-371-1, CAS Number: 120-12-7)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 17 Jul 2015  
Hazard Statements: Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315 , Skin Sens. 1 H317 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

• **fluoranthene** (EC Number: 205-912-4, CAS Number: 206-44-0)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 21 Aug 2015  
Hazard Statements: Acute Tox. 4 H302 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

• **pyrene** (EC Number: 204-927-3, CAS Number: 129-00-0)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 2014  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 21 Aug 2015  
Hazard Statements: Skin Irrit. 2 H315 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

• **indeno[123-cd]pyrene** (EC Number: 205-893-2, CAS Number: 193-39-5)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 06 Aug 2015  
Hazard Statements: Carc. 2 H351

• **benzo[ghi]perylene** (EC Number: 205-883-8, CAS Number: 191-24-2)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 28/02/2015  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 23 Jul 2015  
Hazard Statements: Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

## Appendix B: Rationale for selection of metal species

### arsenic {arsenic trioxide}

Reasonable case CLP species based on hazard statements/molecular weight and most common (stable) oxide of arsenic. Industrial sources include: smelting; main precursor to other arsenic compounds (edit as required);

### barium {barium sulphide}

In the absence of significant chromium concentrations in samples, chromate species not possible; barium sulphide utilised as applicable

### beryllium {beryllium oxide}

Reasonable case CLP species based on hazard statements/molecular weight. Industrial sources include: most common (non alloy) form, used in ceramics (edit as required);

### boron {diboron trioxide; boric oxide}

Reasonable case CLP species based on hazard statements/ molecular weight, physical form and low solubility. Industrial sources include: fluxing agent for glass/enamels; additive for fibre optics, borosilicate glass (edit as required);

### cadmium {cadmium oxide}

Reasonable case CLP species based on hazard statements/molecular weight, very low solubility in water. Industrial sources include: electroplating baths, electrodes for storage batteries, catalysts, ceramic glazes, phosphors, pigments and nematocides. (edit as required) Worst case compounds in CLP: cadmium sulphate, chloride, fluoride & iodide not expected as either very soluble and/or compound's industrial usage not related to site history (edit as required);

**chromium in chromium(III) compounds {chromium(III) oxide (worst case)}**

Reasonable case species based on hazard statements/molecular weight. Industrial sources include: tanning, pigment in paint, inks and glass (edit as required);

**chromium in chromium(VI) compounds {chromium(VI) oxide}**

Worst case CLP species based on hazard statements/molecular weight. Industrial sources include: production stainless steel, electroplating, wood preservation, anti-corrosion agents or coatings, pigments (edit as required);

**copper {dicopper oxide; copper (I) oxide}**

Reasonable case CLP species based on hazard statements/molecular weight and insolubility in water. Industrial sources include: oxidised copper metal, brake pads, pigments, antifouling paints, fungicide. (edit as required) Worse case copper sulphate is very soluble and likely to have been leached away if ever present and/or not enough soluble sulphate detected. (edit as required);

**lead {lead chromate}**

Worst case CLP species based on hazard statements/molecular weight (edit as required);

**mercury {mercury dichloride}**

Worst case CLP species based on hazard statements/molecular weight (edit as required);

**nickel {nickel chromate}**

Worst case CLP species based on hazard statements/molecular weight (edit as required);

**selenium {selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex}**

Harmonised group entry used as most reasonable case. Pigment cadmium sulphoselenide not likely to be present in this soil. No evidence for the other CLP entries: sodium selenite, nickel II selenite and nickel selenide, to be present in this soil. (edit as required);

**vanadium {divanadium pentaoxide; vanadium pentoxide}**

Applicable for this waste stream

**zinc {zinc chromate}**

Worst case CLP species based on hazard statements/molecular weight (edit as required);

**cyanides {salts of hydrogen cyanide with the exception of complex cyanides such as ferrocyanides, ferricyanides and mercuric oxycyanide and those specified elsewhere in this Annex}**

Harmonised group entry used as most reasonable case as complex cyanides and those specified elsewhere in the annex are not likely to be present in this soil: [Note conversion factor based on a worst case compound: sodium cyanide] (edit as required);

**Appendix C: Version**

HazWasteOnline Classification Engine: WM3 1st Edition v1.1, May 2018  
 HazWasteOnline Classification Engine Version: 2020.315.4525.8798 (10 Nov 2020)  
 HazWasteOnline Database: 2020.315.4525.8798 (10 Nov 2020)

This classification utilises the following guidance and legislation:

- WM3 v1.1 - Waste Classification** - 1st Edition v1.1 - May 2018
- CLP Regulation** - Regulation 1272/2008/EC of 16 December 2008
- 1st ATP** - Regulation 790/2009/EC of 10 August 2009
- 2nd ATP** - Regulation 286/2011/EC of 10 March 2011
- 3rd ATP** - Regulation 618/2012/EU of 10 July 2012
- 4th ATP** - Regulation 487/2013/EU of 8 May 2013
- Correction to 1st ATP** - Regulation 758/2013/EU of 7 August 2013
- 5th ATP** - Regulation 944/2013/EU of 2 October 2013
- 6th ATP** - Regulation 605/2014/EU of 5 June 2014
- WFD Annex III replacement** - Regulation 1357/2014/EU of 18 December 2014
- Revised List of Waste 2014** - Decision 2014/955/EU of 18 December 2014
- 7th ATP** - Regulation 2015/1221/EU of 24 July 2015
- 8th ATP** - Regulation (EU) 2016/918 of 19 May 2016
- 9th ATP** - Regulation (EU) 2016/1179 of 19 July 2016
- 10th ATP** - Regulation (EU) 2017/776 of 4 May 2017
- HP14 amendment** - Regulation (EU) 2017/997 of 8 June 2017
- 13th ATP** - Regulation (EU) 2018/1480 of 4 October 2018
- 14th ATP** - Regulation (EU) 2020/217 of 4 October 2019
- 15th ATP** - Regulation (EU) 2020/1182 of 19 May 2020
- POPs Regulation 2019** - Regulation (EU) 2019/1021 of 20 June 2019



GEOSPHERE ENVIRONMENTAL

**Ec**

**Ecology.**

**Fr**

**Flood Risk.**

**Ge**

**Geotechnical.**

**En**

**Environmental.**

**Kw**

**Knotweed.**

**GEOSPHERE ENVIRONMENTAL LTD**

Brightwell Barns, Ipswich Road, Brightwell, Suffolk, IP10 0BJ

T: 01603 298076 | 01473 353519 | E: [info@geosphere-environmental.co.uk](mailto:info@geosphere-environmental.co.uk) | W: [geosphere-environmental.co.uk](http://geosphere-environmental.co.uk)