

KEY

- Planning red line boundary
- Existing building to be demolished
- Proposed buildings
- Phase 2
- Basement outline
- Block/Terrace Letter
- Stores
- Units


Notes:
Do not scale. All dimensions are in millimetres unless otherwise stated. This drawing should be read in conjunction with all relevant project information and contract documentation. All dimensions to be checked prior to fabrication and/or commencement of works. All works to comply with all relevant legal standards, building regulations and warranty provider requirements. Report any discrepancies, if in doubt ask.


Revisions:	Rev	Status	Date	Description	Dim	Chkd
	001	A3	12/04/22	Planning Issue		JB / CD

Client Name:		Hill Residential	
Project Name:		Ham Close Regeneration	
Drawing Name:		Proposed Phase 2 Masterplan	
Drawing Number:	HCR-BPTW-501-00-DR-A-0115	Rev:	CO1
Project No:	21-090	Status:	A3
RIBA Stage:	03	Drawn By:	JB
Scale:	1:500 @ A1		

PLANNING ISSUE

40 Norman Road,
Greenwich, London
SE10 9GX
t: 020 8293 5175
bptw.co.uk





KEY

- Planning red line boundary
- Existing building to be demolished
- Proposed buildings
- Phase 3
- Basement outline
- A Block/Terrace Letter
- 4 Stores
- 12 Units


Notes:
Do not scale. All dimensions are in millimetres unless otherwise stated. This drawing should be read in conjunction with all relevant project information and contract documentation. All dimensions to be checked prior to fabrication and/or commencement of works. All works to comply with all relevant legal standards, building regulations and warranty provider requirements. Report any discrepancies, if in doubt ask.

Revisions:	Rev	Status	Date	Description	Dim	Chkd
	001	A3	12/04/22	Planning Issue		JB / CD

Client Name:		Hill Residential	
Project Name:		Ham Close Regeneration	
Drawing Name:		Proposed Phase 3 Masterplan	
Drawing Number:	HCR-BPTW-501-00-DR-A-0116	Rev:	CO1
Project No:	21-090	Status:	A3
RIBA Stage:	03	Drawn By:	JB
Scale:	1:500 @ A1		

PLANNING ISSUE

40 Norman Road,
Greenwich, London
SE10 9OX
t. 020 8293 5175
bptw.co.uk



Phase 2 Car Park V/M
1 : 100



Location Plan
1 : 2000



Notes:
Do not scale. All dimensions are in millimetres unless otherwise stated. This drawing should be read in conjunction with all relevant project information and contract documentation. All dimensions to be checked prior to fabrication and/or commencement of works. All works to comply with all relevant legal standards, building regulations and warranty provider requirements. Report any discrepancies, if in doubt ask.


Rev	Status	Date	Description	Drn	Chkd
C01	A3	26.04.22	Planning Issue	JB	CD

Client Name:		Hill Residential	
Project Name:		Ham Close Regeneration	
Drawing Name:		Phase 2 Basement Section	
Drawing Number:	Rev:	Status:	
HCR-BPTW-S01-ZZ-DR-A-2241	C01	A3	
Project No:	RIBA Stage:	Drawn By:	Scale:
21-090	3	JB	1:100 @ A1

PLANNING ISSUE

40 Norman Road,
Greenwich, London
SE10 9GX
t 020 8293 5175
bptw.co.uk






1 Phase 3 Basement Section E/C
1:100



Location Plan
1:2000



2 Phase 3 Cycle Access Lift Section
1:100



Notes:
Do not scale. All dimensions are in millimetres unless otherwise stated. This drawing should be read in conjunction with all relevant project information and contract documentation. All dimensions to be checked prior to fabrication and/or commencement of works. All works to comply with all relevant legal standards, building regulations and warranty provider requirements. Report any discrepancies, if in doubt ask.


Revisions	Rev	Status	Date	Description	Rev	Drn	Chkd
CD1	A3		26.04.22	Planning Issue		JB	CD

Client Name:		Hill Residential	
Project Name:		Ham Close Regeneration	
Drawing Name:		Phase 3 Basement Section	
Drawing Number:	HCR-BPTW-S01-ZZ-DR-A-2242	Rev:	C01
Project No:	21-090	Status:	A3
RIBA Stage:	3	Scale:	1:100 @ A1
Drawn By:	JB		


PLANNING ISSUE

40 Norman Road,
Greenwich, London
SE10 9GX
t 020 8293 5175
bptw.co.uk







1 **Basement Section Phase 2 Ramp**
1:50




2 **Basement Section Phase 3 Ramp**
1:50




Location Plan
1:2500



Phase 2 Basement Entrance Ramp Plan
1:100



Phase 3 Basement Entrance Ramp Plan
1:100



Notes:
Do not scale. All dimensions are in millimetres unless otherwise stated. This drawing should be read in conjunction with all relevant project information and contract documentation. All dimensions to be checked prior to fabrication and/or commencement of works. All works to comply with all relevant legal standards, building regulations and warranty provider requirements. Report any discrepancies, if in doubt ask.


Rev	Status	Date	Description	Drn	Chkd
C01	A3	26.04.22	Planning Issue	JB	CD

Client Name: Hill Residential					
Project Name: Ham Close Regeneration					
Drawing Name: Basement Entrance Ramp Details					
Drawing Number: HCR-BPTW-S01-ZZ-DR-A-2243	Rev: C01	Status: A3			
Project No: 21-090	RIBA Stage: 3	Drawn By: JB	Scale: As Indicated @ A1		


PLANNING ISSUE

40 Norman Road,
Greenwich, London
SE10 9GX
t 020 8293 5175
bptw.co.uk






Soft landscaping Indicative Detail
1:50



Hard landscaping Indicative Detail
1:50



Basement Ventilation Turret Detail
1:50

Notes:
Do not scale. All dimensions are in millimetres unless otherwise stated. This drawing should be read in conjunction with all relevant project information and contract documentation. All dimensions to be checked prior to fabrication and/or commencement of works. All works to comply with all relevant legal standards, building regulations and warranty provider requirements. Report any discrepancies, if in doubt ask.

Rev	Status	Date	Description	Drn	Chkd
CD1	A3	26.04.22	Planning Issue	JB	CD

Client Name: Hill Residential					
Project Name: Ham Close Regeneration					
Drawing Name: Indicative Basement Details					
Drawing Number: HCR-BPTW-S01-ZZ-DR-A-2244		Rev: C01		Status: A3	
Project No: 21-090	RIBA Stage: 3	Drawn By: JB	Scale: 1:50 @ A1		

PLANNING ISSUE

40 Norman Road,
Greenwich, London
SE10 9GX
t 020 8293 5175
bptw.co.uk



APPENDIX B – GROUND INVESTIGATION DATA



Geo-Environmental Report

Ashburnham Rd, Richmond, TW10 7PB
for:

Hill Residential Ltd



Contact Details:

Enzygo Geoenvironmental Ltd.
 The Byre
 Woodend Lane
 Cromhall
 Gloucestershire
 GL12 8AA

tel: 01454 269237
 fax: 01454 269760
 email: steve.rhodes@enzygo.com
 www: enzygo.com

Geo-Environmental Report

Project:	Ashburnham Rd, Richmond, TW10 7PB
For:	Hill Residential Ltd
Ref:	CRM.1027.087.GE.R.003.
Status:	Revision C
Date:	December 2021
Author:	Steve Rhodes Director
Reviewer:	Richard Hamilton Director of Geoenvironmental

Executive Summary

Proposed Development

This document is a report of this survey and has been produced to support a planning submission for the site which seeks the demolition of the existing buildings on-site and phased mixed-use development comprising 452 residential homes (Class C3) up to six storeys, a Community/Leisure Facility (Class F2) of up to three storeys in height, a “MakersLab” (sui generis) of up to two storeys together with basement car parking and site wide landscaping.

Investigation

Site investigation, desk study and monitoring visits were undertaken by Enzygo Geoenvironmental Ltd.

Ground Conditions

Ground Conditions comprise Made Ground over firm clay and loose becoming dense with depth sand and gravel. Shallow groundwater was not encountered.

Contamination

Elevated PAH, Lead and Arsenic was encountered together with asbestos. Remediation and management procedures are proposed.

Foundations

Spread foundations should be suitable for domestic houses but piled foundations are likely to be required for apartments.

Pavement Design

An equilibrium CBR of 3% is recommended. Soils are not considered to be frost susceptible.

Buried Concrete

It is recommended that Class AC-1s conditions of Special Digest 1 are used.

Ground Gas and Radon

No radon risk has been identified. No significant ground gas has been measured.

TABLE OF CONTENTS

Executive Summary i

1.0 INTRODUCTION 5

Background 5

Proposed Development 5

Objectives..... 5

Risk Classification 5

2.0 SITE SETTING 7

Site Description 7

Current Site Description 7

Surrounding Area 7

3.0 SITE HISTORY 9

4.0 ENVIRONMENTAL SETTING 10

Ground Conditions 10

Groundwater 10

Coal Mining 10

Cavities 10

Hydrology..... 10

Radon Risk Potential 11

Natural Hazards Finding 11

Sensitive Land Uses..... 11

Environmental Sensitivity 11

Industrial Land Uses..... 12

Landfill Sites and Waste Treatment Sites 12

Planning Records..... 12

5.0	PREVIOUS REPORTS	13
6.0	PRELIMINARY CONCEPTUAL MODEL	14
7.0	SITE INVESTIGATION	15
	<i>General</i>	15
	<i>Site Works</i>	15
	<i>Monitoring</i>	16
	<i>Laboratory Testing</i>	16
8.0	GROUND AND GROUNDWATER CONDITIONS.....	17
	<i>Summary of Ground and Groundwater Conditions</i>	17
	<i>Made Ground</i>	17
	<i>London Clay</i>	17
	<i>Visual and Olfactory Evidence of Contamination</i>	18
	<i>Soil Strength</i>	18
	<i>Groundwater</i>	18
	<i>Ground Gas</i>	18
	<i>Soakaways</i>	19
9.0	CONTAMINATION ASSESSMENT.....	20
	<i>General</i>	20
	<i>Human Health</i>	20
	<i>Controlled Waters</i>	21
	<i>Ground Gas</i>	21
	<i>Revised Conceptual Model</i>	22
	<i>Waste Classification</i>	25
10.0	GEOTECHNICAL ASSESSMENT.....	26
	<i>Proposed Development</i>	26
	<i>Ground Conditions</i>	26

<i>Site Preparation</i>	26
<i>Foundations</i>	26
<i>Ground Floor Slab</i>	27
<i>Pavement Construction</i>	27
<i>Drainage</i>	28
<i>Buried Concrete</i>	28
<i>Excavation and Materials Re-Use</i>	28
Drawings	29
Appendix A – Desk Study Report	30
Appendix B – Exploratory Hole Records	31
Appendix C – Chemical Testing	32
Appendix D – Geotechnical Testing	37

1.0 INTRODUCTION

Background

- 1.1 Enzygo Geoenvironmental Limited has been commissioned to prepare a Geo-Environmental Report for a site at Ashburnham Rd, Richmond, TW10 7PB.

Proposed Development

- 1.2 This document is a report of this survey and has been produced to support a planning submission for the site which seeks the demolition of the existing buildings on-site and phased mixed-use development comprising 452 residential homes (Class C3) up to six storeys, a Community/Leisure Facility (Class F2) of up to three storeys in height, a “MakersLab” (sui generis) of up to two storeys together with basement car parking and site wide landscaping.

Objectives

- 1.3 The objectives of the study are to:
- Review an existing Phase I desk study, a copy of which is included in Appendix A;
 - Undertake a ground investigation;
 - Assess the implications of any potential environmental risks, liabilities and development constraints associated with the site in relation to the future use of the site and in relation to off-site receptors; and
 - Provide a factual and interpretative report relating to the desk study and site investigations. Provide a revised conceptual model and recommendations on any potential development issues and mitigation measures, where appropriate.
 - Provide geotechnical recommendations in relation to foundations and infrastructure.

Risk Classification

- 1.4 Enzygo Geoenvironmental has utilised the available information, together with our experience to assess the likely risks to development from land quality issues. Definitions of the risk terms used are provided on the following table.

Risk	Description
Negligible	No contamination risk has been identified which is likely to affect development.
Low	No significant contaminated land risks have been encountered affecting development and a low risk that remediation will be required.
Low-Moderate	There are unlikely to be significant contaminated land issue associated with the site which will adversely affect its re-development. However, minor or localised contamination may be present requiring remediation. Remediation should be possible under a discovery strategy and with a call out service.
Moderate	Some potential contaminated land risks have been encountered or identified which may affect re- development. The risks identified are unlikely to affect the entire site or preclude development. Remediation is considered feasible as part of the development process and no further investigation is considered necessary.
Moderate-High	Some potentially significant contaminated land risks have been identified at the property that requires remediation. It is recommended that a separate remedial methodology is prepared supported by a site-specific risk assessment
High	Significant potential contaminated land risks have been identified and remediation is required supported by further intrusive ground investigation, risk assessment and remedial design.

1.5 Where adverse risks from ground instability are identified these are discussed within the report.

2.0 SITE SETTING

Site Description

Item	Description
Site Address	Ashburnham Rd, Richmond, TW10 7PB
National Grid Reference	Site centred at National Grid Reference TQ0030585 and Ordnance Survey Co-ordinates 550309, 158566.
Site Area	4.7 Ha

Current Site Description

- 2.1 The following site description has been compiled from the site inspection undertaken by Enzygo Geoenvironmental staff, together with current maps, aerial photographs and a topographical survey.
- 2.2 The site comprises existing residential buildings arranged in five storey blocks, four storey deck access flats and three storey 'T' shaped blocks. The public realm consists of large areas of surface parking and amenity grassland with scattered trees. The Youth Centre and associated car park occupies a central location on the site. Ham Village Green sits at the eastern edge of the site. The site is bound by Woodville Road to the north, Wiggins Lane and Ham Street to the east, Ham Clinic and Ashburnham Road to the south and St Richard's C of E Primary School playing fields and the children's garden pre-school to the west.
- 2.3 Internal roadways, parking areas and lock-up garages were present between the apartment blocks.
- 2.4 Within the southern area of the site an amenity hall, clinic and estate office are present with associated parking.
- 2.5 The eastern area of the site is open land vegetated with grass and including footpaths.
- 2.6 An electricity sub station is present on the western boundary. This appears to be of modern construction with no evidence of leakage. The sub-station is not considered a significant risk.

Surrounding Area

- 2.7 The surrounding land uses are summarised as follows:

Direction	Land Use

South	Ashburnham Road with residential development beyond.
East	Wiggins Lan with residential development beyond.
West	School and open space.
North	Woodville Road with residential development beyond.

2.8 No significant sources of potential contamination were noted on or adjacent to the site.

3.0 SITE HISTORY

- 3.1 A review of historical Ordnance Survey maps and information pertinent to the site obtained from the existing desk study report is summarised below:
- 3.2 The site is shown as open land prior to construction of a farm in the eastern part of the site by 1868.
- 3.3 The site was redeveloped for residential use by 1947. A ruin is shown in the eastern part of the site by 1959 which is likely to be from bomb damage.
- 3.4 The current residential development is shown by 1983 and with open space in the east.
- 3.5 There is the potential for Made Ground associated with historic buildings, demolished prior to the current development. No other significant potential sources identified on or near to the site.
- 3.6 No significant off-site contamination sources are identified.
- 3.7 A low Unexploded Ordnance Risk was identified in relation to ground investigation works.

4.0 ENVIRONMENTAL SETTING

Ground Conditions

- 4.1 The British Geological Survey (BGS) indicates that the site is underlain by the following geological sequence:

Geological Unit	Type	Description	Aquifer Classification
Drift	Kempton Park Gravels	Sand and Gravel	Secondary A
Solid	London Clay	Clay	Unproductive

- 4.2 There are no records of Made Ground below the site. Made Ground is shown 41m south west. Given the distance from the site this is not considered a significant risk.
- 4.3 There are no records of landslips on the site.
- 4.4 BGS borehole records on site show 0.6m of Made ground over gravel and with London Clay encountered at depths of 6m.

Groundwater

- 4.5 The Desk Study Report shows that the site is not within a Source Protection Zone.
- 4.6 BGS records show that the site is at potential risk of groundwater flooding.

Coal Mining

- 4.7 No historical or current coal mining extraction has been identified within 1000m of the site.

Non Coal Mining

- 4.8 No other mining activity has been identified within 1000m of the site.

Cavities

- 4.9 No natural cavities or solution features are identified on site.

Hydrology

- 4.10 There are no water courses on the site.

4.11 Environment Agency records show that the site is not within an Environment Agency Flood Zone.

Radon Risk Potential

4.12 The Groundsure Geolnsight Report indicates that the site is not within a Radon Affected Area. No radon protective measures are necessary in the construction of new dwellings.

Natural Hazards Finding

4.13 BGS information presented within the Groundsure Geoinsight report identifies the following:

Hazard	Risk Designation (Groundsure)
Coal Mining.	None Identified.
Collapsible Ground.	Very Low.
Compressible Ground.	Very Low.
Ground Dissolution.	Very Low.
Landslide.	Very Low.
Running Sand.	Very Low.
Swelling / Shrinking Clay.	Very Low.

4.14 No significant geotechnical risks are identified.

Sensitive Land Uses

4.15 There are no sites of special interest on or surrounding the site.

4.16 English Heritage has not identified any listed buildings or scheduled ancient monuments on or close to the site. No sensitive geology has been identified at the site.

Environmental Sensitivity

4.17 Overall the site is currently considered to be of low/moderate sensitivity due to the following:

- The underlying stratum is classified as a Secondary A Aquifer;
- Not within a source protection zone;
- No surface water courses on or adjacent to the site; and
- No sensitive ecology is noted adjacent to or on the site.

- 4.18 The proposed end use of the site is residential and as such future sensitivity will be high for end users.

Industrial Land Uses

- 4.19 No significant current industrial activities are identified on or adjacent to the site.

Landfill Sites and Waste Treatment Sites

- 4.20 There are no active or historic landfills within 250m of the site.

Planning Records

- 4.21 A review of London Borough of Richmond's planning history shows no relevant information for the site.

5.0 PREVIOUS REPORTS

5.1 No previous ground investigation reports were provided.

6.0 PRELIMINARY CONCEPTUAL MODEL

6.1 Based on the desk study information the following Preliminary Conceptual Model has been prepared:

Source	Location	Exposure Pathway	Potential Receptor	Probability of Exposure	Details
Human Health					
Asbestos, Hydrocarbon and metals.	Unforeseen Contamination.	Ingestion dermal and inhalation.	Construction Workers.	Dismissed.	Normal site management practices and PPE will address risk.
			Site users.	Negligible.	No source identified.
Asbestos, Hydrocarbon and metals.	Made Ground.	Ingestion dermal and inhalation.	Construction Workers.	Dismissed.	Normal PPE will address risk.
			Site users.	Very Low.	If present can easily be addressed through development.
Hydrocarbon and metals.	Potential migration from off-site source.	Ingestion dermal and inhalation.	Construction Workers.	Dismissed.	No significant off site sources identified.
			Site users.		
Ground Gas.	Historic Landfill.	Inhalation & Explosive.	Construction Workers.	Dismissed.	No source identified.
			Site users.		
	Potential Made Ground.	Inhalation & Explosive.	Construction Workers.	Dismissed.	No significant source identified.
			Site users.		
Groundwater					
Hydrocarbon and metals.	Potential spillage on site.	Vertical Migration.	Groundwater.	Dismissed.	No source identified.
Surface Water					
Hydrocarbon and metals.	Potential spillage on site.	Horizontal Migration.	River Network.	Dismissed.	No source or credible receptor.
Environmental Receptors					
On site contaminants		Ingestion dermal and inhalation.	Ecology.	Dismissed.	No sensitive ecology designation.
		Direct.	Archaeology.	Dismissed.	None present.
		Direct.	Geology.	Dismissed.	No sensitive receptor present.
		Phytotoxic.	Woodland.	Dismissed.	None present.
		Phytotoxic.	Crops.	Dismissed.	No source identified.
		Ingestion dermal and inhalation.	Livestock.	Dismissed.	No source identified.
Building Services					
On site contaminants		Direct.	Historic Buildings.	Dismissed.	None present.
		Direct.	Proposed Buildings.	Dismissed.	No source identified.
		Permeate into pipework.	Water Pipes.	Dismissed.	No significant source identified.

6.2 There is a very low risk from Made Ground, including former buildings which will be investigated. Should contamination be present this can easily be addressed through development. No other significant risks are identified.

7.0 SITE INVESTIGATION

General

- 7.1 A ground investigation was undertaken based on the findings of the desk study. The locations of the exploratory holes are shown on Drawing CRM.1027.087.GE.D.001.

Site Works

- 7.2 The site investigation works comprised window sampler holes (WS1 to WS18) advanced between 27th and 29th April 2021 and six deep boreholes (BH1 to BH6) advanced between 16th and 19th August 2021.
- 7.3 A subsequent visit was undertaken during October 2021 with six window sampler holes (WS101 to WS106) being advanced on 25th October 2021 in areas of car park where access was not previously permitted. Six soakaway tests (SA1 to SA6) were undertaken on 26th and 27th October 2021.
- 7.4 Exploratory hole locations were determined to provide general coverage of the site within areas where access was permitted by the land owner. The investigation works are summarised in the table below:

Rational	Exploratory Holes	Notes
Site Coverage.	WS1 to WS18.	Across site.
Car park areas	WS101 to WS106	Car parks
Soakaways	SA1 to SA6	To assess viability of soil infiltration.
Monitoring.	WS5 WS6 WS7 WS9 WS14 WS16 & WS18.	Installations.
Deep foundations.	BH1 to BH6.	Deep boreholes.

- 7.5 Strength of soils were assessed using Standard Penetration Tests (SPT). The results of which are included on the borehole logs presented in Appendix B.
- 7.6 Representative soil samples were collected for chemical and geotechnical testing. Soil samples destined for chemical analysis were collected in appropriate containers provided by the analytical laboratory. Samples were stored in cool boxes prior to dispatch to the laboratory for analysis. All samples were collected using appropriate sampling equipment that was cleaned at each sampling location.
- 7.7 Generally samples were collected from Made Ground, which may contain potential inclusions of contaminating materials and materials displaying evidence of potential contamination.

7.8 In the absence of any evidence of contamination samples were collected near surface as this material is more likely to be contaminated by surface spillages and also will potentially be in contact with future residents.

Monitoring

7.9 Return visits to monitor groundwater levels were undertaken and during these visits ground gas was also measured.

Laboratory Testing

7.10 Samples for geotechnical testing were sent to the laboratories of I2, which is UKAS accredited, for the following analysis:

- California Bearing Ratio(CBR) tests undertaken on re-compacted samples
- Atterberg Limits Determinations;
- Moisture Content; and
- Soluble sulphate and pH.

7.11 Samples for chemical analysis were sent to the laboratories of The I2 Ltd who are UKAS and MCERTS accredited. Samples were tested for the CLEA metal suite, pH, sulphate, cyanide, phenols, speciated Polycyclic Aromatic Hydrocarbons (PAH), organic carbon, banded Total Petroleum Hydrocarbon (TPH), asbestos quantification, and two stage WAC tests.

8.0 GROUND AND GROUNDWATER CONDITIONS

Summary of Ground and Groundwater Conditions

8.1 The investigations undertaken by Enzygo Geoenvironmental Ltd identify the following strata:

Strata	Summary Description	Thickness (m)
Made Ground	Brown and grey clayey fine sand and flint gravel with fragments of brick concrete and ash.	0.4 to 1.2
Kempton Park Gravels	Firm and stiff brown clay and gravelly clay.	0 to 0.9
	Loose becoming medium dense and dense with depth brown sand and flint gravel.	3.8 to 5.3
London Clay	Stiff grey brown silty clay with occasional claystone gravel.	>20
Groundwater	Seepages	2.2m to 4.3 bgl.

8.2 Details of the ground and groundwater conditions encountered are given on the exploratory hole records included in Appendix B and are summarised in the sections below:

Made Ground

8.3 Made Ground was encountered across the site comprising brown and grey clayey fine sand and flint gravel with fragments of brick concrete and ash.

8.4 This material is consistent with typical Made Ground comprising natural soils with anthropogenic inclusions associated with demolition and removal of historic buildings

Kempton Park Gravels

8.5 The Kempton Park Gravels were encountered at depths of between 0.4m and 1.2m below ground level (bgl). The upper horizon of the Kempton Park Gravels generally comprised firm and stiff brown clay and gravelly clay.

8.6 The clay layer was underlain by loose becoming medium dense and dense with depth brown sand and flint gravel. The granular Kempton Park Gravels were encountered at depths of between 0.4m and 1.5m bgl.

London Clay

8.7 The London Clay was only encountered in deep boreholes and comprised stiff grey brown silty clay with occasional claystone gravel.

Visual and Olfactory Evidence of Contamination

- 8.8 Potential asbestos fragments were encountered in Window Sampler boreholes WS6 and WS8. No other visual or olfactory evidence of contamination was encountered during the site works. Samples of potential asbestos were collected for laboratory testing and this is discussed in Section 9.

Soil Strength

- 8.9 Undrained shear strength of cohesive Kempton Park Gravels were calculated using the correlations of Stroud and Butler. These show the undrained shear strength values to vary from 45kN/m² to 100kN/m² at 1m bgl. Granular soils are noted to be loose medium dense and dense with depth. SPT values increasing 7 at 1m bgl to over 50 at 4m bgl being recorded.
- 8.10 London Clay was noted to have undrained shear strength values increasing from 60kN/m² at 6m to 170kN/m² at 25m bgl.

Groundwater

- 8.11 Groundwater was encountered as seepages at depths of between 2.2m to 4.3 bgl from within the Kempton Park Gravels. The depth to groundwater measured during the monitoring visit is summarised on the table below:

Exploratory Hole	Depth m(bgl)					
	12.5.21	19.5.21	2.6.21	16.6.21	30.6.21	14.7.21
WS5	Dry	Dry	Dry	Dry	Dry	Dry
WS6	Dry	Dry	Dry	Dry	Dry	Dry
WS7	Dry	Dry	Dry	Dry	Dry	Dry
WS9	Dry	Dry	Dry	Dry	Dry	Dry
WS14	Dry	Dry	Dry	Dry	Dry	Dry
WS16	Dry	Dry	Dry	Dry	Dry	Dry
WS18	Dry	Dry	Dry	Dry	Dry	Dry

Ground Gas

- 8.12 Ground gas was monitored during the return visit to monitor groundwater levels and the results are summarised on the table below:

Exploratory Hole	Atmos pressure (Mb)	Flow (l/hr)	CH ₄		CO ₂		O ₂
			Concentration (%)	GSV (l/hr)	Concentration (%)	GSV (l/hr)	Concentration (%)
12.5.21							
WS5	997	<0.1	<0.1	<0.0001	1.8	<0.0018	19.5
WS6	997	<0.1	<0.1	<0.0001	1.8	<0.0018	19.4
WS7	997	<0.1	<0.1	<0.0001	1.5	<0.0015	19.1
WS9	997	<0.1	<0.1	<0.0001	1.2	<0.0012	19.3

WS14	997	<0.1	<0.1	<0.0001	1.6	<0.0016	18.9
WS16	997	<0.1	<0.1	<0.0001	0.8	<0.0008	18.8
19.5.21							
WS5	1017	<0.1	<0.1	<0.0001	1.9	<0.0019	18.1
WS6	1017	<0.1	<0.1	<0.0001	1.1	<0.0011	18.8
WS7	1017	<0.1	<0.1	<0.0001	2.0	<0.0020	18.0
WS9	1017	<0.1	<0.1	<0.0001	1.3	<0.0013	19.6
WS14	1017	<0.1	<0.1	<0.0001	1.7	<0.0017	18.2
WS16	1017	<0.1	<0.1	<0.0001	1.4	<0.0014	18.9
WS18	1017	<0.1	<0.1	<0.0001	1.1	<0.0011	19.6
2.6.21							
WS5	1014	<0.1	<0.1	<0.0001	2.1	<0.0021	18.2
WS6	1014	<0.1	<0.1	<0.0001	1.2	<0.0012	18.6
WS7	1014	<0.1	<0.1	<0.0001	1.7	<0.0017	18.5
WS9	1014	<0.1	<0.1	<0.0001	1.2	<0.0012	19.1
WS14	1014	<0.1	<0.1	<0.0001	1.6	<0.0016	18.8
WS16	1014	<0.1	<0.1	<0.0001	1.5	<0.0015	18.7
WS18	1014	<0.1	<0.1	<0.0001	1.0	<0.0010	19.7
16.6.21							
WS5	1009	<0.1	<0.1	<0.0001	2.1	<0.0023	18.3
WS6	1009	<0.1	<0.1	<0.0001	1.4	<0.0014	18.7
WS7	1009	<0.1	<0.1	<0.0001	1.5	<0.0015	18.8
WS9	1009	<0.1	<0.1	<0.0001	1.3	<0.0013	19.2
WS14	1009	<0.1	<0.1	<0.0001	1.6	<0.0016	18.9
WS16	1009	<0.1	<0.1	<0.0001	1.7	<0.0017	18.5
WS18	1009	<0.1	<0.1	<0.0001	0.7	<0.0007	19.9
30.6.21							
WS5	1015	<0.1	<0.1	<0.0001	1.8	<0.0018	18.2
WS6	1015	<0.1	<0.1	<0.0001	1.3	<0.0013	18.9
WS7	1015	<0.1	<0.1	<0.0001	1.6	<0.0016	18.7
WS9	1015	<0.1	<0.1	<0.0001	1.4	<0.0014	18.9
WS14	1015	<0.1	<0.1	<0.0001	1.5	<0.0015	19.0
WS16	1015	<0.1	<0.1	<0.0001	1.6	<0.0016	18.8
WS18	1015	<0.1	<0.1	<0.0001	1.0	<0.0010	19.2
14.7.21							
WS5	1017	<0.1	<0.1	<0.0001	1.9	<0.0019	18.3
WS6	1017	<0.1	<0.1	<0.0001	1.5	<0.0015	18.9
WS7	1017	<0.1	<0.1	<0.0001	1.6	<0.0016	18.7
WS9	1017	<0.1	<0.1	<0.0001	1.2	<0.0012	18.7
WS14	1017	<0.1	<0.1	<0.0001	1.7	<0.0017	18.8
WS16	1017	<0.1	<0.1	<0.0001	0.9	<0.0009	19.3
WS18	1017	<0.1	<0.1	<0.0001	0.8	<0.0008	19.5

8.13 No significant ground gas has been measured.

Soakaways

8.14 Results of the soakaway testing is provided on the table below:

Soakaway	Depth (m bgl)	Test No	Soil Infiltration Rate	
SA 1	2.0	Test 1	Insufficient soakage	
SA 2	2.0	Test 1	9.1E ⁻⁶ m/s	
SA 3	2.0	Test 1	Insufficient soakage	
SA4	2.1	Test 1	5.6E ⁻⁶ m/s	
SA5	2.0	Test 1	Insufficient soakage	
SA6	2.0	Test 1	7.7E ⁻⁴ m/s	Extrapolated

9.0 CONTAMINATION ASSESSMENT

General

- 9.1 A Tier I risk assessment has been undertaken using available and current screening values for human health and where appropriate controlled waters. The risk assessment is undertaken based on the findings of the preliminary conceptual model presented in Section 6. Based on the contamination testing and Tier I assessment a revised Conceptual Model has been prepared, which is presented later in this section.
- 9.2 Where significant risks are identified remedial measures are recommended.

Human Health

- 9.3 Assessment of the risks to human health has been undertaken by comparing the soil quality data with reference values obtained from the Contaminated Land Exposure Assessment (CLEA), Soil Guideline Values (SGV) and General Acceptance Criteria (GAC) published by LQM and derived in consultation with the Chartered Institute of Environmental Health. The LQM/CIEH S4ULs values are used and summary tables of the reference values are included in Appendix C.
- 9.4 Where an exceedance is identified the risk is assessed by considering the sensitivity of the proposed development and the potential pathway. The proposed development comprises conventional residential houses with domestic gardens.
- 9.5 The GAC values for residential use with plant uptake are used as the development includes domestic properties.
- 9.6 The soil quality shows exceedances of the GAC values for the following contaminants.

Exploratory Hole	Determinant	Concentration (mg/kg)	
		GAC	Soil
WS2 0.2m	Asbestos	Absent	0.006%
	Arsenic	37	40
WS6 0.4m	Asbestos	Absent	<0.001%
WS8 0.4m	Asbestos	Absent	3.127%
	Benzo(b)fluoranthene	2.6	3.4
	Benzo(a)pyrene	2.2	2.6
	Dibenzo(a,h)anthracene	0.24	0.53
	Lead	200	320
WS1 0.4m	Benzo(b)fluoranthene	2.6	8.1
	Benzo(a)pyrene	2.2	7.0
	Dibenzo(a,h)anthracene	0.24	1.1
	Lead	200	310
WS10 0.4m	Lead	200	250

WS102 @ 0.3m	Lead	200	1400
WS104 @ 0.3m	Lead	200	510
WS105 @ 0.35m	Lead	200	320

9.7 No other exceedances were recorded.

Controlled Waters

9.8 Risk to groundwater resources is dismissed due to the absence of any significant source of mobile contamination.

9.9 The risk to surface waters risk has been dismissed within the Initial Conceptual Model. No new risks are identified.

Ground Gas

9.10 Following the guidance provided in Section 3 of CIRIA C665 an initial assessment is undertaken to determine if there are any significant sources of potential ground gas. Such sources include landfills, organic clays and made ground incorporating putrescible materials such as rags, paper and wood. Where no significant source is identified no further assessment is necessary.

9.11 This approach is further supported by supplementary guidance given in RB17, published by CL:AIRE which confirms that gas monitoring is not generally required on sites where Made Ground is less than 5m thick and with low organic matter content or on natural soils such as alluvial clays and Chalk as the ground gas sources are not considered significant. The supplementary guidance given in RB17 also takes account of the current requirements for sealing of floor slabs and substructures to meet air tightness requirements under Part L of the Building Regulations which were not considered in CIRIA C665. The advice given in RB17 is consistent with CIRIA C665 and the Local Authority Guide to Ground Gas published by CIEH.

9.12 Where significant potential risk from ground gas is identified from the Initial Conceptual Model and the intrusive ground investigation works ground gas monitoring is undertaken and the results of the monitoring are compared against the Gas Screening Values given in CIRIA Report 665. From this the Characteristic Situation is identified and remedial measures proposed.

9.13 When assessing the risk and type of remedial measures appropriate consideration is given to the likely construction of the development, the nature of the gas posing a risk and the nature of the likely source. The use of engineering judgement when determining risk from

ground gas is consistent with the recommendations given in CIRIA C665 using a pollutant linkage model.

9.14 Gas monitoring was undertaken during return visits which has not recorded elevated concentrations of Methane and no flow. Based on the gas monitoring undertaken the Gas Screening Value is less than 0.07l/hr and therefore falls within Characteristic Situation 1 (CS1).

9.15 Additional monitoring is being undertaken.

Revised Conceptual Model

9.16 The Initial Conceptual Model presented in Section 6 has been revised based on the findings of the ground investigation and the revised Conceptual Model is presented below:

Source	Location	Exposure Pathway	Potential Receptor	Probability of Exposure	Details
Human Health					
Asbestos, Hydrocarbon and metals.	Made Ground.	Ingestion dermal and inhalation.	Construction Workers.	Low	Management procedures proposed.
			Site users.	Low	Remediation proposed.
Asbestos, Hydrocarbon and metals.	Unforeseen Contamination.	Ingestion dermal and inhalation.	Construction Workers.	Dismissed.	Normal PPE will address risk.
			Site users.	Negligible.	No source identified.
Hydrocarbon and metals.	Potential migration from off-site source.	Ingestion dermal and inhalation.	Construction Workers.	Dismissed.	No source and no exceedance of GAC.
			Site users.		
Ground Gas.	Historic Landfill.	Inhalation & Explosive.	Construction Workers.	Dismissed.	No significant source identified and no significant ground gas measured.
			Site users.		
	Potential Made Ground.	Inhalation & Explosive.	Construction Workers.		
			Site users.		
Groundwater					
Hydrocarbon and metals.	Potential spillage on site	Vertical Migration.	Groundwater	Dismissed.	No mobile source identified.
Surface Water					
Hydrocarbon and metals.	Potential spillage on site	Horizontal Migration.	River Network	Dismissed.	No source or credible receptor.
Environmental Receptors					
On site contaminants		Ingestion dermal and inhalation.	Ecology.	Dismissed.	No sensitive ecology designation.
		Direct.	Archaeology.	Dismissed.	None present.
		Direct.	Geology.	Dismissed.	No sensitive receptor present.
		Phytotoxic.	Woodland.	Dismissed.	None present.
		Phytotoxic.	Crops.	Dismissed.	No source identified.
		Ingestion dermal and inhalation.	Livestock.	Dismissed.	No source identified.
Building Services					
On site contaminants		Direct.	Historic Buildings.	Dismissed.	None present.
		Direct.	Proposed Buildings.	Dismissed.	No source identified.
		Permeate into pipework.	Water Pipes.	Dismissed.	No significant source identified.

9.17 Elevated Lead, Arsenic and PAH have been identified and it is recommended that remediation is undertaken.

9.18 Within areas of buildings and pavements the use of hardstanding will provide remediation by breaking the potential pollutant linkage. Within proposed soft landscape areas it is

recommended that clean cover soils are provided comprising 600mm in domestic garden areas and 400mm in communal areas over a geotextile no dig layer. Validation of the cover soils should be undertaken using hand pits with testing of cover soils.

9.19 Asbestos contaminated material has been identified during the ground investigation and it is possible that further material could be encountered during construction works. The use of clean cover soils discussed above will provide remediation to protect future site users. Measures should to be incorporated in to the Contractors Construction Stage Health and Safety Plan and asbestos management plan as required under the Construction Design and Management (CDM) Regulations to mitigate risk to construction works. Measures may include:

- Designing temporary works to minimise disturbance of the Back fill material;
- Separating material and disposal of soils containing asbestos;
- Wetting down during excavation;
- Sheeting of stockpiles where asbestos is suspected;
- Testing of soils and off-site disposal of any soils found or suspected of containing asbestos;
- Preventing access to the construction site by members of the public;
- Use of good hygiene measures, including washing down of plant; and
- Use of appropriate PPE, including face masks..

9.20 If unforeseen contamination is encountered during construction works such as localised spillage outside the areas investigated an Environmental consultant will be available on a 'call out' basis to undertake an assessment of risk. If 'unforeseen contamination' is encountered such as hydrocarbon contamination or solvent odours the discovery strategy will be to remove the source as it is likely to be very limited in extent or encapsulate it on site as appropriate and the Local Planning Authority advised.

9.21 As part of this discovery strategy it is recommended that additional investigation by trial pits is undertaken in areas of existing hardstanding where access can not currently be obtained to identify potential areas of contamination. This supplementary investigation is best undertaken following demolition works where safe access can be gained.

Waste Classification

- 9.22 Two part WAC test has been undertaken, the results of which are included in Appendix C. These show no exceedances above the inert threshold values PAH, TPH or TOC. Exceedance above leachable thresholds for Inert Waste by Antimony and Lead were recorded. In addition, asbestos above 0.1% has been recorded.
- 9.23 The Waste Management paper 2 has been updated to version 3 which states that sites which previously could be considered 'uncontaminated land' surplus soils if they did not exceed the GAC values now requires the landfill to make an appropriate assessment of the waste classification. As such final assessment, will be undertaken by the receiving landfill based on the requirements of their permit.
- 9.24 Based on the results received it is considered that Made Ground is likely to be classified as Stable Non Reactive Waste.

10.0 GEOTECHNICAL ASSESSMENT

Proposed Development

- 10.1 This document is a report of this survey and has been produced to support a planning submission for the site which seeks the demolition of the existing buildings on-site and phased mixed-use development comprising 452 residential homes (Class C3) up to six storeys, a Community/Leisure Facility (Class F2) of up to three storeys in height, a “MakersLab” (sui generis) of up to two storeys together with basement car parking and site wide landscaping.
- 10.2 It is considered that the scheme meets the criteria of Geotechnical Category 1 of Eurocode 7.

Ground Conditions

- 10.3 Ground Conditions comprise Made Ground over firm clay and loose becoming dense with depth sand and gravel. This is underlain by London Clay comprising stiff clay.
- 10.4 Additional groundwater monitoring is being undertaken shortly pre-planning application and that the basement will be designed accordingly with the groundwater flood risk in mind.

Site Preparation

- 10.5 The site should be cleared and any vegetation below areas of proposed development stripped in accordance with Series 200 of the Specification for Highway Works. This should include:
- Any redundant services should be sealed off and grubbed out and replaced with suitable compacted engineered fill; and
 - Any tree roots should be grubbed out.

Foundations

- 10.6 It is considered that conventional strip foundations should be suitable for low rise buildings with wall loadings of 75kN/m or less assuming an allowable bearing capacity of 100kN/m² for natural soils at depths of 1.5m bgl. Within the natural firm clay or medium dense sand and gravel. An assessment of likely settlements has been undertaken and these are estimated to be less than 25mm.

10.7 Foundations may need to be stepped down locally where Made Ground is deeper. Foundations may also need to be deepened in accordance with NHBC requirements for building near trees. Foundations should be designed assuming soils of moderate shrinkage potential. It is recommended that foundations are reinforced to allow them to span both clay and granular soils.

10.8 No evidence of desiccation was noted.

10.9 It is likely that apartment blocks and structures with wall loadings above 75kN per m will require piled foundations.

10.10 For preliminary purposes and an initial pile assessment has been undertaken using the following assumptions:

- Upper 1.5m is ignored.
- Soil properties have been taken from the ground investigation and laboratory testing.
- A global factor of safety of 2.5 has been used, together with factors of 1.5 on shaft resistance and 3 on base resistance.

10.11 The following preliminary pile working loads have been calculated:

Pile depth (m bgl)	Working Load kN					
	200mm	250mm	300mm	350mm	450mm	600mm
10	80	100	125	150	200	300
15	150	180	235	280	370	530
20	220	290	350	420	560	770
25	320	400	500	590	780	1080

10.12 Final design should be undertaken by a specialist piling contractor who can use case studies to negotiate more economic pile designs.

Ground Floor Slab

10.13 Based on thickness of Made Ground suspended floor slabs are recommended.

Pavement Construction

10.14 An assessment of the likely California Bearing Ratio (CBR) has been assessed from the following sources:

- Description of the materials encountered in the exploratory holes; and

- Guidance given in HD25/94.

10.15 Based on the above it is considered that an equilibrium CBR of 3% is suitable.

10.16 It is recommended that the sub-formation is proof rolled with any soft materials being excavated and replaced with suitable compacted capping.

10.17 Soils are not considered to be frost susceptible.

Drainage

10.18 Soakaway testing identified poor soil infiltration rates due to the clay content of the sand and gravel deposits. Soakaway drainage is not considered feasible.

10.19 Chemical results should be provided to the water authority to confirm the design of potable water supply pipes.

Buried Concrete

10.20 Results of the sulphate and pH testing indicate that shallow soils have soluble sulphate concentrations are generally less than 0.5 g/l consistent with DS1 Conditions. Samples from the London Clay below 6m bgl recorded a concentration above 0.5 g/l within the London Clay at 25m bgl but the soils have a neutral pH. Taking account of pH and sulphate concentrations it is considered that shallow buried concrete can be designed to Class AC1-s.

Excavation and Materials Re-Use

10.21 Site observations indicated that excavations should be feasible in the near surface. Where access is required the excavations should be designed in accordance with CIRIA RR97.


10.22 Significant dewatering of excavations is not likely to be required.



9.4 Preliminary Conceptual Model

Receptors		Potential pathways											Comments on discounted pathways				
		Inhalation of contaminated vapour	Inhalation of contaminated dust	Direct Soil Ingestion	Direct dermal contact	Inhalation of asbestos	Drinking contaminated water supply	Direct contact of soil with building materials	Surface water run-off	Surface water percolation to groundwater	Migration via groundwater	Build-up of ground gas					
Site Users / Residents		Y	Y	Y	Y	Y	Y					Y					
Construction / Maintenance Operatives		Y	Y	Y	Y	Y											
Neighbours		Y	Y			Y			Y			Y					
Proposed Building								Y									
Watercourse									N				N				Nearest water course too far to be impacted by site.
Aquifer																	

Schematic Conceptual Model



Sources	Pathways	Receptors
<p>1 Car park, lock up garages, electricity substations, demolition debris & imported hard core (On Site)</p> <p>2 Nearby commercial activity (Off Site)</p> <p>3 Naturally occurring contaminants</p> <p>4 Unknown nature of fill material on-site & off site</p>	<p>A Inhalation, ingestion, dermal contact, vapours</p> <p>B Drinking contaminated water supply</p> <p>C Direct contact of soil with building materials</p> <p>D Surface water run-off</p> <p>E Surface water percolation to groundwater</p> <p>F Migration via groundwater</p> <p>G Vertical and lateral migration of soil gases</p>	<p>i Residents & Site User</p> <p>ii Construction & Maintenance Operatives</p> <p>iii Neighbours</p> <p>iv Proposed Building</p> <p>v Groundwater (Secondary A Aquifer)</p>



10 RISK ASSESSMENT

The level of information provided by the Landmark report and historic Ordnance Survey maps, together with the other information within the report is considered suitable to provide the data for a satisfactory risk assessment for the site. While there will always be uncertainties due to known or unknown gaps in information it is considered that sufficient information is available to reduce those uncertainties to within acceptable limits for the nature of the site under review.

An asbestos survey of existing structures and infrastructure (as defined under Section 5(a) of the Control of Asbestos Regulations 2012) was beyond the brief of this report. The risk assessment has been undertaken on the basis that should asbestos be identified within buildings or infrastructure, these materials will be removed appropriately by licensed contractors and asbestos materials disposed of in accordance with legal requirements prior to demolition or other works in order to avoid contaminating soils at the site.



Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Car park, lock up garages, electricity substations, demolition debris & imported hard core	Metals Hydrocarbons PAHs, PCB	Residents & Site Users	Dermal contact	Medium	Likely	Moderate risk	Contamination testing
			Inhalation of vapours, indoors and outdoors	Mild	Low likelihood	Low risk	
			Soil Ingestion	Medium	Likely	Moderate risk	
			Inhalation of contaminated dust	Medium	Likely	Moderate risk	
			Drinking of water from supply impacted by contaminated soil	Mild	Low likelihood	Low risk	



Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Car park, lock up garages, electricity substations, demolition debris & imported hard core	Metals Hydrocarbons PAHs, PCB	Construction operatives	Dermal contact	Mild	Likely	Moderate/Low risk	Information to be contained in site Health & Safety Plan. Use of appropriate ppe and normal good hygiene measures. Appropriate dust control measures during construction.
			Inhalation of vapours, indoors and outdoors	Minor	Low likelihood	Very low risk	
			Soil Ingestion	Mild	Likely	Moderate/Low risk	
			Inhalation of contaminated dust	Mild	Likely	Moderate/Low risk	
		Maintenance Operatives	Dermal contact	Mild	Low likelihood	Low risk	Information to be contained in site Health & Safety Plan.
			Inhalation of vapours, indoors and outdoors	Minor	Low likelihood	Very low risk	
			Soil Ingestion	Mild	Low likelihood	Low risk	
			Inhalation of contaminated dust	Mild	Low likelihood	Low risk	



Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Car park, lock up garages, electricity substations, demolition debris & imported hard core	Metals Hydrocarbons PAHs, PCB	Neighbours	Inhalation of vapours, indoors and outdoors	Minor	Unlikely	Very low risk	No further action required
			Inhalation of contaminated dust	Mild	Likely	Moderate/Low risk	Appropriate dust control measures during construction.
			Inhalation of contaminated dust (post construction)	Mild	Low likelihood	Low risk	Contamination testing
			Surface water run-off	Mild	Likely	Moderate/Low risk	
			Migration via groundwater	Mild	Likely	Moderate/Low risk	



Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Car park, lock up garages, electricity substations, demolition debris & imported hard core	Metals Hydrocarbons PAHs, PCB	Aquifer	Vertical percolation to groundwater via Foundations & Drainage	Mild	Likely	Moderate/Low risk	Foundations and drainage should be designed in such a way that they do not create a pathway for surface water percolation.
			Vertical percolation to groundwater via soft landscaped and permeable areas	Mild	Likely	Moderate/Low risk	Contamination testing

Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Unknown nature of fill material on-site & off site	Methane & carbon dioxide	Structures & other confined spaces	Migration via permeable strata & build up in buildings & other confined spaces	Severe	Likely	High risk	Ground gas monitoring to be undertaken. Gas protection measures installed if required. Information to be contained in site Health & Safety Plan.
		Construction & Maintenance Operatives		Severe	Low likelihood	Moderate risk	
		Residents & Site Users		Severe	Likely	High risk	
		Neighbours		Severe	Low likelihood	Moderate risk	
		Residents & Site Users		Severe	Low likelihood	Moderate risk	
Demolition debris & imported hard core	Asbestos	Construction operatives	Inhalation (during construction)	Severe	Low likelihood	Moderate risk	Any debris from earlier demolition found during site strip is to be inspected for asbestos by a suitably experienced contractor. Information to be contained in site Health & Safety Plan.
		Maintenance Operatives		Severe	Unlikely	Moderate/Low risk	
		Neighbours		Severe	Unlikely	Moderate/Low risk	
		Neighbours		Severe	Unlikely	Moderate/Low risk	



Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Demolition debris & imported hard core	Asbestos	Residents & Site Users	Inhalation of contaminated dust (post construction)	Severe	Low likelihood	Moderate risk	Contamination testing
		Neighbours		Severe	Unlikely	Moderate/Low risk	
Naturally occurring contaminants, Car park, lock up garages, electricity substations, demolition debris & imported hard core	Sulphates, pH	Proposed Building	Direct contact of soil with building materials	Medium	Likely	Moderate risk	As the protection of concrete is normally resolved in the building design process, the designer of the foundations should determine the requirement to undertake any investigation.



Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Nearby commercial activity (Off Site)	Metals Hydrocarbons PAHs, PCB	Residents & Site Users	Lateral migration of groundwater transporting contaminants to soil/made ground on site	Medium	Low likelihood	Moderate/low risk	Contamination testing
		Construction & Maintenance Operatives		Mild	Low likelihood	Low risk	Information to be contained in site Health & Safety Plan.
		Residents & Site Users	Drinking water supply impacted by groundwater transporting contaminants to site	Medium	Low likelihood	Moderate/low risk	It is not considered that an upgraded water supply pipe is required, however it is recommended that this report is provided to the water supplier for their comment.



Sources	Potential pollutant	Receptor	Pathway	Hazard severity	Likelihood of occurrence	Risk / Significance	Comment & control measures
Nursery (offsite)	Pesticides	Residents & Site Users	Lateral migration of groundwater transporting contaminants to soil/made ground on site	Mild	Low likelihood	Low risk	No further action required
		Construction & Maintenance Operatives		Mild	Unlikely	Very Low risk	
		Residents & Site Users	Drinking water supply impacted by groundwater transporting contaminants to site	Mild	Low likelihood	Low risk	

Any visual or olfactory evidence of contamination noted during works should be investigated by a suitably qualified person and their recommendations implemented.



11 SITE WORK

11.1 Investigations

11.1.1 In order to determine if the current or former usage of the property is a potential cause of contamination it is recommended that some site investigation should be undertaken based upon the requirements of BS 10175: 2001 which is the code of practice for the investigation of potentially contaminated sites. It is proposed that soil samples be taken from representative locations around the site and tested for a typical range of determinands, comprising asbestos, heavy metals, pH, speciated aromatic and aliphatic hydrocarbons and speciated PAHs and PCBs.

11.1.2 Due to the unknown nature of fill material on-site & off site monitoring for ground gas should be undertaken, in accordance with BS 8576, in order to determine if gas has migrated to the property. Furthermore, if the site has been filled in the past monitoring will determine if ground gas is being generated by the fill material.

11.2 Site Preparation

During the works a watching brief should be maintained by an experienced person. Should any visual or olfactory evidence of contamination be noted during the Chelmer Site Investigation Laboratories Ltd and the local authority Environmental Health Officer (EHO) should be contacted. Chelmer Site Investigation Laboratories Ltd shall assess if further intrusive investigation and remediation is required. Proposals will be issued to the EHO for comment prior to undertaking the additional investigation or implementing the remediation strategy.

The form of investigation proposed in 11.1.1 will indicate if there is any contamination present and if it is necessary will enable remedial works to be formulated.

If any potentially contaminated spoil is to be removed from site, the Waste Acceptance Criteria (WAC) testing should be agreed with the facility to which the spoil is being transported. It is recommended that consideration is given to this testing as part of the phase 2 investigation. Guidance can be obtained from Environment Agency document *Waste Sampling and Testing for Disposal to Landfill*.



11.3 External Works

In regard to water supply reference should be made to the UK Water Industry Research (UKWIR) publication "*Guidance for the Selection of Water Supply Pipes to be used in Brownfield Sites*" (Ref 10/WM/03/21; the '*UKWIR Guidance*'). This document provides guidance to ensure that water quality is safeguarded by identifying suitable pipe materials and components to be used below ground in potentially contaminated sites. It is not considered that an upgraded water supply pipe is required, however it is recommended that this report is provided to the water supplier for their comment.

12 SITE DEVELOPMENT CONSIDERATIONS

During the course of the site visit and preparation of this report the following items, whilst not within the scope of this report, have come to our attention and should be considered. This is not necessarily an exhaustive list.

12.1 An intrusive geotechnical investigation may be required to provide detailed information about the engineering nature of the ground, in order to allow the most suitable foundations in terms of economy and performance to be designed. This should follow the recommendations of BS 5930, the Code of Practice for site investigations with tests carried out to satisfy the requirements of BS 1377, the Code of Practice for methods of tests for soils for civil engineering purposes. It is recommended that this includes testing for sulphates.

12.2 As redevelopment of the property is proposed it is recommended that a full topographical survey is undertaken, if one is not available. This should identify all relevant features, boundaries and levels relating to the site and should also include ground levels on the adjacent properties and roads.

12.3 If it is proposed to make use of the existing drainage system, or any existing connections to the mains sewers. A CCTV survey should be considered in order to determine both the general condition and suitability for the proposed use.

12.4 If any excavation works are proposed, it is recommended that all the relevant utility companies are contacted to ascertain what pipes, cables, wires, lines and other apparatus exist close to where the work is to take place.



12.5 An asbestos survey of existing structures and infrastructure (as defined under Section 5(a) of the Control of Asbestos Regulations 2012) was beyond the brief of this report. Advice should be sought regarding the potential presence and management of asbestos within existing structures and infrastructure.

13 CONCLUSIONS

Based upon the information currently available, there would in principle, appear to be some significant contamination issues associated with the site, however, the following should be considered at this stage. It is considered that provided the recommendations of this report are implemented there is no increased risk to human health from redevelopment of the site for the proposed residential and commercial use.

13.1 There is potential contamination of the site from its uses as a car park, lock up garages and electricity substations and from demolition debris and imported hard core below ground slabs and paved areas.

13.2 It is recommended that some preliminary intrusive environmental site investigation is undertaken to determine if contamination is present on the property.

13.3 Study of the historical maps indicate that there is potential for the site to have been impacted by nearby commercial activities.

13.4 Due to the unknown nature of fill material on-site & off site, monitoring of potential ground gases, over a suitable period of time, will be required in order to determinate the requirements for gas mitigation measures. Information to be contained in Health & Safety Plan.

13.5 It is not considered that an upgraded water supply pipe is required, however it is recommended that this report is provided to the water supplier for their comment.

13.6 Should any visual or olfactory evidence of contamination be noted during the works this should be investigated by a suitably qualified person and their recommendations implemented.



13.7 If any potentially contaminated spoil is to be removed from site, the Waste Acceptance Criteria (WAC) testing should be agreed with the facility to which the spoil is being transported.



14 REFERENCES


- Card, G. B., Wilson, S., & Mortimer, S. (2012). *A Pragmatic Approach to Ground Gas Risk Assessment*. London, UK: Contaminated Land: Applications in Real Environments.
- Department of the Environment, Food and Rural Affairs and Environment Agency. (2004). *CLR 11: Model procedures for the management of land contamination*. Environment Agency. (2013). *Groundwater protection: principles and practice (GP3)*. Bristol: Environment Agency.
- Environment Agency. (2013). *Waste Sampling and Testing for Disposal to Landfill*. Bristol, UK: EA.
- Health and Safety Executive in the United Kingdom. (2012). *The Control of Asbestos Regulations 2012*.
- NHBC and Environment Agency. (2008). *Guidance for the Safe Development of Housing on Land Affected by Contamination*. NHBC and Environment Agency.
- UK Water Industry Research Ltd. (2010). *Guidance for the Selection of Water Supply Pipes to be used in Brownfield Sites*. UKWIR.
- Wilson, S., Oliver, S., Mallet, H., Hutchings, H., & Card, G. (2007). *CIRIA Report C665. Assessing risks posed by hazardous gases to buildings*. London, UK: Construction Industry Research and Information Association.



This document has been prepared for the titled project and should not be relied upon or used for any other project without an independent check being carried out as to its suitability and the prior written authority of Chelmer Site Investigation Laboratories Ltd being obtained. No responsibility or liability is accepted for the consequences of this document being used for a purpose other than that for which it was commissioned. Any person using or relying on this document for such other purpose will by such use or reliance be taken to confirm his agreement to indemnify Chelmer Site Investigation Laboratories Ltd for all loss or damage resulting therefrom. Chelmer Site Investigation Laboratories Ltd accepts no responsibility or liability for this document to any party other than Richmond Housing Partnership by whom it was commissioned.



Appendix A – Site Location Plan



bbbwpartnership
 110-114 Norman Road,
 Greenwich, London SE10 9QU
 020 8293 5175 www.bbw.co.uk

Date: Dec 16	Client: RHP
Drawn: AR	Project: Ham - Re-appraisal
Checked:	Title: Site areas diagram
Scale: 1:1000 @ A3	Drawn: 16.178 SK 1000

Rev	Date	Drawn	Check

Notes:
 ALL DETAILS TO BE CHECKED AND APPROVED BY
 THE CLIENT AND APPROVED BY THE ARCHITECT
 ACCORDANCE WITH MANUFACTURERS DESIGN AND
 SPECIFICATION



Appendix B – Photographs



View across site from northwest corner



View across site from the east



Appendix C – Landmark Report Extracts

Where the overview indicates that no data has been found the relevant detail report sections may have been omitted.

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding to Occur at Surface	A13NW (W)	0	1	517160 172357
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding of Property Situated Below Ground Level	A13SE (SE)	0	1	517200 172300
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding of Property Situated Below Ground Level	A13NE (E)	88	1	517400 172450
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding of Property Situated Below Ground Level	A8NW (S)	257	1	517050 171950
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding to Occur at Surface	A12NE (W)	322	1	516700 172450
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding of Property Situated Below Ground Level	A14NW (E)	431	1	517750 172400
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding of Property Situated Below Ground Level	A12NE (NW)	475	1	516600 172600
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding of Property Situated Below Ground Level	A12NE (W)	480	1	516550 172500
	BGS Groundwater Flooding Susceptibility Flooding Type: Potential for Groundwater Flooding of Property Situated Below Ground Level	A14SW (E)	462	1	517750 172200
1	Discharge Consents Operator: Thames Water Utilities Ltd Property Type: PUMPING STATION ON SEWERAGE NETWORK (WATER COMPANY) Location: Ham Authority: Environment Agency, Thames Region Catchment Area: Not Supplied Reference: Temp.1082 Permit Version: 2 Effective Date: 3rd September 2010 Issued Date: 3rd September 2010 Revocation Date: 13th October 2015 Discharge Type: Sewage Discharges - Pumping Station - Water Company Discharge: Saline Estuary Environment: Receiving Water: Tidal Thames Status: Surrendered under EPR 2010 Positional Accuracy: Located by supplier to within 100m	A13SE (SE)	214	2	517300 172100
1	Discharge Consents Operator: Thames Water Utilities Ltd Property Type: PUMPING STATION ON SEWERAGE NETWORK (WATER COMPANY) Location: Ham Authority: Environment Agency, Thames Region Catchment Area: Not Supplied Reference: Temp.1082 Permit Version: 1 Effective Date: 2nd November 1989 Issued Date: 2nd November 1989 Revocation Date: 2nd September 2010 Discharge Type: Sewage Discharges - Pumping Station - Water Company Discharge: Saline Estuary Environment: Receiving Water: Tidal Thames Status: Temporary Consents (Water Act 1989, Section 113) Positional Accuracy: Located by supplier to within 100m	A13SE (SE)	214	2	517300 172100

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
2	Discharge Consents Operator: Environment Agency Property Type: DOMESTIC PROPERTY (SINGLE) (INCL FARM HOUSE) Location: Teddington Lockteddingtonmiddlesex Authority: Environment Agency, Thames Region Catchment Area: Thames-Teddington/Beverley Brook Reference: Casm.1384 Permit Version: 1 Effective Date: 21st March 2006 Issued Date: 3rd May 2006 Revocation Date: Not Supplied Discharge Type: Sewage Discharges - Final/Treated Effluent - Not Water Company Discharge: Land/Soakaway Environment: Receiving Water: Into Land Status: New Consent, by Application, granted by Secretary of State Positional Accuracy: Located by supplier to within 10m	A7SE (SW)	768	2	516620 171580
3	Discharge Consents Operator: British Aerospace Plc Property Type: MAKING OF OTHER TRANSPORT EQUIP/SHIPS/TRAINS/BIKES Location: British Aerospace Plc, Kingstonupon Thames, Surrey Authority: Environment Agency, Thames Region Catchment Area: Not Supplied Reference: Ctr.1987 Permit Version: 1 Effective Date: 25th April 1983 Issued Date: 25th April 1983 Revocation Date: 17th June 1993 Discharge Type: Trade Effluent Discharge: Freshwater Stream/River Environment: Receiving Water: Thames Status: Authorisation revokedRevoked Positional Accuracy: Located by supplier to within 100m	A3NE (S)	966	2	517400 171300
4	Discharge Consents Operator: J E Perry Property Type: DOMESTIC PROPERTY (SINGLE) (INCL FARM HOUSE) Location: Palm Beach, Eel Pie Island, Twickenham, London Authority: Environment Agency, Thames Region Catchment Area: Not Supplied Reference: Ctwc.0573 Permit Version: 1 Effective Date: 20th December 1985 Issued Date: 20th December 1985 Revocation Date: 16th April 1991 Discharge Type: Unknown Discharge: Saline Estuary Environment: Receiving Water: River Thames Status: Authorisation revokedRevoked Positional Accuracy: Located by supplier to within 100m	A17NE (NW)	983	2	516500 173200
5	Local Authority Pollution Prevention and Controls Name: Ks Dry Cleaners Location: 65 Ham Street, Richmond, Tw10 7hw Authority: London Borough of Richmond upon Thames, Environmental Health Department Permit Reference: LBRUT/DC/29 Dated: 29th March 2007 Process Type: Local Authority Pollution Prevention and Control Description: PGG46 Dry cleaning Status: Permitted Positional Accuracy: Manually positioned to the address or location	A13NE (E)	19	3	517314 172389
6	Local Authority Pollution Prevention and Controls Name: Divine Dry Cleaners Location: 424 Richmond Road, Ham, K12 5pu Authority: London Borough of Richmond upon Thames, Environmental Health Department Permit Reference: LBRUT/DC/08 Dated: 1st April 2007 Process Type: Local Authority Pollution Prevention and Control Description: PGG46 Dry cleaning Status: Permitted Positional Accuracy: Manually positioned to the address or location	A9SW (SE)	935	3	517805 171565

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
7	Local Authority Pollution Prevention and Controls Name: Ham Cross Service Station Location: 297 Richmond Road, KINGSTON UPON THAMES, Surrey, KT2 5QU Authority: London Borough of Richmond upon Thames, Environmental Health Department Permit Reference: 16/PVR Dated: 31st December 1998 Process Type: Local Authority Pollution Prevention and Control Description: PG1/14 Petrol filling station Status: Permitted Positional Accuracy: Automatically positioned to the address	A9SW (SE)	935	3	517745 171527
	Nearest Surface Water Feature	A12SE (SW)	295	-	516804 172060
8	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Richmond, EEL PIE ISLAND Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed incident Incident Date: 19th February 1999 Incident Reference: THSE1999042077 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 10m	A13NE (E)	182	2	517500 172400
9	Pollution Incidents to Controlled Waters Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 25th May 1993 Incident Reference: SE930143 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A8SW (S)	628	2	516900 171600
10	Pollution Incidents to Controlled Waters Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Unknown Note: Not Supplied Incident Date: 3rd February 1996 Incident Reference: SE960049 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7NE (SW)	687	2	516600 171700
11	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Teddinton Lock Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: Not Supplied Incident Reference: SE950308 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SE (SW)	708	2	516700 171600

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
12	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 15th October 1990 Incident Reference: SE900296 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A8SW (S)	709	2	517000 171500
12	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: Richmond Upon, TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Miscellaneous - Natural Note: Confirmed incident Incident Date: 30th April 1999 Incident Reference: THSE1999042983 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 10m</p>	A8SW (S)	714	2	517000 171495
13	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: HAM Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Not Supplied Incident Date: 22nd March 1996 Incident Reference: SE960127 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A18NW (N)	715	2	517100 173200
14	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Miscellaneous - Unknown Note: Confirmed As A Pollution Incident Incident Date: 26th February 1990 Incident Reference: SE900045 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A7NW (SW)	729	2	516400 171900
15	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Chemicals - Unknown Note: Not Supplied Incident Date: 27th March 1996 Incident Reference: SE960135 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A7SE (SW)	754	2	516800 171500
16	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: Ferry Road, TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Chemicals - Unknown Note: Confirmed As A Pollution Incident Incident Date: 10th May 1990 Incident Reference: SE900141 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A7SE (SW)	795	2	516700 171500

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
17	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Broom Road Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 7th August 1989 Incident Reference: N1890418 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A8SW (S)	807	2	517100 171400
18	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Teddington Lock Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Yes Incident Date: 17th July 1992 Incident Reference: SE920227 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A8SW (S)	809	2	517000 171400
19	Pollution Incidents to Controlled Waters Property Type: Not Given Location: TWICKENHAM Authority: Environment Agency, Thames Region Pollutant: Unknown Sewage Note: Confirmed As A Pollution Incident Incident Date: 17th May 1991 Incident Reference: SE910115 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 2 - Significant Incident Positional Accuracy: Located by supplier to within 100m	A12NW (W)	821	2	516200 172500
20	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Riverside, TWICKENHAM Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 7th August 1990 Incident Reference: SE900241 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A17NE (NW)	827	2	516800 173200
21	Pollution Incidents to Controlled Waters Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 22nd September 1990 Incident Reference: SE900286 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SE (SW)	846	2	516600 171500
22	Pollution Incidents to Controlled Waters Property Type: Not Given Location: River Thames At, TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Unknown Sewage Note: Not Supplied Incident Date: 11th June 1997 Incident Reference: THSE1997032324 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SE (S)	847	2	516805 171400

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
22	Pollution Incidents to Controlled Waters Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 6th October 1990 Incident Reference: SE900292 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SE (S)	849	2	516800 171400
22	Pollution Incidents to Controlled Waters Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Not Supplied Incident Date: 2nd February 1996 Incident Reference: SE960075 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SE (S)	852	2	516805 171395
22	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Lemsburyclub Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 26th July 1991 Incident Reference: SE910214 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SE (S)	853	2	516800 171395
23	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Ferry Road, TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Miscellaneous - Natural Note: No Pollution Found Incident Date: 17th November 1998 Incident Reference: THSE1998041140 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SE (SW)	885	2	516700 171400
24	Pollution Incidents to Controlled Waters Property Type: Not Given Location: RICHMOND Authority: Environment Agency, Thames Region Pollutant: Unknown Sewage Note: Not Supplied Incident Date: 26th June 1997 Incident Reference: THSE1997032339 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A7SW (SW)	900	2	516400 171600
25	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Marble Hill Park Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 17th November 1991 Incident Reference: SE910330 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A23SE (N)	903	2	517300 173400

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
26	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Unknown Sewage Note: Confirmed As A Pollution Incident Incident Date: 19th September 1989 Incident Reference: S1890460 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A3NW (S)	909	2	517000 171300
27	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: TWICKENHAM Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Not Supplied Incident Date: 9th April 1998 Incident Reference: 38469 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A11NE (W)	910	2	516100 172395
27	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: Swansland, TWICKENHAM Authority: Environment Agency, Thames Region Pollutant: Unknown Sewage Note: Not Supplied Incident Date: 17th February 1997 Incident Reference: THSE1997031864 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A11NE (W)	910	2	516100 172400
28	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: 1 Strawberry Vale Authority: Environment Agency, Thames Region Pollutant: Unknown Sewage Note: Confirmed As A Pollution Incident Incident Date: 8th March 1989 Incident Reference: SE890072 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A7NW (SW)	911	2	516200 171900
29	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: British Aerospace Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 18th August 1993 Incident Reference: SE930248 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A7NW (SW)	917	2	516300 171700
29	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: British Aerospace Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 1st September 1993 Incident Reference: SE930262 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A7NW (SW)	920	2	516300 171695

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
30	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: Swan Island Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 12th December 1989 Incident Reference: SE890431 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A11NE (W)	920	2	516100 172500
31	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 20th August 1993 Incident Reference: SE930250 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A3NE (S)	966	2	517400 171300
31	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: TEDDINGTON Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Not Supplied Incident Date: 24th February 1996 Incident Reference: S1960079 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A3NE (S)	968	2	517405 171300
31	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: British Aerospace Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: Not Supplied Incident Reference: SE930192 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A3NE (S)	971	2	517400 171295
31	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: British Aerospace Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Yes Incident Date: Not Supplied Incident Reference: SE940332 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 2 - Significant Incident Positional Accuracy: Located by supplier to within 100m</p>	A3NE (S)	973	2	517405 171295
32	<p>Pollution Incidents to Controlled Waters</p> <p>Property Type: Not Given Location: KINGSTON Authority: Environment Agency, Thames Region Pollutant: Miscellaneous - Unknown Note: Confirmed As A Pollution Incident Incident Date: 8th February 1991 Incident Reference: SE910033 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m</p>	A9SW (SE)	967	2	517600 171400

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
33	Pollution Incidents to Controlled Waters Property Type: Not Given Location: STRAWBERRY HILL Authority: Environment Agency, Thames Region Pollutant: Miscellaneous - Unknown Note: Confirmed As A Pollution Incident Incident Date: 11th August 1992 Incident Reference: SE920269 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A11NE (W)	973	2	516040 172450
34	Pollution Incidents to Controlled Waters Property Type: Not Given Location: Swan Island Authority: Environment Agency, Thames Region Pollutant: Oils - Unknown Note: Confirmed As A Pollution Incident Incident Date: 26th May 1992 Incident Reference: SE920170 Catchment Area: Not Given Receiving Water: Not Given Cause of Incident: Not Given Incident Severity: Category 3 - Minor Incident Positional Accuracy: Located by supplier to within 100m	A11NE (W)	991	2	516030 172510
	River Quality Name: Not Supplied GQA Grade: Unclassified Tidal River Reach: Not Supplied Estimated Distance (km): Not Supplied Flow Rate: Not Supplied Flow Type: Not Supplied Year: 1995	A18NW (N)	750	2	516857 173164
	River Quality Name: Thames GQA Grade: River Quality B Reach: Hogsmill - Teddington Estimated Distance (km): 2.7 Flow Rate: Flow less than 80 cumecs Flow Type: River Year: 2000	A8SW (S)	844	2	516915 171375

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
35	River Quality Chemistry Sampling Points Name: Thames Reach: Hogsmill To Teddington Estimated Distance: 2.70 Objective: Not Supplied Positional Accuracy: Located by supplier to within 10m Year: 1990 GQA Grade: River Quality Chemistry GQA Grade C - Fairly Good Compliance: Not Supplied Year: 1993 GQA Grade: River Quality Chemistry GQA Grade C - Fairly Good Compliance: Not Supplied Year: 1994 GQA Grade: River Quality Chemistry GQA Grade C - Fairly Good Compliance: Not Supplied Year: 1995 GQA Grade: River Quality Chemistry GQA Grade C - Fairly Good Compliance: Not Supplied Year: 1996 GQA Grade: River Quality Chemistry GQA Grade C - Fairly Good Compliance: Not Supplied Year: 1997 GQA Grade: River Quality Chemistry GQA Grade C - Fairly Good Compliance: Not Supplied Year: 1998 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied Year: 1999 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied Year: 2000 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied Year: 2001 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied Year: 2002 GQA Grade: River Quality Chemistry GQA Grade A - Very Good Compliance: Not Supplied Year: 2003 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied Year: 2004 GQA Grade: River Quality Chemistry GQA Grade A - Very Good Compliance: Not Supplied Year: 2005 GQA Grade: River Quality Chemistry GQA Grade A - Very Good Compliance: Not Supplied Year: 2006 GQA Grade: River Quality Chemistry GQA Grade A - Very Good Compliance: Not Supplied Year: 2007 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied Year: 2008 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied Year: 2009 GQA Grade: River Quality Chemistry GQA Grade B - Good Compliance: Not Supplied	A8SW (S)	837	2	517020 171370
36	Substantiated Pollution Incident Register Authority: Environment Agency - Thames Region, South East Area Incident Date: 11th March 2002 Incident Reference: 63255 Water Impact: Category 2 - Significant Incident Air Impact: Category 4 - No Impact Land Impact: Category 4 - No Impact Positional Accuracy: Located by supplier to within 10m Pollutant: Oils - Diesel (Including Agricultural)	A7SE (SW)	714	2	516740 171570

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	Water Abstractions Operator: D.G.Tilles & R.H.Tilles Licence Number: 28/39/34/0008 Permit Version: 102 Location: Borehole At The Exiles Ground, Twickenham Authority: Environment Agency, Thames Region Abstraction: Sports Grounds/Facilities: Spray Irrigation - Direct Abstraction Type: Water may be abstracted from a single point Source: Groundwater Daily Rate (m3): Not Supplied Yearly Rate (m3): Not Supplied Details: The Exiles Ground, Twickenham Authorised Start: 01 October Authorised End: 30 September Permit Start Date: 14th September 2001 Permit End Date: Not Supplied Positional Accuracy: Located by supplier to within 10m	A24NE (NE)	1487	2	517840 173860
	Water Abstractions Operator: Threadneedle Property Part. Licence Number: 28/39/34/0008 Permit Version: 101 Location: Borehole At The Exiles Ground, Twickenham Authority: Environment Agency, Thames Region Abstraction: Sports Grounds/Facilities: Spray Irrigation - Direct Abstraction Type: Water may be abstracted from a single point Source: Groundwater Daily Rate (m3): Not Supplied Yearly Rate (m3): Not Supplied Details: The Exiles Ground, Twickenham Authorised Start: 01 January Authorised End: 31 December Permit Start Date: 31st March 2000 Permit End Date: Not Supplied Positional Accuracy: Located by supplier to within 10m	A24NE (NE)	1487	2	517840 173860
	Water Abstractions Operator: Cable & Wireless (Meadowbank) Ltd Licence Number: 28/39/34/0008 Permit Version: 100 Location: Borehole At The Exiles Ground, Twickenham Authority: Environment Agency, Thames Region Abstraction: Sports Grounds/Facilities: Spray Irrigation - Direct Abstraction Type: Water may be abstracted from a single point Source: Groundwater Daily Rate (m3): 56 Yearly Rate (m3): 5300 Details: The Exiles Ground, Twickenham Authorised Start: 01 January Authorised End: 31 December Permit Start Date: 15th October 1996 Permit End Date: Not Supplied Positional Accuracy: Located by supplier to within 100m	A24NE (NE)	1487	2	517840 173860
	Groundwater Vulnerability Soil Classification: Soils of High Leaching Potential (U) - Soil information for restored mineral workings and urban areas is based on fewer observations than elsewhere. A worst case vulnerability classification (H) assumed, until proved otherwise Map Sheet: Sheet 39 West London Scale: 1:100,000	A13NW (W)	0	2	517160 172357
	Drift Deposits None				
	Bedrock Aquifer Designations Aquifer Designation: Unproductive Strata	A13NW (W)	0	1	517160 172357
	Superficial Aquifer Designations Aquifer Designation: Secondary Aquifer - A	A13NW (W)	0	1	517160 172357
	Extreme Flooding from Rivers or Sea without Defences None				
	Flooding from Rivers or Sea without Defences None				
	Areas Benefiting from Flood Defences None				
	Flood Water Storage Areas None				

Agency & Hydrological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	Flood Defences None				
41	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 379.3 Watercourse Level: On ground surface Permanent: True Watercourse Name: Not Supplied Catchment Name: Thames Primacy: 1	A12SE (SW)	295	4	516804 172060
42	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 300.1 Watercourse Level: On ground surface Permanent: True Watercourse Name: Not Supplied Catchment Name: Thames Primacy: 1	A12SE (SW)	309	4	516768 172102
43	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 15.7 Watercourse Level: On ground surface Permanent: True Watercourse Name: Not Supplied Catchment Name: Thames Primacy: 1	A12NE (W)	339	4	516671 172391
44	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 125.4 Watercourse Level: On ground surface Permanent: True Watercourse Name: Not Supplied Catchment Name: Thames Primacy: 1	A14NE (E)	711	4	518001 172613
45	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 162.9 Watercourse Level: Not Supplied Permanent: True Watercourse Name: Not Supplied Catchment Name: Thames Primacy: 1	A14NE (E)	721	4	518023 172568
46	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 424.2 Watercourse Level: On ground surface Permanent: True Watercourse Name: River Thames Catchment Name: Thames Primacy: 2	A7SE (SW)	726	4	516785 171536
47	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 239.1 Watercourse Level: On ground surface Permanent: True Watercourse Name: River Thames Catchment Name: Thames Primacy: 2	A7SE (SW)	731	4	516643 171609
48	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 21.1 Watercourse Level: On ground surface Permanent: True Watercourse Name: River Thames Catchment Name: Thames Primacy: 2	A7SE (SW)	745	4	516681 171568
49	OS Water Network Lines Watercourse Form: Inland river Watercourse Length: 873.4 Watercourse Level: Not Supplied Permanent: True Watercourse Name: Not Supplied Catchment Name: Thames Primacy: 1	A14NE (E)	750	4	518020 172685

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	Local Authority Landfill Coverage Name: London Borough of Richmond Upon Thames - Has no landfill data to supply		0	5	517160 172357
	Local Authority Landfill Coverage Name: Royal Borough of Kingston Upon Thames - Has supplied landfill data		667	6	517531 171710
77	Potentially Infilled Land (Non-Water) Bearing Ref: S Use: Unknown Filled Ground (Pit, quarry etc) Date of Mapping: 1992	A13SW (S)	92	-	517100 172121
78	Potentially Infilled Land (Non-Water) Bearing Ref: NW Use: Unknown Filled Ground (Pit, quarry etc) Date of Mapping: 1992	A13NW (NW)	329	-	516880 172668

Geological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	BGS 1:625,000 Solid Geology Description: Thames Group	A13NW (W)	0	1	517160 172357
	BGS Estimated Soil Chemistry No data available				
79	BGS Recorded Mineral Sites Site Name: Ham Location: Ham, Richmond, Surrey Source: British Geological Survey, National Geoscience Information Service Reference: 19674 Type: Opencast Status: Ceased Operator: Not Supplied Operator Location: Not Supplied Periodic Type: Quaternary Geology: Kempton Park Gravel Formation Commodity: Sand and Gravel Positional Accuracy: Located by supplier to within 10m	A12NE (NW)	457	1	516620 172600
80	BGS Recorded Mineral Sites Site Name: Ham Location: Ham, Richmond, Surrey Source: British Geological Survey, National Geoscience Information Service Reference: 19676 Type: Opencast Status: Ceased Operator: Not Supplied Operator Location: Not Supplied Periodic Type: Quaternary Geology: Kempton Park Gravel Formation Commodity: Sand and Gravel Positional Accuracy: Located by supplier to within 10m	A7NE (SW)	480	1	516825 171790
81	BGS Recorded Mineral Sites Site Name: Ham Location: Ham, Richmond, Surrey Source: British Geological Survey, National Geoscience Information Service Reference: 19675 Type: Opencast Status: Ceased Operator: Not Supplied Operator Location: Not Supplied Periodic Type: Quaternary Geology: Kempton Park Gravel Formation Commodity: Sand and Gravel Positional Accuracy: Located by supplier to within 10m	A12SE (SW)	577	1	516500 172050
82	BGS Recorded Mineral Sites Site Name: Ham Gravel Pit Location: Ham, Richmond, Surrey Source: British Geological Survey, National Geoscience Information Service Reference: 164161 Type: Opencast Status: Ceased Operator: Not Supplied Operator Location: Not Supplied Periodic Type: Quaternary, Devensian Geology: Kempton Park Gravel Formation Commodity: Sand and Gravel Positional Accuracy: Located by supplier to within 10m	A12SW (W)	611	1	516417 172208
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 517196, 172203 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured: 18.90 mg/kg Concentration: Cadmium Measured: 0.60 mg/kg Concentration: Chromium Measured: 89.60 mg/kg Concentration: Lead Measured: 246.20 mg/kg Concentration: Nickel Measured: 25.70 mg/kg Concentration:	A13SE (S)	71	1	517196 172203

Geological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Gnd: 516775, 172208 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 15.30 mg/kg Cadmium Measured Concentration: 0.50 mg/kg Chromium Measured Concentration: 68.70 mg/kg Lead Measured Concentration: 160.00 mg/kg Nickel Measured Concentration: 27.70 mg/kg	A12SE (W)	268	1	516775 172208
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Gnd: 517162, 172797 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 35.90 mg/kg Cadmium Measured Concentration: 0.30 mg/kg Chromium Measured Concentration: 59.80 mg/kg Lead Measured Concentration: 418.30 mg/kg Nickel Measured Concentration: 41.40 mg/kg	A18SW (N)	308	1	517162 172797
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Gnd: 517224, 171792 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 16.20 mg/kg Cadmium Measured Concentration: 0.40 mg/kg Chromium Measured Concentration: 61.20 mg/kg Lead Measured Concentration: 239.30 mg/kg Nickel Measured Concentration: 20.90 mg/kg	A8NE (S)	444	1	517224 171792
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Gnd: 516653, 172693 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 16.30 mg/kg Cadmium Measured Concentration: 0.30 mg/kg Chromium Measured Concentration: 70.90 mg/kg Lead Measured Concentration: 79.80 mg/kg Nickel Measured Concentration: 22.10 mg/kg	A17SE (NW)	488	1	516653 172693
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Gnd: 516754, 171749 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 16.10 mg/kg Cadmium Measured Concentration: 0.40 mg/kg Chromium Measured Concentration: 61.40 mg/kg Lead Measured Concentration: 208.10 mg/kg Nickel Measured Concentration: 25.30 mg/kg	A7NE (SW)	553	1	516754 171749

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 517870, 172143 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 17.80 mg/kg Cadmium Measured Concentration: 0.60 mg/kg Chromium Measured Concentration: 53.80 mg/kg Lead Measured Concentration: 81.50 mg/kg Nickel Measured Concentration: 15.50 mg/kg	A14SE (E)	614	1	517870 172143
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 517880, 172804 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 13.90 mg/kg Cadmium Measured Concentration: 0.30 mg/kg Chromium Measured Concentration: 44.00 mg/kg Lead Measured Concentration: 161.70 mg/kg Nickel Measured Concentration: 17.70 mg/kg	A19SE (NE)	674	1	517880 172804
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 517228, 173180 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 18.30 mg/kg Cadmium Measured Concentration: 0.50 mg/kg Chromium Measured Concentration: 61.50 mg/kg Lead Measured Concentration: 75.40 mg/kg Nickel Measured Concentration: 20.70 mg/kg	A18NE (N)	681	1	517228 173180
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 516303, 172232 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 28.10 mg/kg Cadmium Measured Concentration: 0.60 mg/kg Chromium Measured Concentration: 49.80 mg/kg Lead Measured Concentration: 98.50 mg/kg Nickel Measured Concentration: 27.70 mg/kg	A12SW (W)	718	1	516303 172232
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 517788, 171803 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 14.30 mg/kg Cadmium Measured Concentration: 0.40 mg/kg Chromium Measured Concentration: 51.60 mg/kg Lead Measured Concentration: 85.20 mg/kg Nickel Measured Concentration: 14.20 mg/kg	A9NW (SE)	738	1	517788 171803

Geological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 516264, 172716 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 22.90 mg/kg Cadmium Measured Concentration: 0.40 mg/kg Chromium Measured Concentration: 60.00 mg/kg Lead Measured Concentration: 89.90 mg/kg Nickel Measured Concentration: 30.20 mg/kg	A17SW (W)	826	1	516264 172716
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 517785, 173299 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 22.20 mg/kg Cadmium Measured Concentration: 0.30 mg/kg Chromium Measured Concentration: 71.00 mg/kg Lead Measured Concentration: 203.80 mg/kg Nickel Measured Concentration: 30.40 mg/kg	A19NW (NE)	967	1	517785 173299
	BGS Measured Urban Soil Chemistry Source: British Geological Survey, National Geoscience Information Service Grid: 518303, 172289 Soil Sample Type: Topsoil Sample Area: London Arsenic Measured Concentration: 22.20 mg/kg Cadmium Measured Concentration: 0.30 mg/kg Chromium Measured Concentration: 61.00 mg/kg Lead Measured Concentration: 134.70 mg/kg Nickel Measured Concentration: 18.70 mg/kg	A15SW (E)	992	1	518303 172289
	BGS Urban Soil Chemistry Averages Source: British Geological Survey, National Geoscience Information Service Sample Area: London Count Id: 7209 Arsenic Minimum Concentration: 1.00 mg/kg Arsenic Average Concentration: 17.00 mg/kg Arsenic Maximum Concentration: 161.00 mg/kg Cadmium Minimum Concentration: 0.10 mg/kg Cadmium Average Concentration: 0.90 mg/kg Cadmium Maximum Concentration: 165.20 mg/kg Chromium Minimum Concentration: 13.00 mg/kg Chromium Average Concentration: 79.00 mg/kg Chromium Maximum Concentration: 2094.00 mg/kg Lead Minimum Concentration: 11.00 mg/kg Lead Average Concentration: 280.00 mg/kg Lead Maximum Concentration: 10000.00 mg/kg Nickel Minimum Concentration: 2.00 mg/kg Nickel Average Concentration: 28.00 mg/kg Nickel Maximum Concentration: 506.00 mg/kg	A13NW (W)	0	1	517160 172357

Geological

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
	Coal Mining Affected Areas In an area that might not be affected by coal mining				
	Non Coal Mining Areas of Great Britain No Hazard				
	Potential for Collapsible Ground Stability Hazards Hazard Potential: Very Low Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357
	Potential for Compressible Ground Stability Hazards Hazard Potential: No Hazard Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357
	Potential for Compressible Ground Stability Hazards Hazard Potential: Moderate Source: British Geological Survey, National Geoscience Information Service	A13SW (SW)	41	1	516906 172263
	Potential for Ground Dissolution Stability Hazards Hazard Potential: No Hazard Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357
	Potential for Landslide Ground Stability Hazards Hazard Potential: Very Low Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357
	Potential for Running Sand Ground Stability Hazards Hazard Potential: Very Low Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357
	Potential for Shrinking or Swelling Clay Ground Stability Hazards Hazard Potential: No Hazard Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357
	Potential for Shrinking or Swelling Clay Ground Stability Hazards Hazard Potential: Moderate Source: British Geological Survey, National Geoscience Information Service	A13SE (SE)	78	1	517300 172260
	Radon Potential - Radon Affected Areas Affected Area: The property is in a Lower probability radon area (less than 1% of homes are estimated to be at or above the Action Level). Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357
	Radon Potential - Radon Protection Measures Protection Measure: No radon protective measures are necessary in the construction of new dwellings or extensions Source: British Geological Survey, National Geoscience Information Service	A13NW (W)	0	1	517160 172357

Industrial Land Use

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
83	Contemporary Trade Directory Entries Name: K S Dry Cleaners Ltd Location: 65, Ham Street, Richmond, TW10 7HW Classification: Dry Cleaners Status: Active Positional Accuracy: Automatically positioned to the address	A13NE (E)	19	-	517311 172387
83	Contemporary Trade Directory Entries Name: Peter'S Cleaners Location: 65, Ham Street, Richmond, Surrey, TW10 7HW Classification: Dry Cleaners Status: Inactive Positional Accuracy: Automatically positioned to the address	A13NE (E)	20	-	517312 172387
83	Contemporary Trade Directory Entries Name: Mica Hardware Location: 12, Ashburnham Road, Richmond, Surrey, TW10 7NF Classification: Hardware Status: Inactive Positional Accuracy: Automatically positioned to the address	A13NE (E)	20	-	517302 172362
83	Contemporary Trade Directory Entries Name: Peels Of London Ltd Location: 63, Ham Street, Richmond, Surrey, TW10 7HW Classification: Window Tinting Status: Inactive Positional Accuracy: Automatically positioned to the address	A13NE (E)	26	-	517315 172382
84	Contemporary Trade Directory Entries Name: Wwv Enviro-Blast-Clean.Com Location: 32, Mowbray Road, Richmond, Surrey, TW10 7NQ Classification: Blast Cleaning Status: Inactive Positional Accuracy: Automatically positioned to the address	A13SE (S)	138	-	517212 172135
85	Contemporary Trade Directory Entries Name: Star Optical Location: 202, Ashburnham Road, Richmond, Surrey, TW10 7NL Classification: Laboratory Equipment, Instruments & Supplies Status: Inactive Positional Accuracy: Automatically positioned to the address	A13SW (SW)	155	-	516888 172223
85	Contemporary Trade Directory Entries Name: Mercury Multimedia Ltd Location: 206, Ashburnham Road, RICHMOND, Surrey, TW10 7NL Classification: Photo & Digital Imaging Bureaus Status: Inactive Positional Accuracy: Automatically positioned to the address	A13SW (SW)	158	-	516882 172233
85	Contemporary Trade Directory Entries Name: Express Installers Location: 89, Woodville Road, Richmond, TW10 7QW Classification: Cinema Equipment Status: Active Positional Accuracy: Automatically positioned to the address	A13SW (W)	160	-	516873 172258
86	Contemporary Trade Directory Entries Name: Intech Marketing (Uk) Ltd Location: 32, Back Lane, Richmond, Surrey, TW10 7LF Classification: Office Furniture & Equipment Status: Inactive Positional Accuracy: Automatically positioned to the address	A13SE (SE)	194	-	517400 172186
87	Contemporary Trade Directory Entries Name: Sparkies Location: 89, Ashburnham Road, Richmond, Surrey, TW10 7NN Classification: Cleaning Services - Domestic Status: Inactive Positional Accuracy: Automatically positioned to the address	A13SW (SW)	199	-	516907 172085
87	Contemporary Trade Directory Entries Name: G T Harris Location: 26, Fellbrook, Richmond, Surrey, TW10 7UW Classification: Washing Machines - Servicing & Repairs Status: Inactive Positional Accuracy: Automatically positioned to the address	A13SW (SW)	241	-	516889 172041
88	Contemporary Trade Directory Entries Name: A S Motors Location: Central Garage, Croft Way, Off Dukes Av, Ham, Richmond, Surrey, TW10 7NP Classification: Mot Testing Centres Status: Inactive Positional Accuracy: Manually positioned to the road within the address or location	A13SW (SW)	251	-	516828 172112

Industrial Land Use

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
89	Contemporary Trade Directory Entries Name: Designer Carpets Location: 2, Ham Street, Richmond, Surrey, TW10 7HT Classification: Carpets & Rugs - Manufacturers Status: Inactive Positional Accuracy: Automatically positioned to the address.	A13SE (SE)	273	-	517480 172153
89	Contemporary Trade Directory Entries Name: M W Carpets Ltd Location: 2, Ham Street, Richmond, Surrey, TW10 7HT Classification: Carpets & Rugs - Manufacturers Status: Inactive Positional Accuracy: Automatically positioned to the address.	A13SE (SE)	273	-	517480 172153
90	Contemporary Trade Directory Entries Name: Lifetime Shutters & Blinds Ltd Location: 63, Perryfield Way, Richmond, Surrey, TW10 7SL Classification: Shutters - Internal Status: Inactive Positional Accuracy: Automatically positioned to the address.	A13NW (NW)	278	-	516905 172622
91	Contemporary Trade Directory Entries Name: B & S Car Disposal Service Location: 29, Meadlands Drive, Richmond, Surrey, TW10 7EF Classification: Car Breakers & Dismantlers Status: Inactive Positional Accuracy: Automatically positioned to the address.	A19SW (NE)	388	-	517566 172737
92	Contemporary Trade Directory Entries Name: Key Cleaning Location: Flat 1, 200, Riverside Drive, Richmond, Surrey, TW10 7RP Classification: Commercial Cleaning Services Status: Inactive Positional Accuracy: Automatically positioned to the address.	A8NW (S)	415	-	517006 171795
93	Contemporary Trade Directory Entries Name: M K B Enterprise Ltd Location: 5, Broughton Avenue, Richmond, Surrey, TW10 7TT Classification: Electronic Component Manufacturers & Distributors Status: Active Positional Accuracy: Automatically positioned to the address.	A8NE (S)	433	-	517194 171793
94	Contemporary Trade Directory Entries Name: Az Clean Ltd Location: 10, Momington Walk, Richmond, Surrey, TW10 7LY Classification: Commercial Cleaning Services Status: Inactive Positional Accuracy: Automatically positioned to the address.	A8NE (SE)	445	-	517469 171932
95	Contemporary Trade Directory Entries Name: Surrey Auto Services Location: 156, Dukes Avenue, Richmond, TW10 7YL Classification: Garage Services Status: Active Positional Accuracy: Automatically positioned to the address.	A8NE (S)	498	-	517289 171762
96	Contemporary Trade Directory Entries Name: Ains & Graces Location: 4, Beaufort Road, Richmond, Surrey, TW10 7XS Classification: Cleaning Services - Domestic Status: Inactive Positional Accuracy: Automatically positioned to the address.	A8NE (S)	525	-	517189 171696
97	Contemporary Trade Directory Entries Name: M J W Print Ltd Location: 7, Lauderdale Drive, Richmond, Surrey, TW10 7BS Classification: Printers Status: Inactive Positional Accuracy: Automatically positioned to the address.	A14NE (E)	570	-	517872 172650
98	Contemporary Trade Directory Entries Name: London Cleaning Service Location: 64, Beaufort Court, Beaufort Road, Richmond, Surrey, TW10 7YQ Classification: Cleaning Services - Domestic Status: Inactive Positional Accuracy: Automatically positioned to the address.	A8SW (S)	573	-	517129 171637
99	Contemporary Trade Directory Entries Name: Oscar Pet Foods Location: 28, Buckingham Road, Richmond, Surrey, TW10 7EQ Classification: Pet Foods & Animal Feeds Status: Inactive Positional Accuracy: Automatically positioned to the address.	A19SW (NE)	597	-	517788 172803

Industrial Land Use

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
120	Contemporary Trade Directory Entries Name: B 'N' S Salvage Location: Flat 26, Cranmer Court, Richmond Road, Kingston upon Thames, Surrey, KT2 5PY Classification: Car Breakers & Dismantlers Status: Inactive Positional Accuracy: Automatically positioned to the address	A9SW (SE)	987	-	517819 171512
121	Contemporary Trade Directory Entries Name: Smart Fleet Location: 47, Northweald Lane, Kingston upon Thames, Surrey, KT2 5GN Classification: Car Dealers Status: Inactive Positional Accuracy: Automatically positioned to the address	A4NW (S)	987	-	517518 171330
122	Contemporary Trade Directory Entries Name: Kemetyl Location: Broom Road, Teddington, Middlesex, TW11 9NU Classification: Chemical Manufacturers Status: Inactive Positional Accuracy: Manually positioned within the geographical locality	A3NW (S)	990	-	516967 171221
123	Fuel Station Entries Name: A S Motors Of Ham Location: Croftway, Riverside Drive, Ham, RICHMOND, Surrey, TW10 7NP Brand: Obsolete Premises Type: Not Applicable Status: Obsolete Positional Accuracy: Manually positioned to the address or location	A12SE (SW)	260	-	516810 172129
124	Fuel Station Entries Name: Ham Cross Service Station Location: 297, Richmond Road, Kingston upon Thames, Surrey, KT2 5QU Brand: Texaco Premises Type: Petrol Station Status: Open Positional Accuracy: Automatically positioned to the address	A9SW (SE)	935	-	517745 171527
125	Points of Interest - Commercial Services Name: Tooth Removals Sarl Location: 10 Watemill Close, Richmond, TW10 7UH Category: Transport, Storage and Delivery Class Code: Distribution and Haulage Positional Accuracy: Positioned to address or location	A13SW (S)	189	7	517099 172020
126	Points of Interest - Commercial Services Name: Crown Ltd Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
126	Points of Interest - Commercial Services Name: Crown Motorcycles Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
126	Points of Interest - Commercial Services Name: Vetech Motor Services Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
126	Points of Interest - Commercial Services Name: Crown Garage Kingston Ltd Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
126	Points of Interest - Commercial Services Name: Ham Cross Garage Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527



Industrial Land Use

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
126	Points of Interest - Commercial Services Name: Vetech Motor Services Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A9SW (SE)	936	7	517745 171526
126	Points of Interest - Commercial Services Name: Crown Garages Kingston Ltd Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A9SW (SE)	936	7	517745 171526
127	Points of Interest - Commercial Services Name: L J Motorcycle Repairs Location: Unit D1 1, Strawberry Vale, Twickenham, TW1 4RP Category: Repair and Servicing Class Code: Vehicle Repair, Testing and Servicing Positional Accuracy: Positioned to address or location	A11NE (W)	980	7	516036 172478
128	Points of Interest - Education and Health Name: Cassel Hospital Location: 1 Ham Common, Richmond, TW10 7JF Category: Health Practitioners and Establishments Class Code: Hospitals Positional Accuracy: Positioned to address or location	A9NW (SE)	695	7	517708 171791
129	Points of Interest - Manufacturing and Production Name: Tank Location: TW10 Category: Industrial Features Class Code: Tanks (Generic) Positional Accuracy: Positioned to an adjacent address or location	A13SE (S)	201	7	517267 172095
130	Points of Interest - Manufacturing and Production Name: Works Location: Not Supplied Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A9NW (SE)	768	7	517822 171795
131	Points of Interest - Manufacturing and Production Name: Works Location: Not Supplied Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A11NE (W)	914	7	516100 172454
131	Points of Interest - Manufacturing and Production Name: Works Location: TW1 Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A11NE (W)	918	7	516096 172454
131	Points of Interest - Manufacturing and Production Name: Works Location: TW1 Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A11NE (W)	985	7	516030 172468
131	Points of Interest - Manufacturing and Production Name: Works Location: Not Supplied Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A11NE (W)	989	7	516026 172469
132	Points of Interest - Manufacturing and Production Name: Works Location: Not Supplied Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A17NE (NW)	935	7	516573 173189
133	Points of Interest - Manufacturing and Production Name: Works Location: Not Supplied Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A17NW (NW)	963	7	516452 173145

Industrial Land Use

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
133	Points of Interest - Manufacturing and Production Name: Works Location: Not Supplied Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A17NW (NW)	978	7	516428 173146
133	Points of Interest - Manufacturing and Production Name: Works Location: Not Supplied Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A17NW (NW)	979	7	516443 173158
133	Points of Interest - Manufacturing and Production Name: Works Location: TW1 Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A17NW (NW)	979	7	516428 173147
133	Points of Interest - Manufacturing and Production Name: Works Location: TW1 Category: Industrial Features Class Code: Unspecified Works Or Factories Positional Accuracy: Positioned to an adjacent address or location	A17NW (NW)	980	7	516443 173159
134	Points of Interest - Public Infrastructure Name: Metropolitan Police Service Location: 18 Ashburnham Road, Richmond, TW10 7NF Category: Central and Local Government Class Code: Police Stations Positional Accuracy: Positioned to address or location	A13NE (E)	33	7	517324 172379
134	Points of Interest - Public Infrastructure Name: Metropolitan Police Service Location: 18 Ashburnham Road, Richmond, TW10 7NF Category: Central and Local Government Class Code: Police Stations Positional Accuracy: Positioned to address or location	A13NE (E)	33	7	517324 172379
135	Points of Interest - Public Infrastructure Name: Tesco Petrol Filling Station Location: 185 Ashburnham Road, Richmond, TW10 7NR Category: Road And Rail Class Code: Petrol and Fuel Stations Positional Accuracy: Positioned to address or location	A12SE (SW)	235	7	516818 172182
136	Points of Interest - Public Infrastructure Name: Outfall Location: TW10 Category: Infrastructure and Facilities Class Code: Waste Storage, Processing and Disposal Positional Accuracy: Positioned to an adjacent address or location	A12SW (W)	725	7	516340 172066
137	Points of Interest - Public Infrastructure Name: Sluices Location: TW10 Category: Water Class Code: Weirs, Sluices and Dams Positional Accuracy: Positioned to an adjacent address or location	A8SW (S)	752	7	516893 171474
137	Points of Interest - Public Infrastructure Name: Sluice Location: TW10 Category: Water Class Code: Weirs, Sluices and Dams Positional Accuracy: Positioned to an adjacent address or location	A8SW (S)	767	7	516957 171447
138	Points of Interest - Public Infrastructure Name: Sluices Location: TW11 Category: Water Class Code: Weirs, Sluices and Dams Positional Accuracy: Positioned to an adjacent address or location	A8SW (S)	797	7	517008 171411
138	Points of Interest - Public Infrastructure Name: Sluices Location: TW11 Category: Water Class Code: Weirs, Sluices and Dams Positional Accuracy: Positioned to an adjacent address or location	A8SW (S)	819	7	517019 171389

Industrial Land Use

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
138	Points of Interest - Public Infrastructure Name: Teddington Weir Location: TW11 Category: Water Class Code: Weirs, Sluices and Dams Positional Accuracy: Positioned to an adjacent address or location	A8SW (S)	826	7	517021 171381
139	Points of Interest - Public Infrastructure Name: Cemetery Location: TW10 Category: Infrastructure and Facilities Class Code: Cemeteries and Crematoria Positional Accuracy: Positioned to an adjacent address or location	A9NE (SE)	867	7	517983 171831
139	Points of Interest - Public Infrastructure Name: Cemetery Location: Not Supplied Category: Infrastructure and Facilities Class Code: Cemeteries and Crematoria Positional Accuracy: Positioned to an adjacent address or location	A9NE (SE)	871	7	517988 171832
140	Points of Interest - Public Infrastructure Name: Hamcross Self Serve Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Road And Rail Class Code: Petrol and Fuel Stations Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
140	Points of Interest - Public Infrastructure Name: Ham Cross Service Station Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Road And Rail Class Code: Petrol and Fuel Stations Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
140	Points of Interest - Public Infrastructure Name: Ham Cross Service Station Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Road And Rail Class Code: Petrol and Fuel Stations Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
140	Points of Interest - Public Infrastructure Name: Ham Cross Service Station Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Road And Rail Class Code: Petrol and Fuel Stations Positional Accuracy: Positioned to address or location	A9SW (SE)	935	7	517745 171527
140	Points of Interest - Public Infrastructure Name: Texaco Location: 297 Richmond Road, Kingston upon Thames, KT2 5QU Category: Road And Rail Class Code: Petrol and Fuel Stations Positional Accuracy: Positioned to address or location	A9SW (SE)	936	7	517745 171526
141	Points of Interest - Recreational and Environmental Name: Playground Location: Not Supplied Category: Recreational Class Code: Playgrounds Positional Accuracy: Positioned to an adjacent address or location	A18SW (N)	323	7	517035 172754
141	Points of Interest - Recreational and Environmental Name: Playground Location: Riverside Drive, TW10 Category: Recreational Class Code: Playgrounds Positional Accuracy: Positioned to an adjacent address or location	A18SW (N)	323	7	517035 172754
142	Points of Interest - Recreational and Environmental Name: Playground Location: Not Supplied Category: Recreational Class Code: Playgrounds Positional Accuracy: Positioned to an adjacent address or location	A8SW (S)	650	7	517049 171556
142	Points of Interest - Recreational and Environmental Name: Playground Location: Fisherman Close, TW10 Category: Recreational Class Code: Playgrounds Positional Accuracy: Positioned to an adjacent address or location	A8SW (S)	650	7	517049 171556


Sensitive Land Use

Map ID	Details	Quadrant Reference (Compass Direction)	Estimated Distance From Site	Contact	NGR
145	Local Nature Reserves Name: Ham Lands Multiple Area: Y Area (m2): 600138.24 Source: Natural England Designation Date: 1st January 1992	A12SE (SW)	290	8	516809 172060
146	Local Nature Reserves Name: Ham Common, Richmond, London Multiple Area: N Area (m2): 402691.94 Source: Natural England Designation Date: 1st January 2001	A14SE (E)	671	8	517897 172074



Appendix D – Historical Maps

© Crown copyright. All rights reserved. Licence number LAN1001467.



Contaminated Land Solutions

London

Published 1850

Source map scale - 1:5,280


The historical base plans shown derive from Ordnance Survey mapping from the early to mid 1850s. The data was converted to a vector format by the Ordnance Survey and is available on the Ordnance Survey website. The ground floor is similar to that of the early 1250th settlement study references. The data is derived from the Ordnance Survey's 1:50,000 scale mapping. The scale was also used for a reproduction of the 1:25,000 scale mapping of London that was undertaken between 1860 and 1932.

Please note: Due to the partial coverage of Historical Town Plans, it is possible that not all segments within an order will contain mapping. Only the segments that have been Plan coverage will be generated.

Map Name(s) and Date(s)

LONDON_000000_0E
1:5,280
LONDON_000000_0E
1:5,280

Historical Town Plan - Segment A13



Order Details


Order Number 133757119_L_1
Customer Ref 1202
National Grid Reference 5177160, 1723640
Slice A
Site Area (H) 4.56
Search Index (m) 0


Site Details


Ham Close, RICHMOND UPON THAMES, TW10 7PG

Landmark

Landmark Information Group Services ©2012 27 Jul 2012 Page 1 of 1







Contaminated Land Solutions

**Historical Aerial Photography
Published 1946 - 1947**

Source map scale - 1:1,250

The historical aerial photos were produced by the Ordnance Survey at a scale of 1:1,250 and 1:12,500 from Air Force photography. They were produced by conventional mapping, due to poor weather and the unavailability of many of the 1950s aerial photography and the use of black and white film. The photos were taken in the summer of 1946 and 1947, shortly after a period of six years although due to the accuracy of the aerials, some detail is visible in the 1946 aerials. Where the Ordnance Survey have provided both versions it is for ease to best see the details.

Map Name(s) and Date(s)

1:1,250	1:12,500
1946	1947
1946	1947
1946	1947
1946	1947

Historical Aerial Photography - Segment A13



Order Details


Order Number: 133757119_L1
 Customer Ref: 1322
 National Grid Reference: 517160, 172360
 Size: A
 Site Area (Ha): 4.08
 Search Buffer (m): 100


Site Details


Ham Close, RICHMOND UPON THAMES, TW10 7PG


Landmark


Aerialmark Information Online Service v5.2 27-Jul-2017 Page 13 of 24
















Appendix E – Owner’s Questionnaire

Questionnaire, for completion by current or previous owner or manager, please enter Not Known where you are unable to provide an answer.

Ham Close, Richmond upon Thames, TW10 7PG

I have owned/managed* the above site from .2000..... tocurrent.....
 (*delete as appropriate)

Existing site & property details:

Site use:	Mainly residential Youth club/ clinic/ dentist
Number of Buildings:	14 residential blocks
Building 'A', Nature of Use: <small>(insert lines as required)</small>	residential
Date of Construction	1960's
Land Area (ha):	
Current Tenants:	192 units
Any asbestos containing materials?	Likely due to age of construction
Asbestos Survey available?	no
Any archaeological, geotechnical or environmental reports?	no

Current site utilities:

Commercial/Household Waste Disposal	
Sewage Discharge and Disposal	<i>to main drainage, yes/no, if other please specify</i>
Surface Water Drainage	<i>to main drainage/soakaway, if other please specify</i>
Source of heating and cooling	<i>Individual mains gas/electric</i>
Wells?	no
Septic System?	no

Historical site activities (if answered 'yes', please provide details):

Are you aware of any other past use of the site?	no
Are you aware of any other past use of adjacent areas?	Not to our knowledge
Has anything been buried on or within 250m of the site?	Not to our knowledge
Have any chemicals been stored on or within 250m of the site?	Not to our knowledge
Have any potentially contaminating processes been undertaken either on or within 250m of the site?	Not to our knowledge
Has there been any oil or fuel storage on or within 250m of the site?	Not to our knowledge
Has any fill material been deposited on or within 250m of the site?	Not to our knowledge
Have any animals been kept on site?	Maybe, as originally farmland (approx. 100 years ago)

Signed.....

Date.....01 Aug 2017.....

Name...Tracey Elliott.....

Company....RHP.....

Appendix F – Contacts

Local Authority	Environmental Health London Borough of Richmond upon Thames 4 Waldegrave Road, Teddington, Middlesex, TW11 8EN	www.richmond.gov.uk
		Simon.makoni@richmond.gov.uk
Environment Agency	National Customer Contact Centre PO Box 544 Rotherham S60 1BY	08708 506 506
		enquiries@environment-agency.gov.uk
Coal Authority	Mining Reports Office 200 Lichfield Lane Berry Hill, Mansfield Notts, HG18 4RG	
		www.coalminingreports.co.uk
Health Protection Agency, Radiation Protection Division	Chilton Didcot Oxon, OX11 0RQ	01235 822622
		radon@hpa.org.uk
		www.hpa.org.uk/radiation

- a) This report has been prepared for the purpose of providing advice to the client pursuant to its appointment of Chelmer Site Investigation Laboratories Limited (CSI) to act as a consultant.
- b) Save for the client no duty is undertaken or warranty or representation made to any party in respect of the opinions, advice, recommendations or conclusions herein set out.
- c) All work carried out in preparing this report has used, and is based upon, our professional knowledge and understanding of the current relevant English and European Community standards, approved codes of practice, technology and legislation.
- d) Changes in the above may cause the opinion, advice, recommendations or conclusions set out in this report to become inappropriate or incorrect. However, in giving its opinions, advice, recommendations and conclusions, CSI has considered pending changes to environmental legislation and regulations of which it is currently aware. Following delivery of this report, we will have no obligation to advise the client of any such changes, or of their repercussions.
- e) CSI acknowledges that it is being retained, in part, because of its knowledge and experience with respect to environmental matters. CSI will consider and analyse all information provided to it in the context of our knowledge and experience and all other relevant information known to us. To the extent that the information provided to us is not inconsistent or incompatible therewith, CSI shall be entitled to rely upon and assume, without independent verification, the accuracy and completeness of such information.
- f) The content of this report represents the professional opinion of experienced environmental consultants. CSI does not provide specialist legal advice and the advice of lawyers may be required.
- g) In the Summary and Recommendations sections of this report, CSI has set out our key findings and provided a summary and overview of our advice, opinions and recommendations. However, other parts of this report will often indicate the limitations of the information obtained by CSI and therefore any advice, opinions or recommendations set out in the Executive Summary, Summary and Recommendations sections ought not to be relied upon unless they are considered in the context of the whole report.
- h) The assessments made in this report are based on the ground conditions as revealed by walkover survey and/or intrusive investigations, together with the results of any field or laboratory testing or chemical analysis undertaken and other relevant data, which may have been obtained including previous site investigations. In any event, ground contamination often exists as small discrete areas of contamination (hot spots) and there can be no certainty that any or all such areas have been located and/or sampled.
- i) There may be special conditions appertaining to the site, which have not been taken into account in the report. The assessment may be subject to amendment in light of additional information becoming available.
- j) Where any data supplied by the client or from other sources, including that from previous site investigations, have been used it has been assumed that the information is correct. No responsibility can be accepted by CSI for inaccuracies within the data supplied by other parties.
- k) Whilst the report may express an opinion on possible ground conditions between or beyond trial pit or borehole locations, or on the possible presence of features based on either visual, verbal or published evidence this is for guidance only and no liability can be accepted for the accuracy thereof.
- l) Comments on groundwater conditions are based on observations made at the time of the investigation unless otherwise stated. Groundwater conditions may vary due to seasonal or other effects.
- m) This report is prepared and written in the context of the agreed scope of work and should not be used in a different context. Furthermore, new information, improved practices and changes in legislation may necessitate a reinterpretation of the report in whole or part after its original submission.
- n) The copyright in the written materials shall remain the property of the CSI but with a royalty-free perpetual license to the client deemed to be granted on payment in full to CSI by the client of the outstanding amounts.
- o) These terms apply in addition to the CSI Standard Terms of Engagement (or in addition to another written contract which may be in place instead thereof) unless specifically agreed in writing. (In the event of a conflict between these terms and the said Standard Terms of Engagement the said Standard Terms of Engagement shall prevail). In the absence of such a written contract the Standard Terms of Engagement will apply.
- p) This report is issued on the condition that CSI will under no circumstances be liable for any loss arising directly or indirectly from subsequent information arising but not presented or discussed within the current Report.
- q) In addition CSI will not be liable for any loss whatsoever arising directly or indirectly from any opinion within this report.



Enzygo Ltd
 Tel: 01454 269237
 Fax: 01454 269760
 Web: www.enzygo.com

Site Richmond			WS1
Job No CRM.1027.087	Dates Start 28-04-21 Finish 28-04-21	Ground Level (m) Co-Ordinates	
Client Hill Partnership			Sheet 1 of 1

Well	Water Levels	Samples & In Situ Testing			Depth (m)	Level (mAD)	Legend	Stratum Description	
		Depth (m)	No/Type	Results					
		0.20 - 0.40	ES		0.45			MADE GROUND: Grass over multicoloured (brown to light brown and light black) clayey to very clayey occasionally gravelly fine SAND. Gravel is subangular and subrounded, fine to coarse flint, tarmac, brick and ash.	0
					0.70			Brown sandy CLAY. Sand is fine.	
			0.90 - 1.00	D				Brown clayey fine to medium SAND.	
			1.00 - 1.45	SPT	C 7	1.30		1.00 - 1.45 Loose.	1
			1.90 - 2.00	D				Light brown slightly clayey fine to medium SAND.	
			2.00 - 2.45	SPT	C 11	2.20		Brown to light brown very sandy CLAY. Sand is fine.	2
			2.90 - 3.00	D		2.60		Light brown slightly clayey gravelly fine to medium SAND. Gravel is angular medium flint.	
			3.00 - 3.45	SPT	C 56	3.00		Light brown slightly clayey gravelly fine to medium SAND. Gravel is angular medium flint.	3
						3.45		3.00 - 3.45 Very dense, refused.	
						{4.00}		Borehole completed at 3.45m.	4

General Remarks

EQUIPMENT: Archway compact window sampling tracked rig.
 METHOD: Hand dug inspection pit 0.00m-1.00m begl. Dynamic sampled 1.00m-3.00m begl.
 CASING: Not used.
 GROUNDWATER: Groundwater not encountered.
 BACKFILL: On completion, the borehole was backfilled with arisings.

Groundwater	Date	Strike Depth (m)	Casing Depth (m)	Depth After Observation (m)
All dimensions in metres Scale 1:25				
				Logged By KC

1.0 ENZYGO WS LOG CRM.1027.087 RICHMOND.GPJ GINT STD AGS 3 - 1 ENZYGO.GPJ 3/5/21



Enzygo Ltd
 Tel: 01454 269237
 Fax: 01454 269760
 Web: www.enzygo.com

Site Richmond			WS2
Job No CRM.1027.087	Dates Start 27-04-21 Finish 27-04-21	Ground Level (m) Co-Ordinates	
Client Hill Partnership			Sheet 1 of 1

Well	Water Levels	Samples & In Situ Testing			Depth (m)	Level (mAD)	Legend	Stratum Description		
		Depth (m)	No/Type	Results						
		0.20 - 0.40	ES		0.20			MADE GROUND: Grass over multicoloured (brown to light brown and light black) clayey to very clayey very gravelly fine SAND. Gravel is subangular and subrounded, fine to coarse flint, ash and brick. 0.00 - 1.80 With roots.	0	
					0.45			MADE GROUND: Brown to black clayey very gravelly fine SAND. Gravel is angular fine to coarse flint, ash and clinker. Brown sandy CLAY. Sand is fine.		
		0.90 - 1.00	D							
		1.00 - 1.45	SPT	C 14						
					1.40				Brown clayey fine SAND.	
		1.90 - 2.00	D			1.80			Multicoloured (light brown to light grey and very light orange) clayey to locally slightly clayey, occasionally gravelly fine to coarse SAND. Gravel is rounded and subrounded fine flint. 2.00 - 2.45 Medium dense.	2
	2.00 - 2.45	SPT	C 29							
	2.90 - 3.00	D			3.00			Multicoloured (light brown to light grey and very light orange) clayey to locally slightly clayey, occasionally gravelly fine to coarse SAND. Gravel is rounded and subrounded fine flint.	3	
	3.00 - 3.45	SPT	C 53					3.00 - 3.45 Very dense, refused.		
				{4.00}	3.45			Borehole completed at 3.45m.	4	

General Remarks
 EQUIPMENT: Archway compact window sampling tracked rig.
 METHOD: Hand dug inspection pit 0.00m-1.00m begl. Dynamic sampled 1.00m-3.00m begl.
 CASING: Not used.
 GROUNDWATER: Groundwater not encountered.
 BACKFILL: On completion, the borehole was backfilled with arisngs.

Groundwater	Date	Strike Depth (m)	Casing Depth (m)	Depth After Observation (m)

All dimensions in metres
 Scale 1:25

Logged By
KC

1.0 ENZYGO WS LOG CRM.1027.087 RICHMOND.GPJ GINT STD AGS 3 - 1 ENZYGO.GPJ 3/5/21



Enzygo Ltd
 Tel: 01454 269237
 Fax: 01454 269760
 Web: www.enzygo.com

Site Richmond			WS4
Job No CRM.1027.087	Dates Start 27-04-21 Finish 27-04-21	Ground Level (m) Co-Ordinates	
Client Hill Partnership			Sheet 1 of 1

Well	Water Levels	Samples & In Situ Testing			Depth (m)	Level (mAD)	Legend	Stratum Description	
		Depth (m)	No/Type	Results					
		0.20 - 0.40	ES		0.70		MADE GROUND: Grass over multicoloured (brown to light brown and light black) clayey to very clayey occasionally gravelly fine SAND. Gravel is subangular and subrounded, fine to coarse flint, brick and ash.	0	
		0.90 - 1.00 1.00 - 1.45	D SPT	C 22	1.50		Brown CLAY. 1.00 - 1.45 Stiff, high strength.	1	
		1.90 - 2.00 2.00 - 2.45	D SPT	C 50	2.00		Multicoloured (light orange brown to light grey) gravelly fine to coarse SAND. Gravel is angular coarse flint.	2	
					2.45		Multicoloured (light orange brown to light grey) gravelly fine to coarse SAND. Gravel is angular coarse flint. 2.00 - 2.45 Very dense. Refused at 2.45m begl.	2	
				{4.00}			Borehole completed at 2.45m.	3	
								4	

General Remarks

EQUIPMENT: Archway compact window sampling tracked rig.
 METHOD: Hand dug inspection pit 0.00m-1.00m begl. Dynamic sampled 1.00m-2.00m begl.
 CASING: Not used.
 GROUNDWATER: Groundwater not encountered.
 BACKFILL: On completion, the borehole was backfilled with arisings.

Groundwater

Date	Strike Depth (m)	Casing Depth (m)	Depth After Observation (m)

All dimensions in metres
 Scale 1:25

Logged By
KC

1.0 ENZYGO WS LOG CRM.1027.087 RICHMOND.GPJ GINT STD AGS 3 - 1 ENZYGO.GPJ 3/5/21