



# Phase II Site Investigation Report

***Sheldon House, Cromwell Road, Teddington, TW11 9EJ***

Client Name: Richmond Housing Partnership

Project Number: P4301.3.0

Date: 3 August 2022

<b>Client:</b>	Richmond Housing Partnership
<b>Site:</b>	Sheldon House, Cromwell Road, Teddington, TW11 9EJ
<b>Report ref.:</b>	P4301.3.0
<b>Prepared:</b>	H. Gildersleeves MSci FGS J. Gooch BSc FGS
<b>Reviewed:</b>	S. Pike MSc MEnvSc G. Dowlen MSc CGeol FGS RoGEP EurGeol
<b>Approved:</b>	S. Pike MSc MEnvSc
<b>Date:</b>	03 August 2022
<b>Version:</b>	Final

agb Environmental Ltd has prepared this document in accordance with the instructions of the client, Richmond Housing Partnership, for their sole and specific use. Any other persons who use any information contained herein do so at their own risk.

© agb Environmental Ltd 2022

1, The Mill, Copley Hill Business Park, Babraham Road, Cambridge, CB22 3GN

Tel: 01223 776 117

[www.agbenvironmental.co.uk](http://www.agbenvironmental.co.uk)

Revision	Description	Date
.0	Final	03 August 2022



**agb Environmental Ltd**

## Executive Summary

### Client and Site Location

The client, Richmond Housing Partnership, commissioned agb Environmental to complete a Phase II ground investigation at Sheldon House, Cromwell Road, Teddington, TW11 9EJ.

### Development Proposals

Development proposals are understood to include the demolition of the existing 7-storey residential block and replacement with a 31-unit, 5-storey residential block with car parking provisions and a communal garden area.

### Summary of Encountered Ground Conditions

Made Ground was encountered from surface level in all exploratory hole positions to a maximum depth of 0.60mbgl.

Beneath the Made Ground superficial geology of the Kempton Park Gravel Member was initially encountered as medium dense, becoming dense and then very dense with depth, variably silty, sometimes slightly gravelly sand, to 1.20-3.70mbgl, succeeded by either dense sandy silt (to 1.20-1.40mbgl) or medium dense to very dense, variably silty, sometimes cobbly, gravelly to very gravelly sand (to 1.30-3.10mbgl). In CP01 the Kempton Park Gravel Member continued as dense orange sand with chert gravel and cobbles from 3.70mbgl to a maximum depth of 7.30mbgl.

Underlying the superficial geology was the London Clay Formation, encountered as a firm to stiff grey clay to 9.50mbgl, followed by claystone to 10.40mbgl, and stiff grey clay with occasional claystone patches to 25.00mbgl.

A groundwater seepage was encountered at 2.2mbgl during the formation of borehole CP01. During monitoring groundwater was observed in CP01 between 4.13mbgl and 4.19mbgl.

### Summary of Analysis, Screening and Monitoring Results

Elevated concentrations of lead and four congeners of polycyclic aromatic hydrocarbons have been identified in soil samples from four locations at depths between 0.20mbgl and 1.00mbgl. These concentrations exceed the screening values for residential developments, both with and without homegrown produce. Two of the exceedances are from an area within the proposed future soft landscaping.

Elevated concentrations of cadmium, nickel and zinc have been identified in groundwater sampling which exceed water quality standards for surface water. These exceedances were found in the first round of monitoring only.

The exceedances in relation to surface water quality standards are not considered to be significant given the industrial history of the surrounding area and the lack of exceedances during a subsequent round of monitoring and sampling. The closest surface water receptor is a lake in Bushy Park, located approximately 850m south of site. Given the distance to the identified receptor, an unacceptable risk is not considered to be present.

Ground gas monitoring results and subsequent classification indicate CIRIA 665 Characteristic Situation CS-1 is appropriate for the site based on monitoring undertaken.

Based on the conceptual site model and risk assessment there is a considered to be moderate geoenvironmental risk to end users.

It is recommended that delineation through further sampling and testing could be considered in the proposed soft landscaping area to the south of the new building. This may remove the need for soil remediation to be completed, or reduce the area requiring remediation.

In the absence of a delineation exercise remedial works will be required in the proposed new landscaping area to the south of the proposed building to address the risks identified. A remedial strategy must be undertaken and submitted to the Local Planning Authority prior to any of the aforementioned works being undertaken. Any remediation undertaken would then require validation to show that the identified risks have been adequately addressed.

Excavations within the root protection zones of trees on site should have consideration for the NHBC trees standards and root protection areas associated with the existing trees on site and adjacent to site. The Local Planning Authority Tree Officer should be contacted to discuss options.

Based on the soil testing results, waste soils to be removed from site should be classified as **Non-Hazardous**, categorised as 17 05 04 in the List of Waste from WM3. WAC testing was undertaken for completeness and samples failed the Inert Waste WAC limits. Therefore, as per EA guidance '*Dispose of Waste to Landfill*' (published January 2020), excavated soils to be removed off-site meet the requirements for disposal at a landfill for non-hazardous waste.

We would recommend that this report be forwarded to the relevant statutory consultees including the Environment Agency and Local Authority to seek their comments and subsequent approval prior to site works commencing.

#### Geotechnical Comments

It is anticipated that finished ground levels will be at, or close to, existing ground levels. Should this not be the case then this assessment may need to be reviewed.

Based on the site investigation data and testing currently available, for a 1.0m wide strip/trench fill foundation, bearing on the underlying natural coarse Kempton Park Gravel Member soils at a depth of 1.0m, a design bearing resistance of 300kN/m<sup>2</sup> is considered appropriate. For a 1.0m wide strip/trench fill foundation at a depth of 2.0m, a design bearing resistance of 350kN/m<sup>2</sup> should be available.

Alternatively for a 2.0m square pad foundation also bearing on the underlying natural coarse Kempton Park Gravel Member soils at a depth of 1.0m, a design bearing resistance of 285kN/m<sup>2</sup> should be available. For a 2.0m square pad foundation at 2.0m, a design bearing resistance of 325kN/m<sup>2</sup> should be available.

The above values should result in total settlements of not more than 25mm, keeping differential settlements within acceptable limits.

If structural loads cannot be accommodated on shallow strip/pad foundations, then it would be necessary to consider a piled design.

Shallow ground conditions on site comprise approximately 600mm of made ground overlying natural coarse soils. Grubbing out of existing foundations and services may disturb the ground

to a deeper and greater extent. At this stage consideration should be given to adopting a suspended floor slab. Whilst the natural coarse soils could be considered a suitable formation for ground bearing slabs following proof rolling any Made Ground/disturbed ground would need to be removed and replaced with selected compacted granular materials. During preparation, the formation should be inspected and any soft or unsuitable materials should be removed and replaced with a suitable compacted granular fill.

A CBR value of 2% is considered suitable for underlying made ground following treatment. It is recommended that once the site has been graded to the appropriate pavement formation level, it is inspected and, if necessary, in situ CBR testing be conducted on the subgrade to confirm the appropriate pavement design.

Analysis indicates an ACEC Class of DS-1 / AC-1 for the Made Ground, underlying Kempton Park Gravel Member and groundwater. An ACEC Class of DS-4/AC-4 is recommended for the London Clay Formation. The London Clay Formation has been designated a design sulphate class of DS-4/AC-4 based on the Total Potential Sulphate values calculated. However, it is recognised that given the depth of the London Clay on site oxidation is unlikely and concrete placed within this strata is therefore also unlikely to be exposed to ground that has been disturbed. A lower design sulphate class could therefore be considered if for example piled foundations were to be placed into the London Clay.

## Contents

1	Introduction .....	8
1.1	Development Proposals .....	8
1.2	Previous Reports .....	8
1.3	Purpose of Investigation .....	8
2	Site Details.....	9
2.1	Location and Topography.....	9
2.2	Site Description .....	9
3	Summary of Desk Study Information .....	10
3.1	Anticipated Ground Conditions and Permeability .....	10
3.2	Geological and Engineering Hazards .....	10
3.3	Radon .....	10
3.4	Hydrogeology and Hydrology .....	10
3.5	Summary of Site History .....	10
4	Preliminary Conceptual Site Model and Risk Assessment .....	11
4.1	Potential Contaminant Sources .....	11
4.2	Pathways .....	12
4.3	Receptors .....	12
4.4	Preliminary Conceptual Site Model .....	13
5	Fieldwork and Analysis .....	15
5.1	Site Investigation .....	15
5.1.1	Cable Percussive Boreholes .....	15
5.1.2	Trial Pits .....	15
5.1.3	Dynamic Sampling Boreholes .....	15
5.1.4	Plate Bearing Tests .....	15
5.1.5	Standpipe Installations and Monitoring .....	16
5.2	Laboratory Analysis .....	16
6	Ground Conditions.....	18
6.1	Encountered Ground Conditions .....	18
6.1.1	Made Ground .....	18
6.1.2	Kempton Park Gravel Member.....	18
6.1.3	London Clay Formation .....	19
6.1.4	Groundwater.....	19
6.1.5	Visual and Olfactory Evidence .....	19

7	Chemical Laboratory Test Results and Monitoring .....	20
7.1	Soil Analysis .....	20
7.2	Groundwater Analysis .....	20
7.3	Aggressive Ground .....	20
7.4	Ground Gas Monitoring .....	20
7.5	Soil Analysis and Screening Results .....	22
7.6	Groundwater Analysis and Screening Results .....	26
7.7	Aggressive Ground Analysis .....	29
7.8	Ground Gas Monitoring Results .....	30
8	Updated Risk Assessment.....	31
8.1	Discussion of Results, Screening and Monitoring Results .....	31
9	Waste Classification .....	33
9.1	Soil Waste Classification .....	33
9.2	Soil Waste Disposal.....	33
10	Updated Conceptual Site Model and Qualitative Risk Assessment .....	34
11	Contamination Conclusion and Recommendations.....	36
11.1	Conclusion.....	36
11.2	Recommendations.....	36
11.2.1	Delineation / Remediation .....	36
11.2.2	Protection of Ground Workers.....	37
11.2.3	Watching Brief .....	37
11.2.4	Buried Services .....	37
11.2.5	Importing and Re-Use of Soil and Materials Management Plan.....	37
11.2.6	Soil Disposal.....	37
11.2.7	Statutory Authority Consultation.....	38
12	Geotechnical Assessment .....	39
12.1	Summary of Proposals and Ground Conditions .....	39
12.1.1	Development Proposals .....	39
12.1.2	Summary of Ground Conditions and Test Results .....	39
12.2	Foundations.....	42
12.3	Stability of Excavations and Dewatering Considerations .....	43
12.4	Floor Slabs .....	43
12.5	Hardstanding .....	44
12.6	Chemical Attack on Buried Concrete.....	44
13	Limitations.....	45

## Appendices

- Appendix 1 Plans
- Appendix 2 Fieldwork Records
- Appendix 3 Monitoring Results
- Appendix 4 Laboratory Results
- Appendix 5 CSM Risk Evaluation Methodology



## 1 Introduction

The client commissioned agb Environmental to complete a Phase II Ground Investigation at Sheldon House, Cromwell Road, Teddington, TW11 9EJ.

### 1.1 Development Proposals

Development proposals are understood to include the demolition of the existing 7 storey residential block and replacement with a 31-unit, 5 storey residential block with car parking and communal garden areas. Proposal plans are provided in **Appendix 1**.

Prior to demolition the current 7-storey structure should be inspected for presence of asbestos containing materials (ACM). Should such materials be present these will need to be removed by specialist licensed contractors prior to demolition. The current 7-storey structure is likely to be constructed on a piled foundation. Grubbing out of substructures will need to establish the location of any such piles if present to establish if the pile positions conflict with potential pile locations for the proposed 5-storey structure.

### 1.2 Previous Reports

A Phase I geoenvironmental desk study for the site and the surrounding area was completed by agb Environmental Ltd, report reference P4301.2.0, dated 15<sup>th</sup> June 2022, and should be read in conjunction with this report.

### 1.3 Purpose of Investigation

The principal technical objectives of the report were as follows:

- Review of desk study information,
- Establish the ground conditions,
- Undertake analysis of selected soil samples and groundwater samples,
- Provide a Conceptual Site Model (CSM) and risk assessment,
- Provide geoenvironmental recommendations, and
- Provide geotechnical recommendations for foundation design, floor slabs, pavements, excavations, groundwater control and chemical attack.

The report has been formulated in general accordance with BS10175:2011+A2:2017 Investigation into Potentially Contaminated Sites – Code of Practice, Environment Agency LCRM guidance, BS5930:2015 Code of Practice for Site Investigations, and guidance from the National Planning Policy Framework.

## 2 Site Details

Details regarding the site and anticipated ground conditions extracted from the desk study are provided below.

### 2.1 Location and Topography

The irregularly shaped site is located in an urban area approximately 275m south-east of Teddington railway station in the suburb of Teddington, within the London Borough of Richmond upon Thames. The site covers an area of approximately 0.16ha and is centred at National Grid Reference 516263 170626. The site is at an elevation of approximately 10mOD, and the surrounding land is generally level. A location plan is presented in **Appendix 1**.

### 2.2 Site Description

The site fronted and was accessed via Cromwell Road to the north. The hardstanding areas in the north of site were noted to be relatively level. Towards the south west of site the areas of soft landscaping slope gently downwards to the south. The western soft landscaped planted area was raised 0.20m from surface level.

Vegetation comprised the entire southern half of site and consisted of mowed grass, with mature bushes and trees lining the southern boundaries. At the west and north of site is a small soft landscaped, planted area. In the north, and central area of site are large >6m trees. There is a singular large building within the centre of site. It is a red brick apartment block, which is seven storeys, and consists of several garages on the ground floor. The building is relatively square in shape. There are no other structures on site.

Towards the north and west of site are a selection of parking spaces bordering the northern boundary and surrounding the access. It is estimated that 50% of the site consists of permeable soft landscaping and 50% comprising concreted, hard landscaping.

### **3 Summary of Desk Study Information**

Salient information extracted from the desk study report is provided below.

#### **3.1 Anticipated Ground Conditions and Permeability**

Based on the BGS mapping the site is underlain by superficial geology of the Kempton Park Gravel Formation, which is in turn underlain by bedrock geology of the London Clay Formation. There are no records of artificial or made ground deposits within 250m of site.

#### **3.2 Geological and Engineering Hazards**

According to BGS data, the highest risk on site is very low from running sands, collapsible deposits, and landslides. There is a negligible risk from shrink-swell clays, compressible deposits and the ground dissolution of soluble rocks.

#### **3.3 Radon**

The study site is not located within a Radon Affected Area, as less than 1% of properties are above the Action Level. Therefore, no radon protective measures are necessary for new properties or extensions to existing ones as described in Building Research Establishment (BRE) publication BR211.

#### **3.4 Hydrogeology and Hydrology**

The superficial geology on site is classed as a Principal aquifer and the bedrock is designated unproductive. There are no abstraction licences noted within 500m of site and no surface water features within 250m of site.

#### **3.5 Summary of Site History**

Historical development of site began in 1896 with small structures, which underwent several smaller redevelopments up to the year of 1971, where the site structures were replaced by the apartment block seen during the walkover. Significant residential development and redevelopment of the surrounding site began in 1913 and continued till 1994. The railway 2m south of site has been present since 1840.

## 4 Preliminary Conceptual Site Model and Risk Assessment

An initial CSM and preliminary assessment of plausible contaminant source-pathway-receptor linkages is presented in this section. It is aimed at identifying possible risks, if any, arising from substances used or deposited on-site, or from other sources of land contamination. Both past and current potentially contaminative land uses have been considered.

### 4.1 Potential Contaminant Sources

Based on the site walkover and desk study research, the identified potentially contaminative land uses on or within the vicinity of the site are summarised in **Table 4.1**.

**Table 4.1** Potential Contaminant Sources

Identified Potentially Contaminative Land Uses / Sources	Distance From Site (approx.)	Potential Contaminants Associated with Identified Sources	Plausible S-P-R Contaminant Linkage?
Made Ground (from previous development on site), potential asbestos containing materials.	On site	Metals, Polycyclic Aromatic Hydrocarbons (PAH), Total Organic Hydrocarbons (TOH), Asbestos Containing Materials (ACMs). Soil gas generation (including CH <sub>4</sub> and CO <sub>2</sub> ).	<b>Yes</b> – given the historical development of the site, a potential contaminant source may be present with the potential to impact site.
Railway Sidings	2m south-west to 19m south-west (1840-present day)	Metals, TPH, PAHs, ACMs, polychlorinated biphenyls (PCBs), acids, alkalis, sulphates.	<b>Yes</b> – potential contaminant source is present with the potential to impact site.
Unspecified Pit	41m north (1938)	Metals, TPH, PAHs, ground gasses, vapour.	<b>No</b> - Given and the significant time passed, and how relatively small the pit is, it is considered unlikely that there would be any impact to site.
Three historical tanks	137m south (1896) 236m north (1994) 248m north (1934).	TPH, Semi Volatile Organic Compounds (SVOCs), Volatile Organic Compounds (VOCs).	<b>No</b> - Given the distance from site and significant time since, it is considered unlikely that there would be any impact to site.
Historical ponds	103-111m south and south-east (1938 and 1945)	Metals, TPH, PAHs, ground gasses, vapour.	<b>Yes</b> – Although given the distance from site and significant time since, it is considered that because of its large size it is likely to be a potential contaminant source to site.
Historical and current electricity substation	Historical (53m west 153m east)  Current (57m west)	PCBs, Metals, TPH, PAHs.	<b>No</b> – given the distance from site combined with the low mobility, hydrophobic nature and high viscosity of PCB oils, it is considered unlikely that there would be any impact to site from historical or recent potential contaminant leaks.

## 4.2 Pathways

For this assessment, the principal potential pathways for contaminant migration are provided in **Table 4.2**.

**Table 4.2** Pathways

Source	Pathway
Soil / dust / fibres	Dermal contact, ingestion and inhalation.
Liquid (including surface water / groundwater)	Dermal contact, ingestion. Leaching, infiltration and migration through groundwater. Preferential pathways such as service trenches.
Harmful ground gases / vapour	Migration through permeable geological strata and preferential pathways. Inhalation, accumulation within confined spaces with subsequent asphyxiation or explosion.

## 4.3 Receptors

Based on the proposals and the findings of the desk study the identified receptors are described in **Table 4.3**.

**Table 4.3** Receptors

Receptor	Detail
Site workers	Site workers are anticipated to include those involved with the construction works and long-term maintenance on site.
End users	Residents and visitors.
Neighbouring sites	Residents, visitors and workers.
Controlled Waters	The underlying superficial deposits is designated a principal aquifer underlain by bedrock geology designated as unproductive. The site is not within a Source Protection Zone and there are no abstractions or water features within 250m of site.
Flora and fauna	Plants and animals that may be affected by proposed development. Soft landscaping is anticipated as part of proposals.
Buildings	The completed building and neighbouring residential structures.
Buried services	Potable water pipes are anticipated as part of proposals.

#### 4.4 Preliminary Conceptual Site Model

The preliminary conceptual site model presented in **Table 4.4** has been derived using the findings of the desk study. The risk evaluation methodology is presented in **Appendix 5**.

**Table 4.4** Preliminary Conceptual Site Model

Source	Pathway	Receptor	Consequence	Probability	Potential Risk	Detail
<p><b>On site</b> Made Ground (from previous site development).  Potential asbestos containing materials (within on site buildings).  (Metals, TPHs, PAHs, AMCs, PCBs and ground gases/vapour.).</p>	Dermal contact, ingestion and inhalation of contaminated soil, dust and/or fibres	End users	Medium	Likely	Moderate	Contact is likely between future site users/visitors in shallow soils in the proposed soft landscaping areas of the site, soil/dust tracked back into premises, and potentially from ingestion of produce grown on site. The historical age of various structures and outbuildings is such that the presence of asbestos cannot be discounted. Future site workers are likely to come into direct contact with soils during groundworks. Safe working practices should be implemented, and appropriate personal protective equipment (PPE) should be used to mitigate any potential risk.
		Site workers	Medium	Likely	Moderate	
		Adjacent users	Medium	Likely	Moderate	
	Leaching / infiltration through soils and migration via groundwater or soil pore moisture.	Controlled waters	Medium	Likely	Moderate	There is no current evidence to suggest that groundwater quality beneath the site is affected by contaminant leaching. The superficial geology is a principal aquifer, and the bedrock geology is designated as unproductive. The site is not located within a SPZ. Any potential contamination could have a significant impact on receptors and cannot be presently ruled out.
	Permeation of water pipes.	Construction materials, future end users	Medium	Likely	Moderate	Hydrocarbons, especially aromatics and chlorinated solvents, are known to permeate plastic pipes. Provision of water supply pipes and connectors formed from proprietary "barrier pipe" materials (e.g., polyethylene aluminium-polyethylene) may be required by the water supply company.
	Gas Migration and build up within buildings.	Future end users and building structures	Severe	Low likelihood	Moderate	A moderate risk is considered given the potential for Made Ground to be present and from the historical redevelopment which has occurred on site. The high permeability of the underlying superficial geology, potential contaminant migration could impact the site.
Plant Uptake	Flora and Fauna	Medium	Likely	Moderate	Phytotoxic contamination as a consequence of historical and current land uses is likely due to the made ground from redevelopment at the site.	

Source	Pathway	Receptor	Consequence	Probability	Potential Risk	Detail
<p><b>Off site</b> Railway sidings (1840 – present day)</p> <p><i>(Metals, TPHs, PAHs, PCBs and ground gases/vapour.)</i></p>	Dermal contact, ingestion and inhalation of contaminated soil, dust and/or fibres	End users	Medium	Low likelihood	Moderate / low	Contact is likely between future residential occupiers/visitors in shallow soils in the proposed garden area of the site, soil/dust tracked back into premises, and from ingestion of home grown produce. Future site workers are likely to come into direct contact with soils during groundworks. Safe working practices should be implemented, and appropriate personal protective equipment (PPE) should be used to mitigate any potential risk.
		Site workers	Medium	Low likelihood	Moderate / low	
	Leaching / infiltration through soils and migration via groundwater or soil pore moisture.	Controlled waters	Medium	Unlikely	Moderate	There is no current evidence to suggest that groundwater quality beneath the site is affected by contaminant leaching. The superficial geology is a principal aquifer, and the bedrock geology is designated as unproductive. The site is not located within a SPZ. Any potential contamination could have a significant impact on receptors and cannot be presently ruled out.
	Permeation of water pipes.	Construction materials, future end users	Medium	Likely	Moderate	Hydrocarbons, especially aromatics and chlorinated solvents, are known to permeate plastic pipes. Provision of water supply pipes and connectors formed from proprietary “barrier pipe” materials (e.g., polyethylene aluminium-polyethylene) may be required by the water supply company.
	Gas Migration and build up within buildings.	Future end users and building structures	Severe	Low likelihood	Moderate	A moderate risk is considered given the significant development surrounding the site and unspecified and infilled pits. The high permeability of the underlying superficial geology, potential contaminant migration could impact the site.
	Plant Uptake	Flora and Fauna	Mild	Low likelihood	Low	Phytotoxic contamination as a consequence of historic and current land uses is unlikely.

## 5 Fieldwork and Analysis

The works undertaken as part of the site investigation and subsequent analysis of selected samples is summarised below.

### 5.1 Site Investigation

The locations of the exploratory holes were selected based on available access, the objectives of the investigation and proposed development plans.

Statutory services plans were obtained by agb Environmental. Prior to breaking ground, a cable avoidance tool and signal generator were used to confirm each location was clear of detectable services.

The exploratory hole location plan and fieldwork records are presented in **Appendix 2**. The exploratory holes completed as part of the investigation are detailed below.

#### 5.1.1 Cable Percussive Boreholes

One cable percussive borehole referenced CP01 was drilled between 30<sup>th</sup> June 2022 and 5<sup>th</sup> July 2022 to a depth of 25m bgl. Prior to boring CP01, a service inspection pit was excavated to a depth of 1.20mbgl using hand tools to confirm the absence of services. This borehole was advanced in 200mm diameter casing to a depth of 8mbgl, followed by 150mm diameter to a depth of 25mbgl.

Small or bulk disturbed, and undisturbed samples were taken at regular intervals. Standard Penetration Tests (SPTs) were undertaken at intervals to provide an indication of the strength or density of the soil, the results are presented as 'N' values on the borehole logs. Excess spoil was transferred to a skip for off-site disposal by a licensed waste carrier.

#### 5.1.2 Trial Pits

A total of three trial pits, referenced TP01 to TP03, were excavated on 29<sup>th</sup> June 2022. The trial pits were advanced using a JCB 3CX and completed to depths between 3.00mbgl and 3.10mbgl. Small, and bulk disturbed samples were taken at regular intervals.

#### 5.1.3 Dynamic Sampling Boreholes

A total of 4 dynamic sampling (windowless) boreholes, referenced WS01 to WS04, were formed on 28<sup>th</sup> June 2022. The boreholes were completed to depths between 1.30mbgl and 2.00mbgl, the density of the deposits preventing deeper penetration. The sampling equipment comprised of a track-mounted rig used to drive successive 1.00m long, lined 90mm to 50mm diameter core sample barrels into the ground. The recovered plastic core barrel 'liners' were split, logged and sub-sampled on-site by an engineer, and the samples, taken at regular intervals throughout the length of the boreholes, were placed in laboratory supplied sealed glass jars or plastic containers prior to being stored in cool boxes during transit to the laboratory. Soil penetration tests (SPTs) were undertaken at regular intervals in the boreholes to provide data regarding the strength or density of the soil, the result of each test is presented as the 'N' value on the borehole logs.

#### 5.1.4 Plate Bearing Tests

Plate bearing tests were completed at six locations, referenced CBR01 to CBR06. The tests were completed either at ground level or at a depth of up to 0.2mbgl, using an 8.5t excavator as a reaction load and a 452mm diameter plate. The results are provided in **Appendix 2**.



### 5.1.5 Standpipe Installations and Monitoring

Single standpipe installations were placed into boreholes WS02 and WS04; these comprised of 50mm diameter PTFE piping, plain from surface level to 0.50mbgl, slotted between 0.50mbgl and 1.90-2.00mbgl, and installed to a depth of 1.90-2.00mbgl. Once introduced into the ground the slotted section was surrounded by suitable gravel pack, above which a sealing material (bentonite) was used. A rubber bung with a gas tap was placed at the top of the pipework and a flush cover concreted at surface to protect the installation from damage.

A single standpipe installation was placed in CP01, comprised of 50mm diameter PTFE piping, plain from surface level to 1.00mbgl, slotted between 1.00mbgl and 10.00mbgl, and installed to a depth of 10.00mbgl. Arisings were placed into the borehole between 25.00mbgl and 12.00mbgl, above which a bentonite seal was placed between 12.00mbgl and 10.00mbgl prior to the introduction of the standpipe. Once introduced into the ground the slotted section was surrounded by suitable gravel pack, above which a sealing material (bentonite) was used. A rubber bung with a gas tap was placed at the top of the pipework and a flush cover concreted at surface to protect the installation from damage.

The standpipes were monitored on two occasions between 11<sup>th</sup> July and 21<sup>st</sup> July 2022. The ground gas flow was monitored for a period of up to two minutes, the concentration of volatile organic compounds (VOCs) was monitored for a period of up to three minutes and the concentrations of ground gases including methane, carbon dioxide, hydrogen sulphide and carbon monoxide were monitored for up to five minutes.

The groundwater was sampled and monitored from the deep install of CP01. The monitoring results are presented in **Appendix 3**.

## 5.2 Laboratory Analysis

The scheduled chemical analysis and number of samples tested is summarised **Table 5.1**; the scheduled geotechnical laboratory testing is summarised in **Table 5.2**. The results are presented in **Appendix 4**.

**Table 5.1** Summary of Scheduled Contamination Testing

Analysis	No. of Samples Tested	
	Soil	Groundwater
Metals	6	2
Speciated polycyclic aromatic hydrocarbons (PAHs) (USEPA 16 – PAHs)	6	2
Total petroleum hydrocarbons (CWG Aromatic/Aliphatic Split)	6	2
BTEXMTBE	6	2
Asbestos screening	6	-
pH	16	2
Soil organic matter (SOM)	6	-
Polychlorinated Biphenyls	1	-
Total Sulphate (as SO <sub>4</sub> )	10	-
Total Sulphur	10	-
Water Soluble Sulphate (SO <sub>4</sub> )	10	2
Waste Acceptance Criteria Testing (BS EN 12457/3)	2	-

**Table 5.2** Summary of Scheduled Geotechnical Testing

<b>Test</b>	<b>No. of Soil Samples Tested</b>
Plasticity index	10
Natural Water Content	10
Particle Size Distribution	3
Triaxial Test	4

## 6 Ground Conditions

The encountered ground conditions are summarised below.

### 6.1 Encountered Ground Conditions

The ground conditions encountered are summarised in **Table 6.1** and discussed below.

**Table 6.1** Summary of Encountered Ground Conditions

Stratum	Location	Surface Depth (mbgl)	Base Depth (mbgl)	Thickness (m)
Made Ground	All positions	0.00	0.30 to 0.60	0.30 to 0.60
Kempton Park Gravel Member	All positions	0.30-0.60	≥1.30* to 7.30	≥0.70 to 6.90
London Clay Formation	CP01	7.30	≥25.00*	≥17.70
Groundwater	Groundwater seepage was noted in CP01 at 2.2mbgl during the intrusive site investigation works. No groundwater was encountered in the dynamic sampling boreholes or trial pits.  During monitoring, groundwater was observed between 4.12mbgl and 4.19mbgl in borehole CP01; the dynamic sampling boreholes were dry.			

\* base of stratum not proven at all borehole locations

#### 6.1.1 Made Ground

Made Ground was encountered from surface level in all exploratory hole positions.

This was encountered from surface level as concrete with 7-8mm diameter rebar in positions CP01, WS01 and WS04 to a maximum depth of 0.20mbgl. Underlying the concrete in these positions was brown or dark grey gravelly sand, sand and gravel, or brick and concrete rubble to depths between 0.30 and 0.60mbgl. Gravel comprised brick, chert, limestone and concrete with rare clinker.

In position TP02, the Made Ground was encountered from surface level to a maximum depth of 0.30mbgl as dark brown silty sand. Sand was fine.

In positions TP01, TP03, WS02 and WS03, the Made Ground was encountered from surface level as dark brown, sometimes slightly gravelly, slightly silty to silty sand or slightly gravelly to gravelly sandy silt. Gravel was brick, chert and concrete with occasional brick, glass, clinker and porcelain. Occasional concrete and chert cobbles. Glass, metal and porcelain were notably abundant in the Made Ground at WS03 and concrete was abundant in TP03.

The base of the Made Ground was proven to depths between 0.30mbgl and 0.40mbgl in positions CP01, TP01-TP03 and WS04, and to a maximum depth of 0.60mbgl in positions WS01, WS02 and WS03.

#### 6.1.2 Kempton Park Gravel Member

Beneath the Made Ground in all positions the natural geology was initially encountered as medium dense to very dense, brown, yellowish brown or dark grey, sometimes slightly silty to very silty, sometimes slightly gravelly sand to depths between 1.20mbgl and 3.70mbgl. Gravel was chert, generally rounded or recovered fractured. The sand or slightly gravelly sand was succeeded by stiff yellowish brown, sometimes gravelly, sandy silty clay in positions TP03, WS02 and WS03 to depths between 1.20mbgl and 1.40mbgl. The sand became medium dense to very dense brown or yellowish brown, sometimes slightly silty to silty, sometimes cobbly, gravelly to very gravelly, sand from 1.20-1.60mbgl to the base of most positions at

≥1.30mbgl to ≥3.10mbgl. In CP01 the brown cobbly gravelly fine sand was succeeded by orange sand with some chert gravel and cobbles from 3.70mbgl to a maximum depth of 7.30mbgl.

These strata are initially fine sand-dominated, generally becoming gravelly to very gravelly at 1.20-1.60mbgl, and are considered representative of the Kempton Park Gravel Member, which is shown on the BGS mapping to underlie the site. All positions except CP01 were completed in the Kempton Park Gravel Member between 1.30mbgl and 3.10mbgl.

#### 6.1.3 London Clay Formation

The London Clay Formation was encountered beneath the Kempton Park Gravel Member in CP01 only, at a depth of 7.30mbgl. This stratum was encountered as a firm to stiff grey clay between 7.30mbgl and 9.50mbgl, followed by a claystone from 9.50mbgl to 10.40mbgl, overlying a stiff to very stiff grey clay with occasional patches of claystone between 10.40mbgl and 25.00mbgl.

CP01 was completed in the London Clay Formation at 25.00mbgl; the base of the stratum was not proven.

#### 6.1.4 Groundwater

Groundwater was not observed during the formation of the dynamic sampling boreholes or the trial pits. A groundwater seepage was noted in cable percussive borehole CP01 at 2.2mbgl.

During monitoring, groundwater was observed in CP01 between 4.12mbgl and 4.19mbgl.

#### 6.1.5 Visual and Olfactory Evidence

During the site investigation works and subsequent monitoring there were no visual or olfactory indications of gross contamination in soils or groundwater. The presence of Made Ground across the site could be a potential indicator of the presence of contaminants in soil.

## 7 Chemical Laboratory Test Results and Monitoring

The results of chemical laboratory testing and ground gas monitoring are detailed in the following section.

### 7.1 Soil Analysis

Based on the proposed end use as a residential development, with the incorporation of soft landscaping, the variability of Made Ground encountered and the results of soil organic matter content testing results, the results of chemical laboratory testing of soil samples for inorganic and organic compounds have been compared against screening criteria for residential with homegrown produce end use with 1.0% soil organic matter content as this is the most appropriate generic assessment criteria (GAC) applicable. The screening criteria hierarchy used is as follows:

- Chartered Institute of Environmental Health (CIEH) and Land Quality Management Ltd (LQM) Suitable for Use Levels (S4ULs).
- Department for Environment Food and Rural Affairs (Defra) Category 4 Screening Levels (C4SLs).
- Contaminated Land: Applications in Real Environments (CL:AIRE) soil generic assessment criteria (GACs).
- Environment Agency: Soil Guideline Values (SGVs)

Screening levels for certain organic contaminants have been selected based on laboratory testing for soil organic matter (SOM) content. A conservative SOM of 1% has been considered appropriate for this risk assessment based on the range recorded by laboratory testing in Made Ground samples.

### 7.2 Groundwater Analysis

The superficial geology on site is classed as a Principal aquifer and the bedrock is designated unproductive. There are no abstraction licences noted within 500m of site and no surface water features within 250m of site.

In order to assess the risk to surface water from potential contaminants, the results of groundwater analysis have been compared to water quality standards provided in:

- The Water Framework Directive (Standards and Classification) Directions (England and Wales) 2015 (WFD, 2015).
- The Water Supply (Water Quality) Regulations 2016 (WSR).
- WHO - Guidelines for Drinking-Water Quality, Fourth Edition Incorporating the First Addendum (WHO, 2017).

### 7.3 Aggressive Ground

The results of testing for aggressive ground conditions have been classified using values provided in BRE Special Digest 1:2005: Concrete in aggressive ground.

### 7.4 Ground Gas Monitoring

Where applicable the results of ground gas and volatile organic compound (VOC) monitoring have been compared to:

- CIRIA 665: Assessing risks posed by hazardous ground gases to buildings.

- BS 8485:2015: Code of practice for the design of protective measures for methane and carbon dioxide ground gases for new buildings.
- HSE EH40/2005 Workplace exposure limits.

## 7.5 Soil Analysis and Screening Results

**Table 7.1** Results of Laboratory Analysis for Metals

Determinand <i>Metals</i>	Determinand / Concentration Range (mg/kg)		Screening Values for Residential with Homegrown Produce Land Use (mg/kg)		No. of Samples with Elevated Concentrations	Samples with Elevated Concentrations
	<i>Minimum</i>	<i>Maximum</i>	<i>S4ULs</i>	<i>C4SLs</i>		
Arsenic	9	26	37	-	0	None elevated
Cadmium	< 0.2	0.5	11	-	0	None elevated
Chromium (III)	13	19	910	-	0	None elevated
Chromium (VI)	< 2	< 2	6	-	0	None elevated
Copper	7	63	2400	-	0	None elevated
Lead	16	635	-	210	3	CP01 – 0.30m TP01 – 0.20m WS03 – 0.30m
Mercury	< 1	< 1	40	-	0	None elevated
Nickel	11	16	130	-	0	None elevated
Selenium	< 3	< 3	250	-	0	None elevated
Zinc	40	589	3,700	-	0	None elevated

**Table 7.2** Results of Laboratory Analysis for Polycyclic Aromatic Hydrocarbons

Determinand <i>PAHs</i>	Concentration Range (mg/kg)		Screening Values for Residential with Homegrown Produce Land Use (mg/kg)		No. of Samples with Elevated Concentrations	Samples with Elevated Concentrations
	Minimum	Maximum	S4ULs	C4SLs		
			1% som			
Naphthalene	< 0.1	0.12	2.3	-	0	None elevated
Acenaphthylene	< 0.1	1.15	170	-	0	None elevated
Acenaphthene	< 0.1	0.35	210	-	0	None elevated
Fluorene	< 0.1	1.65	170	-	0	None elevated
Phenanthrene	< 0.1	18	95	-	0	None elevated
Anthracene	< 0.1	4.44	2,400	-	0	None elevated
Fluoranthene	< 0.1	28.7	280	-	0	None elevated
Pyrene	< 0.1	25.1	620	-	0	None elevated
Benzo[a]anthracene	< 0.1	13.3	7.2	-	1	WS02 – 1.00m
Chrysene	< 0.1	11	15	-	0	None elevated
Benzo[b]fluoranthene	< 0.1	11.5	2.6	-	1	WS02 – 1.00m
Benzo[k]fluoranthene	< 0.1	4.24	77	-	0	None elevated
Benzo[a]pyrene	< 0.1	12.6	2.2	10	1	WS02 – 1.00m
Indeno[123-cd]pyrene	< 0.1	7.38	27	-	0	None elevated
Dibenzo[ah]anthracene	< 0.1	2.07	0.24	-	3	TP01 – 0.20m WS02 – 1.00m WS03 – 0.30m
Benzo[ghi]perylene	< 0.1	6.37	320	-	0	None elevated
Total PAH	< 1.6	148	-	-	-	-



**Table 7.3** Results of Laboratory Analysis for Speciated Total Petroleum Hydrocarbons

Determinand <i>Petroleum Hydrocarbons</i>	Determinand Concentration Range (mg/kg)		Screening Values for Residential with Homegrown Produce Land Use (mg/kg)	No. of Samples with Elevated Concentrations	Samples with Elevated Concentrations
			<i>S4ULs</i>		
Speciated - Aliphatic	<i>Minimum</i>	<i>Maximum</i>	<i>1% som</i>		
>C5-C6	< 0.01	< 0.01	42	0	None elevated
>C6-C8	< 0.05	< 0.05	100	0	None elevated
>C8-C10	< 2	< 2	27	0	None elevated
>C10-C12	< 2	< 2	130	0	None elevated
>C12-C16	< 3	< 3	1100	0	None elevated
>C16-C34	< 13	< 13	65000	0	None elevated
Aliphatic C5-C34	< 21	< 21	-	-	-
Speciated - Aromatic	<i>Minimum</i>	<i>Maximum</i>	<i>1% som</i>		
>C5-7	< 0.01	< 0.01	70	0	None elevated
>C7-8	< 0.05	< 0.05	130	0	None elevated
>C8-10	< 2	< 2	34	0	None elevated
>C10-12	< 2	< 2	74	0	None elevated
>C12-16	< 2	5	140	0	None elevated
>C16-21	< 3	52	260	0	None elevated
>C21-35	< 10	114	1,100	0	None elevated
Aromatic C5-35	< 21	171	-	-	-

**Table 7.4** Results of Laboratory Analysis for BTEX and MTBE

Determinand <i>BTEX</i>	Concentration Range (mg/kg)		Screening Values for Residential with Homegrown Produce Land Use (mg/kg)	No. of Samples with Elevated Concentration	Samples with Elevated Concentrations
	Minimum	Maximum	S4ULs		
			1% som		
Benzene	< 0.002	< 0.002	0.087	0	None elevated
Toluene	< 0.005	< 0.005	130	0	None elevated
Ethylbenzene	< 0.002	< 0.002	47	0	None elevated
o-xylene	< 0.002	< 0.002	60	0	None elevated
m-xylene	< 0.002	< 0.002	59	0	None elevated
p-xylene	< 0.002	< 0.002	56	0	None elevated
Determinand <i>MTBE</i>	Minimum	Maximum	GACs	No. of Samples with Elevated Concentration	Samples with Elevated Concentrations
			1% som		
	MTBE	< 0.005	< 0.005		

**Table 7.5** PCB Analysis

Determinand	Concentration Range (mg/kg)		Screening Values for Residential with Homegrown Produce Land Use (mg/kg)	No. of Samples with Elevated Concentration	Samples with Elevated Concentrations
	Minimum	Maximum	EA SGVs		
Total PCB (12 congeners)	< 0.1	< 0.1	8	0	-

**Table 7.6** Asbestos Screening

Determinand	Screening Result	Asbestos Matrix	Asbestos Type	Quantification (%)	Samples with Detected Asbestos
Asbestos	Not Detected	-	-	-	-

## 7.6 Groundwater Analysis and Screening Results

**Table 7.7** Summary of Groundwater Analysis Results

Determinand	Determinand Concentration (ug/l)		Threshold Value (ug/l)			No. of Samples with Elevated Concentrations	Location of Samples with Elevated Concentrations
	Minimum	Maximum	Surface Water	Drinking Water	Odour or Taste Threshold		
<b>Inorganic</b>							
Arsenic	< 5	< 5	50 <sup>a</sup>	10 <sup>g</sup>	-	0	None elevated
Cadmium	< 0.4	0.4	0.08 to 0.25 <sup>a,b</sup>	5 <sup>g</sup>	-	1	CP01 – 4.15m
Chromium (III)	< 5	< 5	4.7 <sup>a</sup>	50 <sup>g</sup>	-	0	Threshold value is less than limit of detection, but no indication of contaminant impact of either soils or groundwaters.
Chromium (VI)	< 20	< 20	3.4 <sup>a</sup>	-	-	0	Threshold value is less than limit of detection, but no indication of contaminant impact of either soils or groundwaters.
Copper	< 5	< 5	1 <sup>a, i</sup>	2,000 <sup>g</sup>	5,000 <sup>l</sup>	0	Threshold value is less than limit of detection, but no indication of contaminant impact of either soils or groundwaters.
Lead	< 5	< 5	1.2 <sup>a, i</sup>	10 <sup>g</sup>	-	0	Threshold value is less than limit of detection, but no indication of significant contaminant impact of either soils or groundwaters.
Mercury	< 0.05	< 0.05	0.07 <sup>b</sup>	1 <sup>g</sup>	-	0	None elevated
Nickel	< 5	18	4 <sup>a, i</sup>	20 <sup>g</sup>	-	1	CP01 – 4.15m
Selenium	< 5	< 5		10 <sup>g</sup>	-	0	None elevated
Zinc	< 2	105	10.9 <sup>a, i, j</sup>		-	1	CP01 – 4.15m
<b>Polycyclic Aromatic Hydrocarbons</b>							
Naphthalene	< 0.01	< 0.01	2 <sup>a</sup>	0.075 <sup>d</sup>	-	0	None elevated
Acenaphthylene	< 0.01	< 0.01			-	0	None elevated
Acenaphthene	< 0.01	< 0.01			-	0	None elevated

Determinand	Determinand Concentration (ug/l)		Threshold Value (ug/l)			No. of Samples with Elevated Concentrations	Location of Samples with Elevated Concentrations
	Minimum	Maximum	Surface Water	Drinking Water	Odour or Taste Threshold		
Fluorene	< 0.01	< 0.01			-	0	None elevated
Phenanthrene	< 0.01	< 0.01			-	0	None elevated
Anthracene	< 0.01	< 0.01	0.1 a		-	0	None elevated
Fluoranthene	< 0.01	< 0.01	0.0063 a	0.075 d	-	0	Threshold value is less than limit of detection, but no indication of contaminant impact of either soils or groundwaters.
Pyrene	< 0.01	< 0.01			-	0	None elevated
Benzo[a]anthracene	< 0.01	< 0.01			-	0	None elevated
Chrysene	< 0.01	< 0.01			-	0	None elevated
Benzo[b]fluoranthene	< 0.01	< 0.01	0.017 b	0.075 d	-	0	None elevated
Benzo[k]fluoranthene	< 0.01	< 0.01	0.017 b		-	0	None elevated
Benzo[a]pyrene	< 0.01	< 0.01	0.00017 a	0.01 g	-	0	Threshold value is less than limit of detection, but no indication of significant contaminant impact of either soils or groundwaters.
Indeno[123-cd]pyrene	< 0.01	< 0.01			-	0	None elevated
Dibenzo[ah]anthracene	< 0.01	< 0.01			-	0	None elevated
Benzo[ghi]perylene	< 0.008	< 0.008	0.0082 b		-	0	None elevated
Total PAH	< 0.16	< 0.16		0.1 g	-	0	Threshold value is less than limit of detection, but no indication of contaminant impact of either soils or groundwaters.
<b>BTEX</b>							
Benzene	< 1	< 1	10 a	1 g	-	0	None elevated
Toluene	< 5	< 5	74 a	700 h	40 i	0	None elevated
Ethylbenzene	< 5	< 5	-	300 h	72 i	0	None elevated
Xylenes	< 15	< 15	30 f	500 h	300 i	0	None elevated

Determinand	Determinand Concentration (ug/l)		Threshold Value (ug/l)			No. of Samples with Elevated Concentrations	Location of Samples with Elevated Concentrations
	Minimum	Maximum	Surface Water	Drinking Water	Odour or Taste Threshold		
MTBE	< 10	< 10	-	-	15 <sup>m</sup>	0	None elevated
<b>Petroleum Hydrocarbons</b>							
Aliphatic >EC5-6	< 10	< 10	-	15000 <sup>n</sup>	-	0	None elevated
Aliphatic>EC6-8	< 10	< 10	-	15000 <sup>n</sup>	-	0	None elevated
Aliphatic>EC8-10	< 10	< 10	-	300 <sup>n</sup>	-	0	None elevated
Aliphatic>EC10-12	< 10	< 10	-	300 <sup>n</sup>	-	0	None elevated
Aliphatic>EC12-16	< 10	< 10	-	300 <sup>n</sup>	-	0	None elevated
Aliphatic>EC16-35	< 10	< 10	-	-	-	0	None elevated
Aromatic >EC5-7	< 10	< 10	-	10 <sup>n</sup>	-	0	None elevated
Aromatic >EC7-8	< 10	< 10	-	700 <sup>n</sup>	-	0	None elevated
Aromatic >EC8-10	< 10	< 10	-	300 <sup>n</sup>	-	0	None elevated
Aromatic >EC10-12	< 10	< 10	-	90 <sup>n</sup>	-	0	None elevated
Aromatic >EC12-16	< 10	< 10	-	90 <sup>n</sup>	-	0	None elevated
Aromatic >EC16-21	< 10	< 10	-	90 <sup>n</sup>	-	0	None elevated
Aromatic >EC21-35	< 10	< 10	-	90 <sup>n</sup>	-	0	None elevated
TPH	< 140	< 140	-	-	10 <sup>l, m</sup>	0	None elevated

a - Water Framework Directive (Standards and Classification), 2015 - EQS Value for Rivers based on long term mean or an annual average.

b - Water Framework Directive - Maximum Allowable Concentration for Rivers

c - Water Framework Directive - Groundwater value where end receptor is surface water

d - Water Framework Directive - Groundwater value where end receptor is drinking water supply

e - Water Framework Directive - General quality of groundwater value

f - Environment Agency "operational" target

g - Water Supply Regulations

h - WHO, 2017 - Drinking Water Standards

i - bioavailable component

j - plus Ambient Background Concentration (dissolved)

k - hardness dependant

l - WHO, 2017 - lower bound taste threshold

m - WHO, 2017 - lower bound odour threshold

n - WHO, 2008 Drinking Water Standards (adopted by CL:AIRE)

## 7.7 Aggressive Ground Analysis

**Table 7.8** Summary of Aggressive Ground Analysis

Stratum	Determinand					DS / ACEC Class
	Total sulphate (%)	W/S sulphate SO <sub>4</sub> (mg/l)	Total sulphur (%)	pH	Total Potential Sulphate	
Made Ground	0.03	< 10	< 0.02	7	-	DS-1 / AC-1
Kempton Park Gravel Member	0.03-0.06	13-227	< 0.02 - 0.02	7.7 - 8.5	-	DS-1 / AC-1
London Clay Formation	0.05 -0.06	108-150	0.28 - 0.65	6.8 - 8.9	0.84-1.95	DS-4 / AC-4
Groundwater	-	103-105	-	7.3	-	DS-1 / AC-1

## 7.8 Ground Gas Monitoring Results

**Table 7.9** Summary of Ground Gas Monitoring Results

Date	Location	CO <sub>2</sub> (%)		CH <sub>4</sub> (%)		O <sub>2</sub> (%)		Flow (Max. l/hr.)	Atmos. Pres. (mb)
		Min	Max	Min	Max	Min	Max		
11.07.2022	CP01	2.9	3.4	0.0	0.0	13.2	16.3	0.0	1022 (falling)
11.07.2022	WS02	1.3	2.2	0.0	0.0	18.9	19.6	0.0	1023 (falling)
11.07.2022	WS04	2.2	3.3	0.0	0.0	17.7	19.3	0.0	1023 (falling)
21.07.2022	CP01	5.0	5.1	0.0	0.0	13.2	14.2	0.0	1022 (falling)
21.07.2022	WS02	1.5	2.1	0.0	0.0	19.2	19.6	0.0	1021 (falling)
21.07.2022	WS04	0.1	3.6	0.0	0.0	17.9	20.6	0.0	1021 (falling)

**Table 7.10** Gas Screening Values for Carbon Dioxide and Methane

Peak Flow Rate (l/hr)	Worst Case CO <sub>2</sub> (%)	CO <sub>2</sub> GSV	Worst Case CH <sub>4</sub> (%)	CH <sub>4</sub> GSV	CIRIA 665 Characteristic Situation
<0.1	5.1	0.0051l/hr CO <sub>2</sub>	<0.1	0.0001l/hr CH <sub>4</sub>	GSV = CS-1 Max recorded values = CS-1*

**Table 7.11** Workplace Exposure Limits

Location	Recorded Concentration (ppm)					
	Carbon monoxide		Hydrogen sulphide		Liquefied Petroleum Gas (VOCs)	
	Min	Max	Min	Max	Min	Max
All Boreholes	1	4	1	4	<0.1	<0.1
HSE Workplace Exposure Limits (ppm)	Long Term	Short Term	Long Term	Short Term	Long Term	Short Term
	30	200	5	10	1000	1250
Locations with Elevated Concentrations	None elevated.		None elevated.		None elevated.	

## 8 Updated Risk Assessment

Discussion of analysis, screening and monitoring results, and an updated qualitative risk assessment are provided below.

### 8.1 Discussion of Results, Screening and Monitoring Results

The soil and groundwater screening and the results of the ground gas monitoring visits are summarised below in **Table 8.1**, **Table 8.2** and **Table 8.3**.

#### Soil

Elevated concentrations of lead and four congeners of polycyclic aromatic hydrocarbons (PAH), namely benzo[a]anthracene, benzo[b]fluoranthene, benzo[a]pyrene and dibenzo[ah]anthracene, have been identified within soils across four exploratory hole positions, which exceed the screening criteria for residential developments with homegrown produce. Additional comparison has been undertaken below against screening criteria for residential developments without homegrown produce end use. The results are presented below in **Table 8.1**.

**Table 8.1** Summary of soil screening value comparisons for samples with screening threshold exceedances.

Determinand	Samples with Exceedance and Location for Screening Values (1% SOM)	
	<i>Residential with homegrown produce</i>	<i>Residential without homegrown produce</i>
Lead	CP01 – 0.30m TP01 – 0.20m WS03 – 0.30m	CP01 – 0.30m TP01 – 0.20m WS03 – 0.30m
Benzo[a]anthracene	WS02 – 1.00m	WS02 – 1.00m
Benzo[b]fluoranthene	WS02 – 1.00m WS03 – 0.30m	WS02 – 1.00m WS03 – 0.30m
Benzo[a]pyrene	WS02 – 1.00m WS03 – 0.30m	WS02 – 1.00m WS03 – 0.30m
Dibenzo[ah]anthracene	TP01 – 0.20m WS02 – 1.00m WS03 – 0.30m	WS02 – 1.00m WS03 – 0.30m

Positions CP01 and WS02 are below the footprint of the proposed building on site; position TP01 is beneath proposed parking and WS03 beneath proposed soft landscaping on site. These results indicate that the Made Ground is not suitable for soft landscaped areas on site which may be accessed by residents. The sample from WS02 at 1.00m is from the natural soil underlying the Made Ground. It is noted that this has the potential to be reworked soil and that the PAH exceedances are in similar congeners to the shallow Made Ground soil from WS03.



Groundwater

**Table 8.2** Groundwater Screening Summary

Determinand	Samples with Exceedance
Cadmium	CP01 – 4.15m. Exceeding surface water criteria.
Nickel	
Zinc	

Elevated concentrations of cadmium, nickel and zinc have been identified in the first round of groundwater sampling underlying the site which exceed water quality standards for surface water. No source has been identified within shallow Made Ground soils on site.

The exceedances in relation to surface water quality standards concentrations are not considered to be significant given the industrial history of the surrounding area and the lack of exceedances during a subsequent round of monitoring and sampling. The closest surface water receptor is a lake in Bushy Park, located approximately 850m south of site. Given the distance to this receptor an unacceptable risk is not considered to be present..

Ground Gas

**Table 8.3** Summary of Ground Gas Monitoring

Item	Result
Characteristic Situation	CS-1 (CIRIA C665)
Workplace Exposure Limits	None elevated.

Ground gas monitoring was undertaken during two visits between 11<sup>th</sup> July and 21<sup>st</sup> July 2022. Based upon the gas screening values, Characteristic Situation 1 is considered appropriate for the site. The maximum recorded carbon dioxide gas concentration is slightly above the 5% threshold between CS-1 and CS-2. However, given that no positive flow rates have been encountered from any of the boreholes monitored on site and the very marginal exceedance of the 5% threshold, CS-1 is still considered appropriate.

Based on the information discussed above, Characteristic Situation (CS) 1 is identified as the appropriate ground gas regime for the site.

## 9 Waste Classification

Excavated soil from the construction works intended for disposal is required to be assessed for hazardous properties prior to disposal. The soil would be classified as either:

- Hazardous
- Non hazardous
- Inert

### 9.1 Soil Waste Classification

An assessment of the chemical data has been undertaken with respect to the Environment Agency's (EA) Technical Guidance Document WM3 (2021) '*Waste Classification- Guidance on the classification and assessment of waste*' (1<sup>st</sup> Ed. V1.2.GB) to determine whether arisings from the site, if intended for disposal to landfill, possess hazardous properties and therefore would require disposal to a hazardous landfill or an alternative facility that deals with designated Hazardous Waste. It is assumed the chemical data obtained is representative of conditions of the soils at the site.

A waste classification assessment was undertaken on 6no. soil samples using HazWasteOnline™ software. The Waste Classification Report is presented in **Appendix 4**. All six of the samples classify as non-hazardous.

Based on the soil testing results, waste soils to be removed from site should be classified as **Non-Hazardous**, categorised as 17 05 04 in the List of Waste from WM3.

### 9.2 Soil Waste Disposal

The Landfill Directive, introduced to the UK via the Landfill Regulations (England and Wales) 2002 aims to reduce reliance on landfill as a disposal option. The Regulations include updated waste assessment criteria (WAC) as limit values for waste destined to various classes of landfill.

WAC testing was undertaken on two soil samples, from WS02 (1.00m) and WS03 (0.30m). The sample from WS02 passed the Inert Waste WAC limits, but the sample from WS03 failed the Inert Waste WAC limit from antimony. Therefore, as per EA guidance '*Dispose of Waste to Landfill*' (published January 2020), excavated soils to be removed off-site meet the requirements for disposal at a landfill for non-hazardous waste. The WAC testing results are presented in **Appendix 4**.

The developer has a statutory responsibility under the Duty of Care Regulations of the Environmental Protection Act 1990 to ensure that contaminated soil and water is disposed of off-site to a suitably licensed waste management facility in a safe and approved manner.

To comply with the Duty of Care all wastes taken off site, in solid or liquid form, must be handled by a registered waste carrier and be accompanied by a consignment note that describes the waste.

## 10 Updated Conceptual Site Model and Qualitative Risk Assessment

The updated assessment of plausible contaminant linkages based on the results of the investigation and a summary of the potential geo-environmental risks associated with the site and in the context of the proposed development is provided in **Table 10.1**. The CSM risk evaluation methodology is presented in **Appendix 5**.

**Table 10.1** Updated Qualitative Risk Assessment

Source	Pathway	Receptor	Consequence	Probability	Potential Risk	Detail
<p><b>On site</b> Made Ground (from previous site development).  Potential asbestos containing materials (within on site buildings).  (Metals, TPHs, PAHs, AMCs, PCBs and ground gases/vapour.).</p>	Dermal contact, ingestion and inhalation of contaminated soil, dust and/or fibres	End users	Medium	Likely	Moderate	Contact is likely between future site users/visitors in shallow soils in the proposed soft landscaping areas of the site, soil/dust tracked back into premises, and potentially from ingestion of produce grown on site. Future site workers are likely to come into direct contact with soils during groundworks. Safe working practices should be implemented, and appropriate personal protective equipment (PPE) should be used to mitigate any potential risk.
		Site workers	Medium	Likely	Moderate	
		Adjacent users	Medium	Unlikely	Low	
	Leaching / infiltration through soils and migration via groundwater or soil pore moisture.	Controlled waters	Medium	Unlikely	Low	Groundwater screening indicates exceedances for heavy metals beneath the site in the first water sample tested. No on-site contamination source has been identified in the Made Ground, and subsequent monitoring did not identify chemical exceedances in groundwater. Given the distance to the nearest identified surface water feature and no abstraction licenses within 500m, an unacceptable risk is not considered to be present.
	Permeation of water pipes.	Construction materials, future end users	Medium	Low likelihood	Moderate / low	A moderate to low likelihood of potential hydrocarbon permeation of pipes is considered to site based upon the results of soil and groundwater screening. The results should be supplied to the water supply company to determine the appropriate pipework for use on site.
	Gas Migration and build up within buildings.	Future end users and building structures	Severe	Unlikely	Moderate / low	Based upon the results of ground gas monitoring, a moderate to low risk is considered to site from ground gasses. Characteristic Situation CS-1 has been considered appropriate for the site based on the ground gas monitoring results.
Plant Uptake	Flora and Fauna	Mild	Low likelihood	Low	Phytotoxic contamination as a consequence of historic and current land uses is unlikely.	

Source	Pathway	Receptor	Consequence	Probability	Potential Risk	Detail
<p><b>Off site</b> Railway sidings (1840 – present day)</p> <p><i>(Metals, TPHs, PAHs, PCBs and ground gases/vapour.).</i></p>	Dermal contact, ingestion and inhalation of contaminated soil, dust and/or fibres	End users	Medium	Low likelihood	Moderate / low	Contact is likely between future residential occupiers/visitors in shallow soils in the proposed garden area of the site, soil/dust tracked back into premises, and from ingestion of home grown produce. Future site workers are likely to come into direct contact with soils during groundworks. Safe working practices should be implemented, and appropriate personal protective equipment (PPE) should be used to mitigate any potential risk.
		Site workers	Medium	Low likelihood	Moderate / low	
	Leaching / infiltration through soils and migration via groundwater or soil pore moisture.	Controlled waters	Medium	Unlikely	Low	Groundwater screening indicates exceedances for heavy metals beneath the site in the first water sample tested. These may have come from an off-site source. No on-site contamination source has been identified in the Made Ground, and subsequent monitoring did not identify chemical exceedances in groundwater. Given the distance to the nearest identified surface water feature and no abstraction licenses within 500m, an unacceptable risk is not considered to be present.
	Permeation of water pipes.	Construction materials, future end users	Medium	Low likelihood	Moderate / low	A moderate to low likelihood of potential hydrocarbon permeation of pipes is considered to site based upon the results of soil and groundwater screening. The results should be supplied to the water supply company to determine the appropriate pipework for use on site.
	Gas Migration and build up within buildings.	Future end users and building structures	Severe	Unlikely	Moderate / low	Based upon the results of ground gas monitoring, a moderate to low risk is considered to site from ground gasses. Characteristic Situation CS-1 has been considered appropriate for the site based on the ground gas monitoring results.
	Plant Uptake	Flora and Fauna	Mild	Low likelihood	Low	Phytotoxic contamination as a consequence of historic and current land uses is unlikely.

## 11 Contamination Conclusion and Recommendations

The following recommendations are based on the results of the conceptual site model and risk assessment.

### 11.1 Conclusion

Based on the conceptual site model and risk assessment there is a considered moderate risk to end users, site workers and other environmental receptors.

Elevated concentrations of lead and four congeners of polycyclic aromatic hydrocarbons have been identified within soils up to 1.00mbgl in soils beneath proposed soft landscaping, parking and building footprints, which exceed the screening values for residential developments both with and without homegrown produce. Future site users and workers have the potential to come into contact with these soils.

Elevated concentrations of cadmium, nickel and zinc were identified in the first round of groundwater sampling which exceed water quality standards for surface water. No source has been identified within shallow Made Ground soils on site and the exceedances were not repeated during the second round of sampling.

The exceedances in relation to surface water quality standards concentrations are not considered to be significant given the industrial history of the surrounding area and the lack of exceedances during a subsequent round of monitoring and sampling. The closest surface water receptor is a lake in Bushy Park, located approximately 850m south of site, and given the distance to this receptor and unacceptable risk is not considered to be present

Based on the gas monitoring results and in line with classification, as detailed within C665 documentation, the CS level has been calculated as CS-1. Consequently, gas protection measures are not considered to be required to be installed within the proposed development.

### 11.2 Recommendations

#### 11.2.1 Delineation / Remediation

It is considered that a pathway break will be introduced between soils and human receptors in the proposed parking and building footprint areas.

It is recommended that delineation through further sampling and testing could be considered in the proposed soft landscaping area in the south. This may reduce the area requiring remediation.

In the absence of a delineation exercise remedial works will be required in the proposed soft landscaping area in the south of site to address the risks identified. If soils are removed in this part of the site, then this could remediate the area by removing the contamination source. The recommended minimum thickness for clean capping soils is 600mm.

Excavations within the root protection zones of trees on site should have consideration for the NHBC trees standards and root protection areas associated with the existing trees on site and adjacent to site. The Local Planning Authority Tree Officer should be contacted to discuss options.

A remedial strategy must be undertaken and submitted to the Local Planning Authority prior to any of the aforementioned works being undertaken. Any remediation undertaken would then require validation to show that the identified risks have been adequately addressed.

#### 11.2.2 Protection of Ground Workers

Suitable health and safety measures will be required for groundworkers. Appropriate precautions should be put in place following risk assessment. This should include, but not limited to, the adoption of suitable safe systems of work, provision of personal protective equipment, dust suppression, the provision and use of welfare facilities and suitable protective measures for the current site users.

#### 11.2.3 Watching Brief

It is recommended that a watching brief be maintained on site, particularly during the groundwork stage. During any ground works a competent person should make an appraisal of the exposed soils. If any material is noted to show visual and/or olfactory signs of contamination it should be stockpiled separately and tested prior to its appropriate removal off-site or re-use. If soils suspected of being contaminated are encountered, it is recommended that a contaminated land specialist be consulted.

#### 11.2.4 Buried Services

Potable water pipework shall comply with the Water Supply Regulations. The agreement of the water provider and Local Authority should be sought regarding the potable water pipework and fittings selected prior to commencement.

#### 11.2.5 Importing and Re-Use of Soil and Materials Management Plan

It is not anticipated that excavated materials will be re-used on site. A material would not be considered a waste if it is uncontaminated soil and other naturally occurring material excavated in the course of construction activities, where it is certain that the material will be used for the purposes of construction in its natural state on the site from which it was excavated.

Where the reuse of excavated material is intended, in accordance with the 'CL:AIRE Definition of Waste: Development Industry Code of Practice', a MMP should be prepared. The Environment Agency should be consulted at an early stage in this process, and this should be overseen by a 'competent person' as defined by LCRM.

#### 11.2.6 Soil Disposal

The client and contractors are advised to follow the process outlined in the Environment Agency's Technical Guidance Document WM3 '*Waste Classification – Guidance on the Classification and Assessment of Waste*', 1<sup>st</sup> edition 2021, v1.2 GB.

Based on the soil testing results, waste soils to be removed from site should be classified as **Non-Hazardous**, categorised as 17 05 04 in the List of Waste from WM3. WAC testing was undertaken for completeness and samples failed the Inert Waste WAC limits. Therefore, as per EA guidance '*Dispose of Waste to Landfill*' (published January 2020), excavated soils to be removed off-site meet the requirements for disposal at a landfill for non-hazardous waste.

The developer has a statutory responsibility under the Duty of Care Regulations of the Environmental Protection Act 1990 to ensure that contaminated soil and water is disposed of off-site to a suitably licensed waste management facility in a safe and approved manner.

To comply with the Duty of Care all wastes taken off site, in solid or liquid form, must be handled by a registered waste carrier and be accompanied by a consignment note that describes the waste.

#### 11.2.7 Statutory Authority Consultation

It is recommended that this report be sent to the statutory authorities including the Local Authority Environmental Health and Planning Departments prior to site works commencing to seek their comments. Where necessary, they will consult the Environment Agency or other relevant statutory authorities. If applicable to this project, this report should also be provided to the relevant building warranty provider.

## 12 Geotechnical Assessment

Comments regarding foundation design and construction are provided below.

### 12.1 Summary of Proposals and Ground Conditions

The development proposals and encountered ground conditions are summarised below.

#### 12.1.1 Development Proposals

Development proposals are understood to include the demolition of the existing 7-storey residential block and replacement with a 31-unit, 5-storey residential block with car parking provisions and a communal garden.

#### 12.1.2 Summary of Ground Conditions and Test Results

The encountered ground conditions and in-situ and geotechnical laboratory test results are summarised in **Table 12.1** to **Table 12.3**.

**Table 12.1** Summary of Encountered Ground Conditions

Stratum	Location	Surface Depth (mbgl)	Base Depth (mbgl)	Thickness (m)
Made Ground	All positions	0.00	0.30 to 0.60	0.30 to 0.60
Kempton Park Gravel Member	All positions	0.30-0.60	≥1.30* to 7.30	≥0.70 to 6.90
London Clay Formation	CP01	7.30	≥25.00*	≥17.60
Groundwater	Groundwater seepage was noted in CP01 at 2.2mbgl during the intrusive site investigation works. No groundwater was encountered in the dynamic sampling boreholes or trial pits.  During monitoring, groundwater was observed between 4.12mbgl and 4.19mbgl in borehole CP01; the dynamic sampling boreholes were dry.			

\*base of stratum not proven at all borehole locations

**Table 12.2** Summary of Test Results

Stratum	Corrected SPT 'N60' Value	Angle of Shearing Resistance	Moisture Content (%)	Plasticity Index (%)	c <sub>u</sub> (kPa)	
					SPT N60 x 4.2	Triaxial Test
Kempton Park Gravel Member	25 - 79	35 - 46	8 - 10	14 - 15	-	-
London Clay Formation	26 - 50	-	24 - 34	38 - 48	107 - 210	121 - 237


**Table 12.3** Summary of PSD Results

Stratum	Fines (%)	Sand (%)	Gravel (%)	Cobbles (%)
Kempton Park Gravel Member	2 – 3	36 – 63	35 – 61	0




The SPT N60 values have been calculated using an energy ratio of 73% from the cable percussive drilling rig and 79% from the dynamic sampling drilling rig. The corrected results are compared to depth in **Figure 12.1** below.

**Figure 12.1** SPT N60 Values vs Depth (mbgl)



The undrained shear strengths calculated from N60 values for the cohesive London Clay Formation soils and determined by laboratory and in-situ testing have been plotted against depth and are presented as **Figure 12.2**.

**Figure 12.2** Cu (kPa) vs Depth (mbgl)



## 12.2 Foundations

The following assessment is based on the ground conditions encountered and parameters determined from the intrusive site investigation, including the results of laboratory analysis. At the time of writing detailed design information and structural loads of the proposed buildings were not available, however it is assumed that the proposed structure will form a new multi storey residential block.

It is assumed that finished ground levels will be at or close to current ground levels, if this is not the case then this assessment will need to be reviewed.

Based on the geotechnical data obtained to date, the ground conditions encountered on site are considered appropriate for traditional trench fill/pad foundations bearing on the underlying natural coarse Kempton Park Gravel Member soils. The soils encountered on site have been interpreted to represent superficial deposits of the Kempton Park Gravel Member overlying bedrock of the London Clay Formation.

Testing undertaken on the coarse soils of the Kempton Park Gravel Member indicated soils of a medium dense to very dense relative density. Testing undertaken on the fine cohesive London Clay Formation soils encountered underlying the superficial coarse soils indicated stiff to very stiff clay with a medium to high volume change potential.

A number of trees are present on site. Thin bands of low volume change potential superficial gravelly clay soils have been encountered to depths of up to 1.70m bgl at locations TP03 and WS02. Whilst the medium to high shrinkable London Clay Formation cohesive clay soils have not been encountered until 7.30mbgl at location CP01, foundations constructed within the influencing distance of trees (whether on or off site and whether to remain, be removed or planted), should have the foundations locally deepened. Rare roots were only identified to some 2m depth, Localised clay units within the Kempton Park Gravel Member were only encountered within the shallowest 2m depth with granular deposits extending to some 7m depth. On this basis it is considered that minimum foundation depths based on appropriate industry guidance, such as NHBC Standards Chapter 4.2, may be excessively conservative and foundation depths may be limited to 2m to take such foundations below any shallow clay units and below observed rare root growth. Such foundations may still require heave protection.

Any made ground or reworked soils encountered within the proposed building footprint are considered unsuitable as a founding stratum and all foundations will need to fully penetrate any made ground, low strength or otherwise unsuitable soils and below any ground affected by grubbing out of the existing foundations and services and be founded a minimum of 150mm into the natural undisturbed founding stratum. It is recommended that shallow foundations are placed within the natural coarse soils and if any areas of superficial fine cohesive soils are encountered, such as at locations TP03 and WS02, these soils are fully penetrated.

A competent person should inspect foundation excavations to ensure they comply with design assumptions. Made Ground has been encountered to a maximum depth of 0.60mbgl at locations WS01, WS02 and WS03, but could be deeper in other areas of the site; grubbing out of existing foundations and services is likely to result in deeper disturbed ground.

Based on the site investigation data and testing available, for a 1.0m wide strip/trench fill foundation, bearing on the underlying natural coarse Kempton Park Gravel Member soils at a

depth of 1.0m, a design bearing resistance of 300kN/m<sup>2</sup> is considered appropriate. However it is recommended that foundations are taken to 2m due to presence of clay lenses and rare rootlets.

For a 1.0m wide strip/trench fill foundation bearing on the Kempton Park Gravel Member at 2.0m depth, a design bearing resistance of 350kN/m<sup>2</sup> should be available.

Alternatively for a 2.0m square pad foundation bearing on the underlying natural coarse Kempton Park Gravel Member soils at a depth of 1.0m, a design bearing resistance of 285kN/m<sup>2</sup> should be available. However it is recommended that foundations are taken to 2m due to presence of clay lenses and rare rootlets.

For a 2.0m square pad foundation bearing on the coarse Kempton Park Gravel Member soils at a depth of 2.0m, a design bearing resistance of 325kN/m<sup>2</sup> should be available.

The above is only applicable for foundations with loads that are applied vertically and centrally and should result in total settlements of not more than 25mm, keeping differential settlements within acceptable limits.

In the absence of design loads the bearing capacity assessment has been undertaken for Design Approach 1, Combination 2 only, and a further assessment taking account of anticipated loadings will be required during detailed design in order to confirm the limit states are satisfied.

If the design bearing capacities noted above are considered inadequate, then consideration should be given to the use of a piled foundation solution. The choice of piling system and detailed design of piles are beyond the scope of this report and should be undertaken by a specialist piling contractor.

### **12.3 Stability of Excavations and Dewatering Considerations**

The sides of excavations through Made Ground or granular soils would not be expected to remain stable and may require temporary support with appropriate shoring to prevent excavation collapse during construction.

Instability is more likely where excavations are left open for longer periods and during inclement weather and may require temporary support with appropriate shoring to prevent excavation collapse during construction.

Where support systems are required, this must be designed by a suitably qualified engineer. Precautionary measures should be adopted should excavations be expected to remain open for an extended period and must be installed if personnel are to enter.

Groundwater seepage was noted in CP01 at 2.2mbgl during fieldwork. It is considered that should groundwater be encountered at shallow excavation depths, it will likely be suitably controlled using sump pumps.

### **12.4 Floor Slabs**

Shallow ground conditions on site comprise approximately 600mm of made ground overlying natural coarse soils. Grubbing out of existing foundations and services may disturb the ground to a deeper and greater extent. At this stage consideration should be given to adopting a suspended floor slab. Whilst the natural coarse soils could be considered a suitable formation for ground bearing slabs following proof rolling any Made Ground/disturbed ground would

need to be removed and replaced with selected compacted granular materials. During preparation, the formation should be inspected and any soft or unsuitable materials should be removed and replaced with a suitable compacted granular fill.

### 12.5 Hardstanding

Following site preparation and regrading it is considered that the subgrade will comprise made ground or natural coarse soils.

The made ground on site is likely to be variable and for preliminary design purposes is considered to have a CBR of 2%. It is recommended that once the site has been graded to the appropriate pavement formation level, it is inspected and, if necessary, in situ CBR testing be conducted on the subgrade to confirm the appropriate pavement design (i.e. to determine the subbase and capping thickness). In addition, the formation should be proof-rolled and any soft/loose pockets encountered should be excavated and replaced with well-compacted granular fill prior to pavement construction. Additional guidance is provided in BS7533-10:2010.

Plate bearing tests on the hardstanding recorded an equivalent CBR value of >26%, with a result of 10% on the block paving and results between 1% and 4% on the shallow Made Ground at a depth of 0.20mbgl.

### 12.6 Chemical Attack on Buried Concrete

The results of testing for aggressive ground conditions have been summarised below in **Table 12.4**, the design sulphate class (DS) and aggressive chemical environment for concrete (ACEC) has also been provided.

**Table 12.4** Summary of Test Results

Stratum	Determinand					DS / ACEC Class
	Total sulphate (%)	W/S sulphate SO <sub>4</sub> (mg/l)	Total sulphur (%)	pH	Total Potential Sulphate	
Made Ground	0.03	< 10	< 0.02	7	-	DS-1 / AC-1
Kempton Park Gravel Member	0.03–0.06	13–227	< 0.02 – 0.02	7.7 - 8.5	-	DS-1 / AC-1
London Clay Formation	0.05 -0.06	108-150	0.28 – 0.65	6.8 – 8.9	0.84-1.95	DS-4 / AC-4
Groundwater	-	103-105	-	7.3	-	DS-1 / AC-1

The London Clay Formation has been designated a design sulphate class of DS-4/AC-4 based on the Total Potential Sulphate values calculated. However, it is recognised that given the depth of the London Clay on site oxidation is unlikely and concrete placed within this strata is therefore also unlikely to be exposed to ground that has been disturbed. A lower design sulphate class could therefore be considered if for example piled foundations were to be placed into the London Clay.

### 13 Limitations

The conclusions and recommendations made in this report are limited to those that can be made on the basis of the research carried out. The results of the research should be viewed in the context of the work that has been carried out and no liability can be accepted for matters outside the stated scope of the research. Any comments made on the basis of information obtained from third parties are given in good faith on the assumption that the information is accurate. No independent validation of third party information has been made by agb Environmental Ltd.

Should any changes to the development be proposed, including changes to the proposed landscaping, then the risks will need to be reassessed. This may require additional site investigation work and may result in the need for alteration of the remedial works.

Advice provided within this report is based on current guidelines available at the time of writing. This report is subject to amendment in light of additional information becoming available or statutory consultee review, including the Environment Agency and Local Authority and the NHBC.

It is possible the conditions observed during the site investigation may change. This may result in changes to sources, pathways or receptors that were unforeseen and unexpected. Statements relating to ground gas or groundwater conditions are based on observations made at the time of the site investigation (unless otherwise stated). Ground gas or groundwater conditions may vary as a result of seasonal fluctuations or other effects.



Ground contamination can exist as small discrete areas of contamination and there can be no certainty that any or all such areas have been sampled or identified. This is particularly significant for an investigation by exploratory holes (as used in this site investigation) as a relatively small sample of soil is extracted, which may not be entirely representative of the surrounding ground conditions.

The geotechnical advice given in this report seeks to provide foundation design guidelines for the proposed building(s). The recommendations/advice given is based on the available information obtained during the investigation. Should any unusual ground conditions be encountered that differ from those proved in the exploratory holes further advice should be sought from agb Environmental Ltd.

This report is written in the context of an agreed scope of work between agb Environmental Ltd and the Client and should only be used in this specific context. Re-interpretation of the Site Investigation and/or this report in whole or part may become necessary if additional information becomes available or practices or legislation changes. agb Environmental Ltd does not provide legal advice; the advice of the Client's legal advisors may also be required. agb Environmental Ltd Terms and Conditions apply.

# Appendix 1 Plans

---



Sheldon House  
Front Elevation



Sheldon House  
Rear Elevation




Sheldon House  
North-West Side Elevation



Sheldon House  
South-East Side Elevation



n.2/4/6 Cromwell Road  
Front Elevation





n.6 Cromwell Road  
Side Elevation



Grosvenor Court  
Front Elevation



<p>Magnolia Square 57 Rathbone Place Soho London W1T 1JU 020 7479 4855</p>	Client: Clive Chapman Architects	Job Title: Existing Information	<p>Notes:</p> <p>All works to be carried out in accordance with current building regulations.</p> <p>All dimensions / levels to be checked and verified on site before commencing any work and any discrepancies to be reported to the office immediately.</p> <p>This drawing to be read in conjunction with contract documents, project working drawings, specification, all consultants / specialists drawings, details and specification.</p>	Scale: 1:200@A1	Drawn: MZ
	Drawing Title: Elevations	Site Address: Sheldon House Cromwell Road, Teddington TW11 9EJ		Date: March 2021	Job No: 21100








**KEY**

	Manhole
	Drain
	Ground level
	Roof level
	Tree height



<p>Magnolia Square Limited 57 Rathbone Place Soho London W1T 1JU 020 7479 4855</p>	Client: Clive Chapman Architects	Job Title: Existing Information	<p>Notes: All works to be carried out in accordance with current building regulations. All dimensions / levels to be checked and verified on site before commencing any work and any discrepancies to be reported to the office immediately. This drawing to be read in conjunction with contract documents, project working drawings, specification, all consultants / specialists drawings, details and specification.</p>	Scale: 1:200@A1	Drawn: MZ
	Drawing Title: Site Plan	Site Address: Sheldon House Cromwell Road, Teddington TW11 9EJ		Date: March 2021	Job No: 21100
			Drawing No: 1	Rev:	




© CLIVE CHAPMAN ARCHITECTS. SURVEY INFORMATION IS USED UNDER SEPARATE COPYRIGHT LICENCE. REFER TO EXISTING SURVEY DRAWINGS / TITLE BLOCK FOR SURVEYORS DETAILS.

Revisions

Project SHELDON HOUSE, CROMWELL ROAD, TEDDINGTON TW11 9EJ		
Drawing LOCATION PLAN		
Drawing No. SH-SK00	Scale 1:500 @ A3	Date 14.01.21

**CLIVE CHAPMAN**  
ARCHITECTS  
SUSTAINABILITY CONSULTANTS  
4 EEL PIE ISLAND  
TWICKENHAM MIDDX  
TW1 3DY  
TELEPHONE 020 8891 4837  
EMAIL INFO@CCAR.CO.UK  
WEBSITE WWW.CCAR.CO.UK



NO FLANK WINDOWS TO NEIGHBOURING PROPERTY OR NEW BUILDING

TOWARDS STATION  
EL SUB STA

**ACCOMMODATION SCHEDULE:**

**NEW RESIDENTIAL BUILDING (5 STOREYS):**  
 18 x 1B/1P APARTMENTS @ 40M<sup>2</sup>  
 2 x 1B/2P APARTMENTS @ 50M<sup>2</sup>  
 2 x 2B/3P APARTMENTS @ 61M<sup>2</sup>  
 2 x 2B/4P APARTMENTS @ 70M<sup>2</sup>  
 4 x 3B/4P APARTMENTS @ 79M<sup>2</sup>

1 x 1B/2P WHEELCHAIR UNIT @ 54M<sup>2</sup>  
 2 x 2B/3P WHEELCHAIR UNIT @ 70M<sup>2</sup>

**TOTAL: 31 UNITS**


21 x 1B - 68%  
 6 x 2B - 19%  
 4 x 3B - 13%

**PARKING: 20 SPACES (65% PARKING / STATION 300M AWAY)**  
 SITE AREA: 1570M<sup>2</sup> OR 0.157 HECTARES  
 DENSITY: 197 DPH  
 NOTE: 10% M4(3) WHEELCHAIR UNITS (x3) LOCATED ON GROUND FLOOR DESIGNED TO TECHNICAL HOUSING STANDARDS (NDSS)


© CLIVE CHAPMAN ARCHITECTS. SURVEY INFORMATION IS USED UNDER SEPARATE COPYRIGHT LICENCE. REFER TO EXISTING SURVEY DRAWINGS / TITLE BLOCK FOR SURVEYORS DETAILS.




ROOF PLAN




FOURTH FLOOR PLAN




THIRD FLOOR PLAN



FIRST & SECOND FLOOR PLANS




GROUND FLOOR PLAN



Revisions

Project <b>1-9 SHELDON HOUSE, CROMWELL ROAD, TEDDINGTON TW11 9EJ</b>		<b>CLIVE CHAPMAN ARCHITECTS</b> SUSTAINABILITY CONSULTANTS 4 EEL PIE ISLAND TWICKENHAM MIDDX TW1 3DY TELEPHONE 020 8891 4837 EMAIL INFO@CCAR.CO.UK WEBSITE WWW.CCAR.CO.UK
Drawing <b>FEASIBILITY SITE LAYOUT &amp; FLOOR PLANS</b>		
Drawing No. <b>SH-SK06</b>	Scale <b>1:500 @ A3</b>	Date <b>03.03.21</b>



Revisions

Project  
1-9 SHELDON HOUSE, CROMWELL ROAD, TEDDINGTON TW11 9EJ

Drawing  
EXISTING VISUALS

Drawing No.  
SH-SK07

Scale  
NTS @ A3

Date  
03.03.21

**CLIVE CHAPMAN**  
**ARCHITECTS**  
SUSTAINABILITY CONSULTANTS  
4 EEL PIE ISLAND  
TWICKENHAM MIDDX  
TW1 3DY  
TELEPHONE 020 8891 4837  
EMAIL INFO@CCAR.CO.UK  
WEBSITE WWW.CCAR.CO.UK



Revisions

Project  
1-9 SHELDON HOUSE, CROMWELL ROAD, TEDDINGTON TW11 9EJ

Drawing  
FEASIBILITY VISUALS

Drawing No.  
SH-SK08


Scale  
NTS @ A3

Date  
03.03.21


**CLIVE CHAPMAN**  
**ARCHITECTS**  
SUSTAINABILITY CONSULTANTS  
4 EEL PIE ISLAND  
TWICKENHAM MIDDX  
TW1 3DY  
TELEPHONE 020 8891 4837  
EMAIL INFO@CCAR.CO.UK  
WEBSITE WWW.CCAR.CO.UK

## Appendix 2 Fieldwork Records






---



9.1M



Legend

-  WS borehole location
-  WS borehole location with monitoring well installation
-  CP borehole location with monitoring well installation
-  Trial Pit Locations
-  Plate Load Testing Locations

*Project*

Sheldon House, Cromwell Rd, Teddington, TW11 9EJ

*Title*

Exploratory Hole Location Plan

*Client*

RHP



**agb Environmental Ltd**

1, The Mill, Copley Hill Business Park,  
Babraham Road, Cambridge, CB22 3GN  
Tel: 01223 776117  
Email: [Info@agbenvironmental.co.uk](mailto:Info@agbenvironmental.co.uk)  
Web: [www.agbenvironmental.co.uk](http://www.agbenvironmental.co.uk)

*Date* 30<sup>th</sup> June 2022

*Scale* NTS

*Project number . Drawing number*

P4301.3.002

© copyright agb Environmental



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>CP01</b>	
Job No P4301	Date 30-06-22 05-07-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 5	

SAMPLES & TESTS			STRATA				Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)		
0.30	D ES					0.20	Concrete with 7mm diameter rebar at 0.10m.	
0.30						0.40	MADE GROUND: Brown gravelly SAND. Gravel is brick, concrete and chert gravel.	
0.50	D ES					(0.40)	Dark grey fine SAND. (KEMPTON PARK GRAVEL MEMBER)	
0.50						0.80		
1.00	D ES	N25				(0.80)	Medium dense brown fine SAND. (KEMPTON PARK GRAVEL MEMBER)	
1.20						1.60		
1.80	D ES B	N28				(2.10)	Medium dense to dense brown cobbly gravelly fine SAND. Cobbles and gravel are rounded chert. (KEMPTON PARK GRAVEL MEMBER)	
2.00						3.70		
3.00	ES	N38					Dense orange medium SAND with gravel and cobbles of subrounded to rounded chert. (KEMPTON PARK GRAVEL MEMBER)	
3.00								
4.00	B	N34					Dense orange medium SAND with gravel and cobbles of subrounded to rounded chert. (KEMPTON PARK GRAVEL MEMBER)	
4.00								
5.00	ES	N42					Dense orange medium SAND with gravel and cobbles of subrounded to rounded chert. (KEMPTON PARK GRAVEL MEMBER)	
5.00								

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater seepage at 2.2m. No significant roots. *No recovery in U sample at 9.5m.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Cable percussive rig	Logged By HG
--	--	---	-----------------





## BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				<b>BOREHOLE No</b>  <b>CP01</b>	
Job No P4301	Date 30-06-22 05-07-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 2 of 5	

SAMPLES & TESTS			STRATA				Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)		
6.50		N45				(3.60)	Dense orange medium SAND with gravel and cobbles of subrounded to rounded chert. (KEMPTON PARK GRAVEL MEMBER) <i>(continued)</i>	
7.00	B					7.30		
7.00	ES							
7.30	B						Firm to stiff grey CLAY. (LONDON CLAY FORMATION)	
8.00	D	N21				(2.20)		
8.00								
9.00	D					9.50	CLAYSTONE. (LONDON CLAY FORMATION)	
9.50	U*					(0.90)		
10.50	U					10.40	Stiff to very stiff grey CLAY with occasional patches of claystone.(LONDON CLAY FORMATION)	

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater seepage at 2.2m. No significant roots. *No recovery in U sample at 9.5m.
All dimensions in metres Scale 1:34.375			Client Richmond Housing Partnership			Method/ Plant Used Cable percussive rig			Logged By HG		



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>CP01</b>	
Job No P4301	Date 30-06-22 05-07-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 3 of 5	

SAMPLES & TESTS			STRATA				Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)		
11.00	D						Stiff to very stiff grey CLAY with occasional patches of claystone.(LONDON CLAY FORMATION) <i>(continued)</i>	
12.00 12.00	ES	N25						
13.00	D							
14.00	U							
14.50	D							
15.00 15.00	D ES							
15.50		N26						

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater seepage at 2.2m. No significant roots. *No recovery in U sample at 9.5m.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Cable percussive rig	Logged By HG
--	--	---	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>CP01</b>	
Job No P4301	Date 30-06-22 05-07-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 4 of 5	

SAMPLES & TESTS			STRATA				Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thick-ness)		
17.00	U					(14.60)	Stiff to very stiff grey CLAY with occasional patches of claystone.(LONDON CLAY FORMATION) <i>(continued)</i>	
18.00 18.00	D ES							
19.50		N31						
21.00 21.00 21.00	D ES U							

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater seepage at 2.2m. No significant roots. *No recovery in U sample at 9.5m.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Cable percussive rig	Logged By HG
--	--	---	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>CP01</b>	
Job No P4301	Date 30-06-22 05-07-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 5 of 5	

SAMPLES & TESTS			STRATA				Geology	Instrument/ Backfill	
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)			DESCRIPTION
22.50	D E S U	N35	Water				Stiff to very stiff grey CLAY with occasional patches of claystone.(LONDON CLAY FORMATION) <i>(continued)</i>		
24.00									
24.00									
25.00		N41				25.00			

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater seepage at 2.2m. No significant roots. *No recovery in U sample at 9.5m.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Cable percussive rig	Logged By HG
--	--	---	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>TP01</b>	
Job No P4301	Date 29-06-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 1	

SAMPLES & TESTS			STRATA					Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)	DESCRIPTION		
0.20 0.20	DS ES					(0.40) 0.40	MADE GROUND: brownish grey gravelly sandy SILT. Gravel is brick, chert and concrete. Occasional concrete cobbles.		
0.80 0.80	DS ES					(0.90) 1.30	Brown slightly silty SAND. Sand is fine. Rare subrounded to rounded chert gravel. Occasional pockets of silt. (KEMPTON PARK GRAVEL MEMBER)		
1.40 1.40	DS ES					1.50	Brown slightly silty gravelly SAND. Sand is fine. Gravel is subrounded chert. (KEMPTON PARK GRAVEL MEMBER)		
1.70	DS					(0.40) 1.90	Brown slightly silty SAND and GRAVEL. Sand is fine to medium. Gravel is medium to coarse subangular to subrounded chert. (KEMPTON PARK GRAVEL MEMBER)		
2.00 2.00	DS ES					(0.60) 2.50	Yellowish brown to brown slightly silty gravelly SAND. Sand is fine to medium. Gravel is subangular to subrounded chert. Silt is concentrated into lenses. (KEMPTON PARK GRAVEL MEMBER)		
2.60 2.60	DS ES					(0.50)	Brown very gravelly SAND. Gravel is subangular to rounded chert. Sand is fine to medium. Occasional chert cobbles. (KEMPTON PARK GRAVEL MEMBER)		
2.90 2.90	DS ES					3.00			

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater not encountered. Rare roots to 1.5m. Dry soil noted.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Excavator	Logged By HG
--	--	------------------------------------	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>TP02</b>	
Job No P4301	Date 29-06-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 1	

SAMPLES & TESTS			STRATA					Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)	DESCRIPTION		
0.20	DS					(0.30)	MADE GROUND: dark brown silty SAND.		
0.20	ES					0.30			
0.80	DS					(0.30)	Brown slightly silty SAND. Sand is fine. Occasional chert gravel. (KEMPTON PARK GRAVEL MEMBER)		
0.80	ES					0.60			
1.20	DS					(0.60)	Brown slightly gravelly slightly silty SAND. Gravel is subangular to rounded chert. (KEMPTON PARK GRAVEL MEMBER)		
1.20	ES					1.20			
2.00	DS					(0.60)	Brown gravelly SAND. Sand is fine. Gravel is subangular to subrounded chert. (KEMPTON PARK GRAVEL MEMBER)		
2.00	ES					1.80			
2.60	DS					(0.70)	Yellowish brown gravelly SAND. Sand is medium. Gravel is subangular to rounded chert. Occasional chert cobbles. (KEMPTON PARK GRAVEL MEMBER)		
2.60	ES					2.00			
2.90	DS					(0.70)	Yellowish brown slightly clayey gravelly SAND. Sand is medium to coarse. Gravel is subangular to rounded chert. (KEMPTON PARK GRAVEL MEMBER)		
2.90	ES					2.70			
						(0.40)	Yellowish brown clayey gravelly SAND. Sand is medium to coarse. Gravel is subangular to rounded chert. (KEMPTON PARK GRAVEL MEMBER)		
						3.10			

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater not encountered. Rare roots to 2.0m. Dry soil noted.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Excavator	Logged By HG
--	--	------------------------------------	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>TP03</b>	
Job No P4301	Date 29-06-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 1	

SAMPLES & TESTS			STRATA					Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)	DESCRIPTION		
0.20 0.20	DS ES					(0.30) 0.30	MADE GROUND: dark brown slightly gravelly sandy SILT. Occasional concrete cobbles. Sand is fine. Gravel is concrete and chert with occasional glass and brick.		
0.80 0.80	DS ES					(0.70) 1.00	Brown SAND with minor silt lenses. Sand is fine. (KEMPTON PARK GRAVEL MEMBER)		
1.30 1.30	DS ES					(0.40) 1.40	Very stiff yellowish brown sandy silty CLAY. Sand is fine. Rare gravel is medium to coarse subangular to subrounded chert. (KEMPTON PARK GRAVEL MEMBER)		
1.90 1.90	DS ES					(0.60) 2.00	Brown gravelly to very gravelly SAND. Sand is fine to medium. Gravel is medium to coarse chert. (KEMPTON PARK GRAVEL MEMBER)		
2.30 2.30	DS					(0.50) 2.50	Yellowish brown gravelly SAND. Sand is fine. Gravel is medium to coarse chert. (KEMPTON PARK GRAVEL MEMBER)		
2.60 2.60	DS ES					(0.50) 3.00	Brown very gravelly SAND. Sand is fine to medium. Gravel is medium to coarse chert. Occasional lenses of firm grey and brown mottled slightly sandy gravelly CLAY; sand is fine; gravel is chert. (KEMPTON PARK GRAVEL MEMBER)		

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater not encountered. Rare roots to 2.0m. Dry soil noted.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Excavator	Logged By HG
--	--	------------------------------------	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>WS01</b>	
Job No P4301	Date 28-06-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 1	

SAMPLES & TESTS			STRATA					Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)	DESCRIPTION		
0.30	DS1 ES1					0.10	Concrete with 7mm diameter rebar at 0.10m.		
0.30						0.20	Concrete with plastic sheet at 0.20m.		
0.50	DS2 ES2					0.35	MADE GROUND: brick and concrete rubble.		
0.50						0.50	MADE GROUND: dense dark grey gravelly SAND. Gravel is brick and chert with pockets of reworked brown sandy silt.		
1.00	DS3 ES3	N26				0.60	MADE GROUND: dense brown gravelly SAND. Gravel is brick, chert and rare clinker. Sand is fine.		
1.00						(0.60)	Brown silty SAND. Sand is fine. Rare chert gravel.(KEMPTON PARK GRAVEL MEMBER)		
1.20						(0.30)	Dense brown silty SAND. Sand is fine. Occasional chert gravel.(KEMPTON PARK GRAVEL MEMBER)		
1.20						1.50			
1.60	DS4 ES4	N53				(0.30)	Very dense yellowish brown very gravelly SAND. Sand is fine. Gravel is subrounded chert.		
1.60						1.80	(KEMPTON PARK GRAVEL MEMBER)		
1.80									

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater not encountered. Rare roots to 1.8m. Refusal at 1.8m.
All dimensions in metres Scale 1:34.375			Client Richmond Housing Partnership			Method/ Plant Used Dynamic sampling rig			Logged By HG		





### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>WS02</b>	
Job No P4301	Date 28-06-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 1	

SAMPLES & TESTS			STRATA					Geology	Instrument/ Backfill	
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)	DESCRIPTION			
0.20	DS1	N19				(0.30)	MADE GROUND: dark brown slightly gravelly slightly silty SAND. Sand is fine. Gravel is medium subangular to subrounded chert with occasional fine clinker and medium white porcelain. Rare chert cobbles.			
0.20	ES1					(0.30)	MADE GROUND: brownish grey slightly silty gravelly SAND. Sand is fine. Gravel is chert and concrete with occasional brick and clinker.			
0.50	DS2						0.60		Dark yellowish brown fine SAND. (KEMPTON PARK GRAVEL MEMBER)	
0.50	ES2						0.80		Yellowish brown slightly silty SAND. Sand is fine. (KEMPTON PARK GRAVEL MEMBER)	
1.00	DS3						(0.50)		Stiff orangish brown to yellowish brown slightly gravelly slightly sandy silty CLAY. Gravel is fine to coarse angular and subangular chert. Occasional subhorizontal dark brown staining. (KEMPTON PARK GRAVEL MEMBER)	
1.00	ES3						1.30		Brown gravelly slightly silty SAND. Sand is fine to medium. Gravel is chert. (KEMPTON PARK GRAVEL MEMBER)	
1.20							1.70		Very dense brown sandy GRAVEL. Gravel is chert, recovered fractured. Sand is fine to medium. (KEMPTON PARK GRAVEL MEMBER)	
1.40	DS4			N52					(0.40)	
1.40	ES4								1.90	
1.80	DS5						2.00			
1.80	ES5				2.00					
2.00										

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater not encountered. Rare roots to 1.9m. Refusal at 2.0m.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Dynamic sampling rig	Logged By HG
--	--	---	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>WS03</b>	
Job No P4301	Date 28-06-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 1	

SAMPLES & TESTS			STRATA				Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)		
0.30 0.30	DS1 ES1					(0.60) 0.60	MADE GROUND: dark brown slightly gravelly slightly sandy SILT. Gravel is glass fragments, glass bottles, porcelain fragments, metal wire and lumps, red brick and red chert. Occasional concrete cobbles.	
0.80 0.80	DS2 ES2					(0.60) 1.20	Medium dense yellowish brown sandy SILT. Sand is fine. (KEMPTON PARK GRAVEL MEMBER, POSSIBLY REWORKED)	
1.20 1.20 1.20 1.30	DS3 ES3	N33 N60				1.30	Very dense yellowish brown SAND and GRAVEL. Sand is fine. Gravel is chert, recovered fragmented. (KEMPTON PARK GRAVEL MEMBER)	

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater not encountered. No significant roots. Refusal at 1.3m.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Dynamic sampling rig	Logged By HG
--	--	---	-----------------



### BOREHOLE LOG

Project Sheldon House, Cromwell Road, Teddington, TW11 9EJ				BOREHOLE No <b>WS04</b>	
Job No P4301	Date 28-06-22	Ground Level (m)	Co-Ordinates ( )		
Contractor Agb Environmental Ltd				Sheet 1 of 1	

SAMPLES & TESTS			STRATA					Geology	Instrument/ Backfill
Depth	Type No	Test Result	Water	Reduced Level	Legend	Depth (Thickness)	DESCRIPTION		
0.25	DS1 ES1	N21				0.06	Concrete paving slab.		
0.25						0.20	Weak concrete.		
0.50						0.30	MADE GROUND: hardcore SAND and GRAVEL. Gravel is chert and Type 1 limestone.		
0.50	DS2 ES2	N21				(0.75)	Brown very silty SAND. Sand is fine. (KEMPTON PARK GRAVEL MEMBER)		
1.00	DS3 ES3					1.05	Medium dense off-white and cream slightly gravelly to gravelly SAND. Sand is fine. Gravel is chert, recovered fractured. (KEMPTON PARK GRAVEL MEMBER)		
1.20				DS4 ES4			(0.60)		
1.80	DS5 ES5	N55				1.90			
1.90									

AGS3 UK BH P4301 SHELDON HOUSE V2.GPJ AGB1.GDT 25/7/22

Boring Progress and Water Observations						Chiselling			Water Added		GENERAL REMARKS
Date	Time	Depth	Casing Depth	Casing Dia. mm	Water Dpt	From	To	Hours	From	To	
											Groundwater not encountered. No significant roots. Refusal at 1.9m.

All dimensions in metres Scale 1:34.375	Client Richmond Housing Partnership	Method/ Plant Used Dynamic sampling rig	Logged By HG
--	--	---	-----------------



**Certificate for the Determination of the Vertical Deformation and Strength Characteristics of Soil by the Incremental Plate Loading Test to BS 1377 Part 9: 1990**

Report No: 8152-1

Report Date: 29/06/2022

Client: AGB Environment Ltd  
 Address: Copley Hill Business Park  
 Babraham Road  
 Cambridge  
 CB22 3GN  
 Site: Sheldon House, Cromwell Rd, Teddington, TW11 9EJ

**Test Details**

Test Location: CBR 01  
 Description: Concrete  
 Material Class: Pile Mat  
 Layer: Ground Level  
 Condition: The results apply only to the location tested and the material was tested in an 'as found' condition



Date of Test: 29/06/2022  
 Reaction Load: 8 Tonne JCB  
 Weather: Wet  
 Plate Diameter (mm): 452

**Test Results**

Deviation: Settlement of  $\geq 1.25\text{mm}$  was not achieved so reported CBR is calculated at the maximum plate stress

Time, s	Settlement, mm	Plate Stress, kPa	Maximum Applied Stress (kPa):	189
0	0.00	22	Maximum Settlement (mm):	0.19
180	0.00	40	Equivalent CBR Value (%):	>26
360	0.00	77	Modulus of Subgrade Reaction, $k_{762}$ (MN/m <sup>2</sup> /m):	95
540	0.07	115		
720	0.12	152		
900	0.19	189		

Note: Supplemental test method, calculation of Nominal CBR Value and Modulus of Subgrade Reaction: IAN 73/06 revision 1 (2009), HD 25/94 (withdrawn)



For and on behalf of Hixtra Ltd

Kevin Shorthouse  
 Authorised signatory



Issued subject to Hixtra Terms and Conditions available at [www.hixtra.com](http://www.hixtra.com)

HU-SOI-01E Issue 3



**Certificate for the Determination of the Vertical Deformation and Strength Characteristics of Soil by the Incremental Plate Loading Test to BS 1377 Part 9: 1990**

Report No: 8152-2

Report Date: 29/06/2022

Client: AGB Environment Ltd  
 Address: Copley Hill Business Park  
 Babraham Road  
 Cambridge  
 CB22 3GN  
 Site: Sheldon House, Cromwell Rd, Teddington, TW11 9EJ

**Test Details**

Test Location: CBR 02  
 Description: Concrete  
 Material Class: Pile Mat  
 Layer: Ground Level  
 Condition: The results apply only to the location tested and the material was tested in an 'as found' condition



Date of Test: 29/06/2022  
 Reaction Load: 8 Tonne JCB  
 Weather: Wet  
 Plate Diameter (mm): 452

**Test Results**

Deviation: Settlement of  $\geq 1.25\text{mm}$  was not achieved so reported CBR is calculated at the maximum plate stress

Time, s	Settlement, mm	Plate Stress, kPa	Maximum Applied Stress (kPa):	189
0	0.00	22	Maximum Settlement (mm):	0.20
180	0.06	40	Equivalent CBR Value (%):	>26
360	0.12	77	Modulus of Subgrade Reaction, $k_{762}$ (MN/m <sup>2</sup> /m):	95
540	0.16	115		
720	0.17	152		
900	0.20	189		

Note: Supplemental test method, calculation of Nominal CBR Value and Modulus of Subgrade Reaction: IAN 73/06 revision 1 (2009), HD 25/94 (withdrawn)



For and on behalf of Hixtra Ltd

Kevin Shorthouse  
 Authorised signatory



Issued subject to Hixtra Terms and Conditions available at [www.hixtra.com](http://www.hixtra.com)

HU-SOI-01E Issue 3



**Certificate for the Determination of the Vertical Deformation and Strength Characteristics of Soil by the Incremental Plate Loading Test to BS 1377 Part 9: 1990**

Report No: 8152-3

Report Date: 29/06/2022

Client: AGB Environment Ltd  
 Address: Copley Hill Business Park  
 Babraham Road  
 Cambridge  
 CB22 3GN  
 Site: Sheldon House, Cromwell Rd, Teddington, TW11 9EJ

**Test Details**

Test Location: CBR 03  
 Description: Block Paving  
 Material Class: Pile Mat  
 Layer: Ground Level  
 Condition: The results apply only to the location tested and the material was tested in an 'as found' condition



Date of Test: 29/06/2022  
 Reaction Load: 8 Tonne JCB  
 Weather: Wet  
 Plate Diameter (mm): 452

**Test Results**

Time, s	Settlement, mm	Plate Stress, kPa
0	0.00	22
180	0.21	40
360	0.73	77
540	1.30	115
720	1.86	152
900	2.08	189

<b>Maximum Applied Stress (kPa):</b>	189
<b>Maximum Settlement (mm):</b>	2.08
<b>Equivalent CBR Value (%):</b>	10
<b>Modulus of Subgrade Reaction, <math>k_{762}</math> (MN/m<sup>2</sup>/m):</b>	56

Note: Supplemental test method, calculation of Nominal CBR Value and Modulus of Subgrade Reaction: IAN 73/06 revision 1 (2009), HD 25/94 (withdrawn)



For and on behalf of Hixtra Ltd

Kevin Shorthouse  
 Authorised signatory



Issued subject to Hixtra Terms and Conditions available at [www.hixtra.com](http://www.hixtra.com)

HU-SOI-01E Issue 3



**Certificate for the Determination of the Vertical Deformation and Strength Characteristics of Soil by the Incremental Plate Loading Test to BS 1377 Part 9: 1990**

Report No: 8152-4

Report Date: 29/06/2022

Client: AGB Environment Ltd  
 Address: Copley Hill Business Park  
 Babraham Road  
 Cambridge  
 CB22 3GN

Site: Sheldon House, Cromwell Rd, Teddington, TW11 9EJ

**Test Details**

Test Location: CBR 04  
 Description: Top Soil  
 Material Class: Pile Mat  
 Layer: 0.2m BGL

Date of Test: 29/06/2022  
 Reaction Load: 8 Tonne JCB  
 Weather: Wet  
 Plate Diameter (mm): 452



Condition: The results apply only to the location tested and the material was tested in an 'as found' condition

**Test Results**

Time, s	Settlement, mm	Plate Stress, kPa
0	0.00	12
180	0.78	40
360	1.40	77
540	1.90	115
720	2.36	152
900	2.82	189

<b>Maximum Applied Stress (kPa):</b>	189
<b>Maximum Settlement (mm):</b>	2.82
<b>Equivalent CBR Value (%):</b>	4
<b>Modulus of Subgrade Reaction, <math>k_{762}</math> (MN/m<sup>2</sup>/m):</b>	34

Note: Supplemental test method, calculation of Nominal CBR Value and Modulus of Subgrade Reaction: IAN 73/06 revision 1 (2009), HD 25/94 (withdrawn)



For and on behalf of Hixtra Ltd

Kevin Shorthouse  
 Authorised signatory



Issued subject to Hixtra Terms and Conditions available at [www.hixtra.com](http://www.hixtra.com)

HU-SOI-01E Issue 3



**Certificate for the Determination of the Vertical Deformation and Strength Characteristics of Soil by the Incremental Plate Loading Test to BS 1377 Part 9: 1990**

Report No: 8152-5  
 Client: AGB Environment Ltd  
 Address: Copley Hill Business Park  
 Babraham Road  
 Cambridge  
 CB22 3GN  
 Site: Sheldon House, Cromwell Rd, Teddington, TW11 9EJ

Report Date: 29/06/2022

**Test Details**

Test Location: CBR 05  
 Description: Top Soil  
 Material Class: Pile Mat  
 Layer: 0.2m BGL  
 Condition: The results apply only to the location tested and the material was tested in an 'as found' condition



Date of Test: 29/06/2022  
 Reaction Load: 8 Tonne JCB  
 Weather: Wet  
 Plate Diameter (mm): 452

**Test Results**

Time, s	Settlement, mm	Plate Stress, kPa
0	0.00	12
180	0.82	26
360	1.40	40
540	2.37	77
720	3.21	115
900	4.01	152
1080	4.57	189

<b>Maximum Applied Stress (kPa):</b>	189
<b>Maximum Settlement (mm):</b>	4.57
<b>Equivalent CBR Value (%):</b>	1
<b>Modulus of Subgrade Reaction, <math>k_{762}</math> (MN/m<sup>2</sup>/m):</b>	18

Note: Supplemental test method, calculation of Nominal CBR Value and Modulus of Subgrade Reaction: IAN 73/06 revision 1 (2009), HD 25/94 (withdrawn)



For and on behalf of Hixtra Ltd

Kevin Shorthouse  
 Authorised signatory



Issued subject to Hixtra Terms and Conditions available at [www.hixtra.com](http://www.hixtra.com)

HU-SOI-01E Issue 3





**Certificate for the Determination of the Vertical Deformation and Strength Characteristics of Soil by the Incremental Plate Loading Test to BS 1377 Part 9: 1990**

Report No: 8152-5

Report Date: 29/06/2022

Client: AGB Environment Ltd  
 Address: Copley Hill Business Park  
 Babraham Road  
 Cambridge  
 CB22 3GN  
 Site: Sheldon House, Cromwell Rd, Teddington, TW11 9EJ

**Test Details**

Test Location: CBR 06  
 Description: Concrete  
 Material Class: Pile Mat  
 Layer: 0.2m BGL  
 Condition: The results apply only to the location tested and the material was tested in an 'as found' condition



Date of Test: 29/06/2022  
 Reaction Load: 8 Tonne JCB  
 Weather: Wet  
 Plate Diameter (mm): 452

**Test Results**

Deviation: Settlement of  $\geq 1.25\text{mm}$  was not achieved so reported CBR is calculated at the maximum plate stress

Time, s	Settlement, mm	Plate Stress, kPa	Maximum Applied Stress (kPa):	189
0	0.00	12	Maximum Settlement (mm):	0.11
180	0.00	40	Equivalent CBR Value (%):	>26
360	0.01	77	Modulus of Subgrade Reaction, $k_{762}$ (MN/m <sup>2</sup> /m):	95
540	0.04	115		
720	0.08	152		
900	0.11	189		

Note: Supplemental test method, calculation of Nominal CBR Value and Modulus of Subgrade Reaction: IAN 73/06 revision 1 (2009), HD 25/94 (withdrawn)



For and on behalf of Hixtra Ltd

Kevin Shorthouse  
 Authorised signatory



Issued subject to Hixtra Terms and Conditions available at [www.hixtra.com](http://www.hixtra.com)

HU-SOI-01E Issue 3

# Appendix 3      Monitoring Results

---

# Monitoring Record

Site name / location:	Sheldon House, Cromwell Road, Teddington, TW11 9EJ
Installation ref.:	CP01
Date:	11/07/2022
Engineer:	HG

Weather / temp:	Air pressure high and falling. 28 C, sunny.
-----------------	---

## PID Monitoring

	Reading		Reading
	ppm		ppm
Ambient	0.0	+3m	0.0
+10s	0.0	+4m	-
+30s	0.0	+5m	-
+1m	0.0	+6m	-
+1m 30s	0.0	+7m	-
+2m	0.0	+8m	-
		<i>Max</i>	0.0

## Flow Rate

	Reading
	l/hr
+10s	0.0
+30s	0.0
+1m	0.0
+1m 30s	0.0
+2m	0.0
	<i>Max</i>
	0.0

## Gas Monitoring

	CO2	CH4	O2	CO	H2S	Pressure	Comments
	%	%	%	ppm	ppm	mb	
+10s	2.9	0.0	16.3	4	3	1022	
+30s	2.9	0.0	13.3	4	3	1022	
+1m	2.9	0.0	13.2	4	4	1022	
+1m 30s	3.0	0.0	13.2	4	3	1022	
+2m	3.0	0.0	13.2	4	4	1022	
+2m 30s	3.1	0.0	13.2	4	4	1022	
+3m	3.1	0.0	13.2	3	4	1022	
+3m 30s	3.2	0.0	13.2	3	4	1022	
+4m	3.3	0.0	13.3	3	4	1022	
+4m 30s	3.3	0.0	13.3	3	3	1022	
+5m	3.4	0.0	13.3	3	3	1022	
<i>Min</i>	2.9	0.0	13.2	3	3	-	
<i>Max</i>	3.4	0.0	16.3	4	4	-	

## Groundwater

Water Depth (m)	4.13
Well Depth (m)	10.13
Sample:	CP01, MON1, 4.15m
Comment:	-



agb Environmental Ltd

# Monitoring Record

Site name / location:	Sheldon House, Cromwell Road, Teddington, TW11 9EJ
Installation ref.:	WS02
Date:	11/07/2022
Engineer:	HG

Weather / temp: Air pressure high and falling. 27 C, sunny.

## PID Monitoring

	Reading		Reading
	ppm		ppm
Ambient	0.0	+3m	0.0
+10s	0.0	+4m	-
+30s	0.0	+5m	-
+1m	0.0	+6m	-
+1m 30s	0.0	+7m	-
+2m	0.0	+8m	-
		<i>Max</i>	0.0

## Flow Rate

	Reading
	l/hr
+10s	0.0
+30s	0.0
+1m	0.0
+1m 30s	0.0
+2m	0.0
	<i>Max</i> 0.0

## Gas Monitoring

	CO2	CH4	O2	CO	H2S	Pressure	Comments
	%	%	%	ppm	ppm	mb	
+10s	2.2	0.0	19.6	2	1	1023	
+30s	2.1	0.0	18.9	1	1	1023	
+1m	2.1	0.0	19.0	1	2	1023	
+1m 30s	1.9	0.0	19.1	1	1	1023	
+2m	1.8	0.0	19.2	1	2	1023	
+2m 30s	1.7	0.0	19.3	1	2	1023	
+3m	1.6	0.0	19.3	1	2	1023	
+3m 30s	1.5	0.0	19.4	1	2	1023	
+4m	1.4	0.0	19.5	1	2	1023	
+4m 30s	1.3	0.0	19.5	1	2	1023	
+5m	1.3	0.0	19.6	1	2	1023	
<i>Min</i>	1.3	0.0	18.9	1	1	-	
<i>Max</i>	2.2	0.0	19.6	2	2	-	

## Groundwater

Water Depth (m)	Dry
Well Depth (m)	1.96
Sample:	-
Comment:	-



agb Environmental Ltd

# Monitoring Record

Site name / location:	Sheldon House, Cromwell Road, Teddington, TW11 9EJ
Installation ref.:	WS04
Date:	11/07/2022
Engineer:	HG

Weather / temp:	Air pressure high and falling. 27 C, sunny.
-----------------	---

## PID Monitoring

	Reading		Reading
	ppm		ppm
Ambient	0.0	+3m	0.0
+10s	0.0	+4m	-
+30s	0.0	+5m	-
+1m	0.0	+6m	-
+1m 30s	0.0	+7m	-
+2m	0.0	+8m	-
		<i>Max</i>	0.0

## Flow Rate

	Reading
	l/hr
+10s	0.0
+30s	0.0
+1m	0.0
+1m 30s	0.0
+2m	0.0
	<i>Max</i>
	0.0

## Gas Monitoring

	CO2	CH4	O2	CO	H2S	Pressure	Comments
	%	%	%	ppm	ppm	mb	
+10s	3.3	0.0	19.3	1	2	1023	
+30s	3.3	0.0	17.7	1	2	1023	
+1m	3.2	0.0	17.7	1	2	1023	
+1m 30s	3.2	0.0	17.8	1	2	1023	
+2m	3.0	0.0	17.8	1	2	1023	
+2m 30s	2.8	0.0	18.0	1	1	1023	
+3m	2.7	0.0	18.1	1	2	1023	
+3m 30s	2.5	0.0	18.2	1	2	1023	
+4m	2.4	0.0	18.3	1	2	1023	
+4m 30s	2.2	0.0	18.4	1	2	1023	
+5m	2.2	0.0	18.4	1	2	1023	
<i>Min</i>	2.2	0.0	17.7	1	1	-	
<i>Max</i>	3.3	0.0	19.3	1	2	-	

## Groundwater

Water Depth (m)	Dry
Well Depth (m)	1.98
Sample:	-
Comment:	-



agb Environmental Ltd

# Monitoring Record

Site name / location:	Sheldon House, Cromwell Road, Teddington, TW11 9EJ
Installation ref.:	CP01
Date:	21/07/2022
Engineer:	NM

Weather / temp:	Air pressure high and falling
-----------------	-------------------------------

## PID Monitoring

	Reading		Reading
	ppm		ppm
Ambient	0.0	+3m	0.0
+10s	0.0	+4m	-
+30s	0.0	+5m	-
+1m	0.0	+6m	-
+1m 30s	0.0	+7m	-
+2m	0.0	+8m	-
		<i>Max</i>	0.0

## Flow Rate

	Reading
	l/hr
+10s	0.0
+30s	0.0
+1m	0.0
+1m 30s	0.0
+2m	0.0
	<i>Max</i>
	0.0

## Gas Monitoring

	CO2	CH4	O2	CO	H2S	Pressure	Comments
	%	%	%	ppm	ppm	mb	
+10s	5.0	0.0	14.2	2	3	1022	
+30s	5.1	0.0	13.3	2	3	1022	
+1m	5.1	0.0	13.2	2	3	1022	
+1m 30s	5.1	0.0	13.2	2	3	1022	
+2m	5.1	0.0	13.2	2	3	1022	
+2m 30s	5.1	0.0	13.2	2	3	1022	
+3m	5.1	0.0	13.2	2	3	1022	
+3m 30s	5.1	0.0	13.2	2	3	1022	
+4m	5.1	0.0	13.2	2	3	1022	
+4m 30s	5.1	0.0	13.2	2	3	1022	
+5m	5.1	0.0	13.2	2	3	1022	
<i>Min</i>	5.0	0.0	13.2	2	3	-	
<i>Max</i>	5.1	0.0	14.2	2	3	-	

## Groundwater

Water Depth (m)	4.19m
Well Depth (m)	10.12m
Sample:	CP01, MON2, 4.20m
Comment:	-



agb Environmental Ltd

# Monitoring Record

Site name / location:	Sheldon House, Cromwell Road, Teddington, TW11 9EJ
Installation ref.:	WS02
Date:	21/07/2022
Engineer:	NM

Weather / temp:	Air pressure high and falling
-----------------	-------------------------------

## PID Monitoring

	Reading		Reading
	ppm		ppm
Ambient	0.0	+3m	0.0
+10s	0.0	+4m	-
+30s	0.0	+5m	-
+1m	0.0	+6m	-
+1m 30s	0.0	+7m	-
+2m	0.0	+8m	-
		<i>Max</i>	0.0

## Flow Rate

	Reading
	l/hr
+10s	0.0
+30s	0.0
+1m	0.0
+1m 30s	0.0
+2m	0.0
	<i>Max</i>
	0.0

## Gas Monitoring

	CO2	CH4	O2	CO	H2S	Pressure	Comments
	%	%	%	ppm	ppm	mb	
+10s	2.1	0.0	19.3	1	2	1021	
+30s	2.1	0.0	19.3	1	2	1021	
+1m	2.1	0.0	19.2	1	2	1021	
+1m 30s	2.1	0.0	19.2	1	2	1021	
+2m	2.1	0.0	19.3	1	2	1021	
+2m 30s	2.1	0.0	19.3	1	2	1021	
+3m	1.8	0.0	19.3	1	2	1021	
+3m 30s	1.8	0.0	19.3	1	2	1021	
+4m	1.8	0.0	19.4	1	2	1021	
+4m 30s	1.6	0.0	19.4	1	2	1021	
+5m	1.5	0.0	19.6	1	2	1021	
<i>Min</i>	1.5	0.0	19.2	1	2	-	
<i>Max</i>	2.1	0.0	19.6	1	2	-	

## Groundwater

Water Depth (m)	Dry
Well Depth (m)	1.96
Sample:	-
Comment:	-



agb Environmental Ltd

# Monitoring Record

Site name / location:	Sheldon House, Cromwell Road, Teddington, TW11 9EJ
Installation ref.:	WS04
Date:	21/07/2022
Engineer:	NM

Weather / temp:	Air pressure high and falling
-----------------	-------------------------------

## PID Monitoring

	Reading		Reading
	ppm		ppm
Ambient	0.0	+3m	0.0
+10s	0.0	+4m	-
+30s	0.0	+5m	-
+1m	0.0	+6m	-
+1m 30s	0.0	+7m	-
+2m	0.0	+8m	-
		<i>Max</i>	0.0

## Flow Rate

	Reading
	l/hr
+10s	0.0
+30s	0.0
+1m	0.0
+1m 30s	0.0
+2m	0.0
	<i>Max</i>
	0.0

## Gas Monitoring

	CO2	CH4	O2	CO	H2S	Pressure	Comments
	%	%	%	ppm	ppm	mb	
+10s	0.1	0.0	20.6	3	2	1021	
+30s	2.9	0.0	18.7	1	2	1021	
+1m	3.6	0.0	17.9	1	2	1021	
+1m 30s	3.6	0.0	17.9	1	2	1021	
+2m	3.6	0.0	17.9	1	2	1021	
+2m 30s	3.5	0.0	18.0	1	2	1021	
+3m	3.3	0.0	18.0	1	2	1021	
+3m 30s	3.3	0.0	18.0	1	2	1021	
+4m	3.0	0.0	18.3	1	2	1021	
+4m 30s	3.0	0.0	18.6	1	2	1021	
+5m	2.7	0.0	18.6	1	2	1021	
<i>Min</i>	0.1	0.0	17.9	1	2	-	
<i>Max</i>	3.6	0.0	20.6	3	2	-	

## Groundwater

Water Depth (m)	Dry
Well Depth (m)	1.98
Sample:	-
Comment:	-



agb Environmental Ltd



# Appendix 4      Laboratory Results

---



Helen Gildersleeves  
AGB Environmental Ltd  
1 The Mill  
Copley Hill Business Park  
Abraham Road  
Cambridge  
CB22 3GN

**Derwentside Environmental Testing Services Ltd**  
Unit 1  
Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Kent  
ME17 2JN  
t: 01622 850410

## **DETS Report No: 22-05652**

**Site Reference:** P4301.3 - Sheldon House, Teddington  
**Project / Job Ref:** P4301.3  
**Order No:** 9232  
**Sample Receipt Date:** 01/07/2022  
**Sample Scheduled Date:** 01/07/2022  
**Report Issue Number:** 1  
**Reporting Date:** 07/07/2022

**Authorised by:**

Dave Ashworth  
Technical Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

For Topsoil and WAC analysis the expanded uncertainty measurement should be considered while evaluating results against compliance values.



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Soil Analysis Certificate</b>						
<b>DETS Report No: 22-05652</b>	<b>Date Sampled</b>	28/06/22	28/06/22	28/06/22	28/06/22	28/06/22
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied	None Supplied	None Supplied
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	<b>TP / BH No</b>	WS01	WS02	WS02	WS03	WS03
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	ES1	ES3	ES3 + DS3	ES1	ES1 + DS1
<b>Order No: 9232</b>	<b>Depth (m)</b>	0.30	1.00	1.00	0.30	0.30
<b>Reporting Date: 07/07/2022</b>	<b>DETS Sample No</b>	603240	603241	603242	603243	603244

Determinand	Unit	RL	Accreditation				
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025	Not Detected	Not Detected		Not Detected
pH	pH Units	N/a	MCERTS	8.4	7.9		6.7
Total Sulphate as SO <sub>4</sub>	mg/kg	< 200	MCERTS				
Total Sulphate as SO <sub>4</sub>	%	< 0.02	MCERTS				
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS				
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS				
Total Sulphur	%	< 0.02	NONE				
Organic Matter (SOM)	%	< 0.1	MCERTS	6.2	2.5		6.1
Arsenic (As)	mg/kg	< 2	MCERTS	13	12		26
Cadmium (Cd)	mg/kg	< 0.2	MCERTS	< 0.2	0.3		0.5
Chromium (Cr)	mg/kg	< 2	MCERTS	14	13		14
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2	< 2		< 2
Copper (Cu)	mg/kg	< 4	MCERTS	18	23		63
Lead (Pb)	mg/kg	< 3	MCERTS	77	137		635
Mercury (Hg)	mg/kg	< 1	MCERTS	< 1	< 1		< 1
Nickel (Ni)	mg/kg	< 3	MCERTS	14	11		16
Selenium (Se)	mg/kg	< 2	MCERTS	< 3	< 3		< 3
Zinc (Zn)	mg/kg	< 3	MCERTS	40	70		589

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Method Description page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Soil Analysis Certificate</b>						
<b>DETS Report No: 22-05652</b>	<b>Date Sampled</b>	28/06/22	28/06/22	28/06/22	28/06/22	28/06/22
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied	None Supplied	None Supplied
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	<b>TP / BH No</b>	WS04	TP01	WS02	WS04	WS01
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	ES2	ES1	ES1	ES4	ES3
<b>Order No: 9232</b>	<b>Depth (m)</b>	0.50	0.20	0.20	1.20	1.00
<b>Reporting Date: 07/07/2022</b>	<b>DETS Sample No</b>	603245	603246	603247	603248	603249

Determinand	Unit	RL	Accreditation					
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025	Not Detected	Not Detected			
pH	pH Units	N/a	MCERTS	7.6	8.0	7.0	8.5	7.8
Total Sulphate as SO <sub>4</sub>	mg/kg	< 200	MCERTS			302	450	633
Total Sulphate as SO <sub>4</sub>	%	< 0.02	MCERTS			0.03	0.05	0.06
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS			< 10	13	227
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS			< 0.01	0.01	0.23
Total Sulphur	%	< 0.02	NONE			< 0.02	< 0.02	0.02
Organic Matter (SOM)	%	< 0.1	MCERTS	1.2	2			
Arsenic (As)	mg/kg	< 2	MCERTS	9	11			
Cadmium (Cd)	mg/kg	< 0.2	MCERTS	< 0.2	0.2			
Chromium (Cr)	mg/kg	< 2	MCERTS	15	16			
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2	< 2			
Copper (Cu)	mg/kg	< 4	MCERTS	7	25			
Lead (Pb)	mg/kg	< 3	MCERTS	16	214			
Mercury (Hg)	mg/kg	< 1	MCERTS	< 1	< 1			
Nickel (Ni)	mg/kg	< 3	MCERTS	11	12			
Selenium (Se)	mg/kg	< 2	MCERTS	< 3	< 3			
Zinc (Zn)	mg/kg	< 3	MCERTS	40	106			

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Method Description page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Soil Analysis Certificate - Speciated PAHs</b>						
<b>DETS Report No: 22-05652</b>	<b>Date Sampled</b>	28/06/22	28/06/22	28/06/22	28/06/22	28/06/22
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied	None Supplied	None Supplied
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	<b>TP / BH No</b>	WS01	WS02	WS03	WS04	TP01
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	ES1	ES3	ES1	ES2	ES1
<b>Order No: 9232</b>	<b>Depth (m)</b>	0.30	1.00	0.30	0.50	0.20
<b>Reporting Date: 07/07/2022</b>	<b>DETS Sample No</b>	603240	603241	603243	603245	603246

Determinand	Unit	RL	Accreditation					
Naphthalene	mg/kg	< 0.1	MCERTS	< 0.1	0.12	< 0.1	< 0.1	< 0.1
Acenaphthylene	mg/kg	< 0.1	MCERTS	< 0.1	1.15	0.20	< 0.1	0.11
Acenaphthene	mg/kg	< 0.1	MCERTS	< 0.1	0.35	< 0.1	< 0.1	< 0.1
Fluorene	mg/kg	< 0.1	MCERTS	< 0.1	1.65	0.12	< 0.1	< 0.1
Phenanthrene	mg/kg	< 0.1	MCERTS	< 0.1	18	2.39	< 0.1	1.25
Anthracene	mg/kg	< 0.1	MCERTS	< 0.1	4.44	0.48	< 0.1	0.26
Fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	28.70	6.38	< 0.1	3.23
Pyrene	mg/kg	< 0.1	MCERTS	< 0.1	25.10	6.04	< 0.1	2.86
Benzo(a)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	13.30	3.63	< 0.1	1.67
Chrysene	mg/kg	< 0.1	MCERTS	< 0.1	11	2.37	< 0.1	1.37
Benzo(b)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	11.50	3.28	< 0.1	1.70
Benzo(k)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1	4.24	1.10	< 0.1	0.52
Benzo(a)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	12.60	3.30	< 0.1	1.60
Indeno(1,2,3-cd)pyrene	mg/kg	< 0.1	MCERTS	< 0.1	7.38	2	< 0.1	1.04
Dibenz(a,h)anthracene	mg/kg	< 0.1	MCERTS	< 0.1	2.07	0.44	< 0.1	0.28
Benzo(ghi)perylene	mg/kg	< 0.1	MCERTS	< 0.1	6.37	1.71	< 0.1	0.93
Total EPA-16 PAHs	mg/kg	< 1.6	MCERTS	< 1.6	148	33.4	< 1.6	16.8



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



**Soil Analysis Certificate - TPH CWG Banded**

<b>DETS Report No: 22-05652</b>	<b>Date Sampled</b>	28/06/22	28/06/22	28/06/22	28/06/22	28/06/22
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied	None Supplied	None Supplied
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	<b>TP / BH No</b>	WS01	WS02	WS03	WS04	TP01
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	ES1	ES3	ES1	ES2	ES1
<b>Order No: 9232</b>	<b>Depth (m)</b>	0.30	1.00	0.30	0.50	0.20
<b>Reporting Date: 07/07/2022</b>	<b>DETS Sample No</b>	603240	603241	603243	603245	603246

Determinand	Unit	RL	Accreditation					
Aliphatic >C5 - C6 : HS 1D MS AL	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01
Aliphatic >C6 - C8 : HS 1D MS AL	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05
Aliphatic >C8 - C10 : EH 1D FID AL	mg/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
Aliphatic >C10 - C12 : EH 1D FID AL	mg/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
Aliphatic >C12 - C16 : EH 1D FID AL	mg/kg	< 3	MCERTS	< 3	< 3	< 3	< 3	< 3
Aliphatic >C16 - C21 : EH 1D FID AL	mg/kg	< 3	MCERTS	< 3	< 3	< 3	< 3	< 3
Aliphatic >C21 - C34 : EH 1D FID AL	mg/kg	< 10	MCERTS	< 10	< 10	< 10	< 10	< 10
Aliphatic (C5 - C34) : EH 1D FID MS HS AL	mg/kg	< 21	NONE	< 21	< 21	< 21	< 21	< 21
Aromatic >C5 - C7 : HS 1D MS AR	mg/kg	< 0.01	NONE	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01
Aromatic >C7 - C8 : HS 1D MS AR	mg/kg	< 0.05	NONE	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05
Aromatic >C8 - C10 : EH 1D FID AR	mg/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
Aromatic >C10 - C12 : EH 1D FID AR	mg/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
Aromatic >C12 - C16 : EH 1D FID AR	mg/kg	< 2	MCERTS	< 2	5	< 2	< 2	< 2
Aromatic >C16 - C21 : EH 1D FID AR	mg/kg	< 3	MCERTS	< 3	52	10	< 3	5
Aromatic >C21 - C35 : EH 1D FID AR	mg/kg	< 10	MCERTS	< 10	114	32	< 10	17
Aromatic (C5 - C35) : EH 1D FID MS HS AR	mg/kg	< 21	NONE	< 21	171	42	< 21	22
Total >C5 - C35 : EH_1D_FID_MS_HS_Total	mg/kg	< 42	NONE	< 42	171	42	< 42	< 42



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - BTEX / MTBE						
DETS Report No: 22-05652	Date Sampled	28/06/22	28/06/22	28/06/22	28/06/22	28/06/22
AGB Environmental Ltd	Time Sampled	None Supplied	None Supplied	None Supplied	None Supplied	None Supplied
Site Reference: P4301.3 - Sheldon House, Teddington	TP / BH No	WS01	WS02	WS03	WS04	TP01
Project / Job Ref: P4301.3	Additional Refs	ES1	ES3	ES1	ES2	ES1
Order No: 9232	Depth (m)	0.30	1.00	0.30	0.50	0.20
Reporting Date: 07/07/2022	DETS Sample No	603240	603241	603243	603245	603246

Determinand	Unit	RL	Accreditation					
Benzene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
Toluene : HS_1D_MS	ug/kg	< 5	MCERTS	< 5	< 5	< 5	< 5	< 5
Ethylbenzene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
p & m-xylene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
o-xylene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2	< 2	< 2	< 2	< 2
MTBE : HS_1D_MS	ug/kg	< 5	MCERTS	< 5	< 5	< 5	< 5	< 5



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**

Soil Analysis Certificate - PCB (12 Congeners)						
DETS Report No: 22-05652	Date Sampled	28/06/22				
AGB Environmental Ltd	Time Sampled	None Supplied				
Site Reference: P4301.3 - Sheldon House, Teddington	TP / BH No	WS03				
Project / Job Ref: P4301.3	Additional Refs	ES1				
Order No: 9232	Depth (m)	0.30				
Reporting Date: 07/07/2022	DETS Sample No	603243				

Determinand	Unit	RL	Accreditation				
PCB Congener 77	mg/kg	0.008	NONE	< 0.008			
PCB Congener 81	mg/kg	0.008	NONE	< 0.008			
PCB Congener 105	mg/kg	0.008	NONE	< 0.008			
PCB Congener 114	mg/kg	0.008	NONE	< 0.008			
PCB Congener 118	mg/kg	0.008	NONE	< 0.008			
PCB Congener 123	mg/kg	0.008	NONE	< 0.008			
PCB Congener 126	mg/kg	0.008	NONE	< 0.008			
PCB Congener 156	mg/kg	0.008	NONE	< 0.008			
PCB Congener 157	mg/kg	0.008	NONE	< 0.008			
PCB Congener 167	mg/kg	0.008	NONE	< 0.008			
PCB Congener 169	mg/kg	0.008	NONE	< 0.008			
PCB Congener 189	mg/kg	0.008	NONE	< 0.008			
Total PCB (12 Congeners)	mg/kg	< 0.1	NONE	< 0.1			

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C



Waste Acceptance Criteria Analytical Certificate - BS EN 12457/3																																		
<b>DETS Report No: 22-05652</b>		<b>Date Sampled</b>	28/06/22		<b>Landfill Waste Acceptance Criteria Limits</b>  <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 33%;">Inert Waste Landfill</th> <th style="width: 33%;">Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill</th> <th style="width: 33%;">Hazardous Waste Landfill</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">3%</td> <td style="text-align: center;">5%</td> <td style="text-align: center;">6%</td> </tr> <tr> <td style="text-align: center;">--</td> <td style="text-align: center;">--</td> <td style="text-align: center;">10%</td> </tr> <tr> <td style="text-align: center;">6</td> <td style="text-align: center;">--</td> <td style="text-align: center;">--</td> </tr> <tr> <td style="text-align: center;">1</td> <td style="text-align: center;">--</td> <td style="text-align: center;">--</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center;">--</td> <td style="text-align: center;">--</td> </tr> <tr> <td style="text-align: center;">100</td> <td style="text-align: center;">--</td> <td style="text-align: center;">--</td> </tr> <tr> <td style="text-align: center;">--</td> <td style="text-align: center;">&gt;6</td> <td style="text-align: center;">--</td> </tr> <tr> <td style="text-align: center;">--</td> <td style="text-align: center; color: red;">To be evaluated</td> <td style="text-align: center; color: red;">To be evaluated</td> </tr> </tbody> </table>			Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill	3%	5%	6%	--	--	10%	6	--	--	1	--	--	500	--	--	100	--	--	--	>6	--	--	To be evaluated	To be evaluated
Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill																																
3%	5%	6%																																
--	--	10%																																
6	--	--																																
1	--	--																																
500	--	--																																
100	--	--																																
--	>6	--																																
--	To be evaluated	To be evaluated																																
<b>AGB Environmental Ltd</b>		<b>Time Sampled</b>	None Supplied																															
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>		<b>TP / BH No</b>	WS02																															
<b>Project / Job Ref: P4301.3</b>		<b>Additional Refs</b>	ES3 + DS3																															
<b>Order No: 9232</b>		<b>Depth (m)</b>	1.00																															
<b>Reporting Date: 07/07/2022</b>		<b>DETS Sample No</b>	603242																															
<b>Determinand</b>	<b>Unit</b>	<b>MDL</b>																																
TOC <sup>MU</sup>	%	< 0.1	0.6																															
Loss on Ignition	%	< 0.01	1.50																															
BTEX <sup>MU</sup>	mg/kg	< 0.05	< 0.05																															
Sum of PCBs	mg/kg	< 0.1	< 0.1																															
Mineral Oil <sup>MU</sup>	mg/kg	< 10	< 10																															
Total PAH <sup>MU</sup>	mg/kg	< 1.7	4.4																															
pH <sup>MU</sup>	pH Units	N/a	8.0																															
Acid Neutralisation Capacity	mol/kg (+/-)	< 1	< 1																															
<b>Eluate Analysis</b>			<b>2:1 mg/l</b>	<b>8:1 mg/l</b>	<b>Cumulative 10:1 mg/kg</b>	<b>Limit values for compliance leaching test using BS EN 12457-3 at L/S 10 l/kg (mg/kg)</b>																												
Arsenic <sup>U</sup>		< 0.01	< 0.01		< 0.2	0.5	2	25																										
Barium <sup>U</sup>		< 0.02	< 0.02		0.1	20	100	300																										
Cadmium <sup>U</sup>		< 0.0005	< 0.0005		< 0.02	0.04	1	5																										
Chromium <sup>U</sup>		< 0.005	< 0.005		< 0.20	0.5	10	70																										
Copper <sup>U</sup>		< 0.01	< 0.01		< 0.5	2	50	100																										
Mercury <sup>U</sup>		< 0.0005	< 0.0005		< 0.005	0.01	0.2	2																										
Molybdenum <sup>U</sup>		0.007	0.003		< 0.1	0.5	10	30																										
Nickel <sup>U</sup>		< 0.007	< 0.007		< 0.2	0.4	10	40																										
Lead <sup>U</sup>		< 0.005	< 0.005		< 0.2	0.5	10	50																										
Antimony <sup>U</sup>		< 0.005	< 0.005		< 0.05	0.06	0.7	5																										
Selenium <sup>U</sup>		< 0.005	< 0.005		< 0.05	0.1	0.5	7																										
Zinc <sup>U</sup>		< 0.005	0.007		< 0.2	4	50	200																										
Chloride <sup>U</sup>		21	5		63	800	15000	25000																										
Fluoride <sup>U</sup>		< 0.5	< 0.5		< 1	10	150	500																										
Sulphate <sup>U</sup>		13	6		60	1000	20000	50000																										
TDS		106	47		511	4000	60000	100000																										
Phenol Index		< 0.01	< 0.01		< 0.5	1	-	-																										
DOC		25.1	8.9		101	500	800	1000																										
<b>Leach Test Information</b>																																		
Sample Mass (kg)		0.18																																
Dry Matter (%)		95.7																																
Moisture (%)		4.6																																
<b>Stage 1</b>																																		
Volume Eluate L2 (litres)		0.34																																
Filtered Eluate VE1 (litres)		0.12																																
Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion Stated limits are for guidance only and DETS Ltd cannot be held responsible for any discrepancies with current legislation M Denotes MCERTS accredited test U Denotes ISO17025 accredited test																																		

Waste Acceptance Criteria Analytical Certificate - BS EN 12457/3																																			
DETS Report No: 22-05652		Date Sampled	28/06/22		Landfill Waste Acceptance Criteria Limits			<table border="1"> <thead> <tr> <th>Inert Waste Landfill</th> <th>Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill</th> <th>Hazardous Waste Landfill</th> </tr> </thead> <tbody> <tr> <td>3%</td> <td>5%</td> <td>6%</td> </tr> <tr> <td>--</td> <td>--</td> <td>10%</td> </tr> <tr> <td>6</td> <td>--</td> <td>--</td> </tr> <tr> <td>1</td> <td>--</td> <td>--</td> </tr> <tr> <td>500</td> <td>--</td> <td>--</td> </tr> <tr> <td>100</td> <td>--</td> <td>--</td> </tr> <tr> <td>--</td> <td>&gt;6</td> <td>--</td> </tr> <tr> <td>--</td> <td>To be evaluated</td> <td>To be evaluated</td> </tr> </tbody> </table>	Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill	3%	5%	6%	--	--	10%	6	--	--	1	--	--	500	--	--	100	--	--	--	>6	--	--	To be evaluated	To be evaluated
Inert Waste Landfill	Stable Non-reactive HAZARDOUS waste in non-hazardous Landfill	Hazardous Waste Landfill																																	
3%	5%	6%																																	
--	--	10%																																	
6	--	--																																	
1	--	--																																	
500	--	--																																	
100	--	--																																	
--	>6	--																																	
--	To be evaluated	To be evaluated																																	
AGB Environmental Ltd		Time Sampled	None Supplied																																
Site Reference: P4301.3 - Sheldon House, Teddington		TP / BH No	WS03																																
Project / Job Ref: P4301.3		Additional Refs	ES1 + DS1																																
Order No: 9232		Depth (m)	0.30																																
Reporting Date: 07/07/2022		DETS Sample No	603244																																
Determinand	Unit	MDL																																	
TOC <sup>MU</sup>	%	< 0.1	5.8																																
Loss on Ignition	%	< 0.01	8.88																																
BTEX <sup>MU</sup>	mg/kg	< 0.05	< 0.05																																
Sum of PCBs	mg/kg	< 0.1	< 0.1																																
Mineral Oil <sup>MU</sup>	mg/kg	< 10	< 10																																
Total PAH <sup>MU</sup>	mg/kg	< 1.7	20.6																																
pH <sup>MU</sup>	pH Units	N/a	6.7																																
Acid Neutralisation Capacity	mol/kg (+/-)	< 1	< 1																																
Eluate Analysis			2:1 mg/l	8:1 mg/l	Cumulative 10:1 mg/kg	Limit values for compliance leaching test using BS EN 12457-3 at L/S 10 l/kg (mg/kg)																													
Arsenic <sup>U</sup>		< 0.01	< 0.01		< 0.2	0.5	2	25																											
Barium <sup>U</sup>		0.04	0.04		0.4	20	100	300																											
Cadmium <sup>U</sup>		< 0.0005	< 0.0005		< 0.02	0.04	1	5																											
Chromium <sup>U</sup>		< 0.005	< 0.005		< 0.20	0.5	10	70																											
Copper <sup>U</sup>		0.01	< 0.01		< 0.5	2	50	100																											
Mercury <sup>U</sup>		< 0.0005	< 0.0005		< 0.005	0.01	0.2	2																											
Molybdenum <sup>U</sup>		0.004	0.003		< 0.1	0.5	10	30																											
Nickel <sup>U</sup>		< 0.007	< 0.007		< 0.2	0.4	10	40																											
Lead <sup>U</sup>		0.030	0.034		0.3	0.5	10	50																											
Antimony <sup>U</sup>		0.014	0.006		0.06	0.06	0.7	5																											
Selenium <sup>U</sup>		< 0.005	< 0.005		< 0.05	0.1	0.5	7																											
Zinc <sup>U</sup>		0.024	0.049		0.5	4	50	200																											
Chloride <sup>U</sup>		4	3		35	800	15000	25000																											
Fluoride <sup>U</sup>		< 0.5	< 0.5		< 1	10	150	500																											
Sulphate <sup>U</sup>		7	5		56	1000	20000	50000																											
TDS		56	52		524	4000	60000	100000																											
Phenol Index		< 0.01	< 0.01		< 0.5	1	-	-																											
DOC		20.6	16.2		166	500	800	1000																											
Leach Test Information																																			
Sample Mass (kg)			0.19																																
Dry Matter (%)			93.6																																
Moisture (%)			6.8																																
Stage 1																																			
Volume Eluate L2 (litres)			0.34																																
Filtered Eluate VE1 (litres)			0.16																																

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Samples Descriptions page describes if the test is performed on the dried or as-received portion  
Stated limits are for guidance only and DETS Ltd cannot be held responsible for any discrepancies with current legislation  
M Denotes MCERTS accredited test  
U Denotes ISO17025 accredited test



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions	
DETS Report No: 22-05652	
AGB Environmental Ltd	
Site Reference: P4301.3 - Sheldon House, Teddington	
Project / Job Ref: P4301.3	
Order No: 9232	
Reporting Date: 07/07/2022	

DETS Sample No	TP / BH No	Additional Refs	Depth (m)	Moisture Content (%)	Sample Matrix Description
603240	WS01	ES1	0.30	4.6	Brown sandy clay with stones and concrete
603241	WS02	ES3	1.00	5.5	Brown gravelly sand with stones and concrete
603242	WS02	ES3 + DS3	1.00	4.3	Light brown sandy clay with stones
603243	WS03	ES1	0.30	6.4	Light brown sandy clay
603244	WS03	ES1 + DS1	0.30	6.3	Light brown sandy clay
603245	WS04	ES2	0.50	4.9	Black sandy clay with stones and glass
603246	TP01	ES1	0.20	4.9	Black sandy clay with stones and vegetation
603247	WS02	ES1	0.20	5.4	Light brown sandy clay
603248	WS04	ES4	1.20	6.8	Brown sandy clay with stones
603249	WS01	ES3	1.00	4.6	Brown sandy clay with stones

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample <sup>U/S</sup>

Unsuitable Sample <sup>U/S</sup>

<b>Soil Analysis Certificate - Methodology &amp; Miscellaneous Information</b>	
<b>DETS Report No: 22-05652</b>	
<b>AGB Environmental Ltd</b>	
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	
<b>Project / Job Ref: P4301.3</b>	
<b>Order No: 9232</b>	
<b>Reporting Date: 07/07/2022</b>	

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphenylcarbazide followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 – C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	Fraction Organic Carbon (FOC)	Determination of TOC by combustion analyser.	E027
Soil	D	Organic Matter (SOM)	Determination of TOC by combustion analyser.	E027
Soil	D	TOC (Total Organic Carbon)	Determination of TOC by combustion analyser.	E027
Soil	AR	Exchangeable Ammonium	Determination of ammonium by discrete analyser.	E029
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCs	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

**D Dried**  
**AR As Received**



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Water Analysis Certificate - Methodology &amp; Miscellaneous Information</b>
DETS Report No: 22-05652
AGB Environmental Ltd
Site Reference: P4301.3 - Sheldon House, Teddington
Project / Job Ref: P4301.3
Order No: 9232
Reporting Date: 07/07/2022

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Water	UF	Alkalinity	Determination of alkalinity by titration against hydrochloric acid using bromocresol green as the end point	E103
Water	F	Ammoniacal Nitrogen	Determination of ammoniacal nitrogen by discrete analyser.	E126
Water	UF	BTEX	Determination of BTEX by headspace GC-MS	E101
Water	F	Cations	Determination of cations by filtration followed by ICP-MS	E102
Water	UF	Chemical Oxygen Demand (COD)	Determination using a COD reactor followed by colorimetry	E112
Water	F	Chloride	Determination of chloride by filtration & analysed by ion chromatography	E109
Water	F	Chromium - Hexavalent	Determination of hexavalent chromium by acidification, addition of 1,5 diphenylcarbazide followed by	E116
Water	UF	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E115
Water	UF	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E115
Water	UF	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E115
Water	UF	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through liquid:liquid extraction with cyclohexane	E111
Water	F	Diesel Range Organics (C10 - C24)	Determination of liquid:liquid extraction with hexane followed by GC-FID	E104
Water	F	Dissolved Organic Content (DOC)	Determination of DOC by filtration followed by low heat with persulphate addition followed by IR dete	E110
Water	UF	Electrical Conductivity	Determination of electrical conductivity by electrometric measurement	E123
Water	F	EPH (C10 - C40)	Determination of liquid:liquid extraction with hexane followed by GC-FID	E104
Water	F	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of liquid:liquid extraction with hexane followed by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E104
Water	F	Fluoride	Determination of Fluoride by filtration & analysed by ion chromatography	E109
Water	F	Hardness	Determination of Ca and Mg by ICP-MS followed by calculation	E102
Leachate	F	Leachate Preparation - NRA	Based on National Rivers Authority leaching test 1994	E301
Leachate	F	Leachate Preparation - WAC	Based on BS EN 12457 Pt1, 2, 3	E302
Water	F	Metals	Determination of metals by filtration followed by ICP-MS	E102
Water	F	Mineral Oil (C10 - C40)	Determination of liquid:liquid extraction with hexane followed by GI-FID	E104
Water	F	Nitrate	Determination of nitrate by filtration & analysed by ion chromatography	E109
Water	UF	Monohydric Phenol	Determination of phenols by distillation followed by colorimetry	E121
Water	F	PAH - Speciated (EPA 16)	Determination of PAH compounds by concentration through SPE cartridge, collection in dichloromethane followed by GC-MS	E105
Water	F	PCB - 7 Congeners	Determination of PCB compounds by concentration through SPE cartridge, collection in dichlorometha	E108
Water	UF	Petroleum Ether Extract (PEE)	Gravimetrically determined through liquid:liquid extraction with petroleum ether	E111
Water	UF	pH	Determination of pH by electrometric measurement	E107
Water	F	Phosphate	Determination of phosphate by filtration & analysed by ion chromatography	E109
Water	UF	Redox Potential	Determination of redox potential by electrometric measurement	E113
Water	F	Sulphate (as SO4)	Determination of sulphate by filtration & analysed by ion chromatography	E109
Water	UF	Sulphide	Determination of sulphide by distillation followed by colorimetry	E118
Water	F	SVOC	Determination of semi-volatile organic compounds by concentration through SPE cartridge, collection in dichloromethane followed by GC-MS	E106
Water	UF	Toluene Extractable Matter (TEM)	Gravimetrically determined through liquid:liquid extraction with toluene	E111
Water	UF	Total Organic Carbon (TOC)	Low heat with persulphate addition followed by IR detection	E110
Water	F	TPH CWG (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of liquid:liquid extraction with hexane, fractionating with SPE followed by GC-FID for C8 to C35. C5 to C8 by headspace GC-MS	E104
Water	F	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of liquid:liquid extraction with hexane, fractionating with SPE followed by GC-FID for C8 to C44. C5 to C8 by headspace GC-MS	E104
Water	UF	VOCs	Determination of volatile organic compounds by headspace GC-MS	E101
Water	UF	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E101

Key

**F Filtered**  
**UF Unfiltered**

Parameter	Matrix Type	Suite Reference	Expanded Uncertainty Measurement	Unit
TOC	Soil	BS EN 12457	20.0	%
Loss on Ignition	Soil	BS EN 12457	35.0	%
BTEX	Soil	BS EN 12457	14.0	%
Sum of PCBs	Soil	BS EN 12457	23.0	%
Mineral Oil	Soil	BS EN 12457	9.0	%
Total PAH	Soil	BS EN 12457	11.6	%
pH	Soil	BS EN 12457	0.28	Units
Acid Neutralisation Capacity	Soil	BS EN 12457	18.0	%
Arsenic	Leachate	BS EN 12457	18.7	%
Barium	Leachate	BS EN 12457	11.6	%
Cadmium	Leachate	BS EN 12457	20.3	%
Chromium	Leachate	BS EN 12457	18.3	%
Copper	Leachate	BS EN 12457	24.3	%
Mercury	Leachate	BS EN 12457	23.7	%
Molybdenum	Leachate	BS EN 12457	14.7	%
Nickel	Leachate	BS EN 12457	16.1	%
Lead	Leachate	BS EN 12457	15.7	%
Antimony	Leachate	BS EN 12457	17.9	%
Selenium	Leachate	BS EN 12457	22.0	%
Zinc	Leachate	BS EN 12457	17.4	%
Chloride	Leachate	BS EN 12457	15.3	%
Fluoride	Leachate	BS EN 12457	16.4	%
Sulphate	Leachate	BS EN 12457	20.6	%
TDS	Leachate	BS EN 12457	12.0	%
Phenol Index	Leachate	BS EN 12457	14.0	%
DOC	Leachate	BS EN 12457	10.0	%
Clay Content	Soil	BS 3882: 2015	15.0	%
Silt Content	Soil	BS 3882: 2015	14.0	%
Sand Content	Soil	BS 3882: 2015	13.0	%
Loss on Ignition	Soil	BS 3882: 2015	35.0	%
pH	Soil	BS 3882: 2015	0.14	Units
Carbonate	Soil	BS 3882: 2015	16.0	%
Total Nitrogen	Soil	BS 3882: 2015	12.0	%
Phosphorus (Extractable)	Soil	BS 3882: 2015	24.0	%
Potassium (Extractable)	Soil	BS 3882: 2015	20.0	%
Magnesium (Extractable)	Soil	BS 3882: 2015	26.0	%
Zinc	Soil	BS 3882: 2015	14.9	%
Copper	Soil	BS 3882: 2015	16.0	%
Nickel	Soil	BS 3882: 2015	17.7	%
Available Sodium	Soil	BS 3882: 2015	23.0	%
Available Calcium	Soil	BS 3882: 2015	23.0	%
Electrical Conductivity	Soil	BS 3882: 2015	10.0	%

## List of HWOL Acronyms and Operators

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
_	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total

### Det - Acronym

Benzene - HS\_1D\_MS  
 Ethylbenzene - HS\_1D\_MS  
 MTBE - HS\_1D\_MS  
 Mineral Oil (C10 - C40) (BS EN 12457-3) - EH\_1D\_FID  
 TPH CWG - Aliphatic >C10 - C12 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C12 - C16 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C16 - C21 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C21 - C34 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C5 - C6 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C6 - C8 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C8 - C10 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic C5 - C34 - EH\_1D\_FID\_MS\_HS\_AL  
 TPH CWG - Aromatic >C10 - C12 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C12 - C16 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C16 - C21 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C21 - C35 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C5 - C35 - EH\_1D\_FID\_MS\_HS\_AR  
 TPH CWG - Aromatic >C5 - C7 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C7 - C8 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C8 - C10 - EH\_1D\_FID\_AR  
 TPH CWG - Total >C5 - C35 - EH\_1D\_FID\_MS\_HS\_Total  
 Toluene - HS\_1D\_MS  
 Total BTEX (BS EN 12457-3) - HS\_1D\_MS\_Total  
 m & p-xylene - HS\_1D\_MS  
 o-Xylene - HS\_1D\_MS



Helen Gildersleeves  
AGB Environmental Ltd  
1 The Mill  
Copley Hill Business Park  
Abraham Road  
Cambridge  
CB22 3GN

**Derwentside Environmental Testing Services Ltd**  
Unit 1  
Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Kent  
ME17 2JN  
t: 01622 850410

## **DETS Report No: 22-05766**

**Site Reference:** P4301.3 - Sheldon House, Teddington

**Project / Job Ref:** P4301.3

**Order No:** 009248

**Sample Receipt Date:** 06/07/2022

**Sample Scheduled Date:** 06/07/2022

**Report Issue Number:** 1

**Reporting Date:** 11/07/2022

**Authorised by:**

Dave Ashworth  
Technical Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.





**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Soil Analysis Certificate</b>						
<b>DETS Report No: 22-05766</b>	<b>Date Sampled</b>	30/06/22	30/06/22	01/07/22	04/07/22	04/07/22
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied	None Supplied	None Supplied
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	<b>TP / BH No</b>	CP01	CP01	CP01	CP01	CP01
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	ES1	ES3	ES	ES	ES
<b>Order No: 009248</b>	<b>Depth (m)</b>	0.30	1.20	7.00	12.00	15.00
<b>Reporting Date: 11/07/2022</b>	<b>DETS Sample No</b>	603668	603669	603670	603671	603672

Determinand	Unit	RL	Accreditation				
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025	Not Detected			
pH	pH Units	N/a	MCERTS	9.7	7.7	8.3	8.2
Total Sulphate as SO <sub>4</sub>	mg/kg	< 200	MCERTS		297	< 200	554
Total Sulphate as SO <sub>4</sub>	%	< 0.02	MCERTS		0.03	< 0.02	0.06
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS		53	< 10	148
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS		0.05	< 0.01	0.15
Total Sulphur	%	< 0.02	NONE		< 0.02	< 0.02	0.33
Organic Matter (SOM)	%	< 0.1	MCERTS	3.4			
Arsenic (As)	mg/kg	< 2	MCERTS	11			
Cadmium (Cd)	mg/kg	< 0.2	MCERTS	< 0.2			
Chromium (Cr)	mg/kg	< 2	MCERTS	19			
Chromium (hexavalent)	mg/kg	< 2	NONE	< 2			
Copper (Cu)	mg/kg	< 4	MCERTS	36			
Lead (Pb)	mg/kg	< 3	MCERTS	241			
Mercury (Hg)	mg/kg	< 1	MCERTS	< 1			
Nickel (Ni)	mg/kg	< 3	MCERTS	13			
Selenium (Se)	mg/kg	< 2	MCERTS	< 3			
Zinc (Zn)	mg/kg	< 3	MCERTS	121			

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Method Description page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



<b>Soil Analysis Certificate</b>						
<b>DETS Report No: 22-05766</b>	<b>Date Sampled</b>	04/07/22	04/07/22	04/07/22		
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied	None Supplied	None Supplied		
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	<b>TP / BH No</b>	CP01	CP01	CP01		
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	ES	ES	ES		
<b>Order No: 009248</b>	<b>Depth (m)</b>	18.00	21.00	24.00		
<b>Reporting Date: 11/07/2022</b>	<b>DETS Sample No</b>	603673	603674	603675		

Determinand	Unit	RL	Accreditation				
Asbestos Screen <sup>(S)</sup>	N/a	N/a	ISO17025				
pH	pH Units	N/a	MCERTS	8.9	8.7	6.8	
Total Sulphate as SO <sub>4</sub>	mg/kg	< 200	MCERTS	545	570	555	
Total Sulphate as SO <sub>4</sub>	%	< 0.02	MCERTS	0.05	0.06	0.06	
W/S Sulphate as SO <sub>4</sub> (2:1)	mg/l	< 10	MCERTS	108	150	141	
W/S Sulphate as SO <sub>4</sub> (2:1)	g/l	< 0.01	MCERTS	0.11	0.15	0.14	
Total Sulphur	%	< 0.02	NONE	0.28	0.43	0.39	
Organic Matter (SOM)	%	< 0.1	MCERTS				
Arsenic (As)	mg/kg	< 2	MCERTS				
Cadmium (Cd)	mg/kg	< 0.2	MCERTS				
Chromium (Cr)	mg/kg	< 2	MCERTS				
Chromium (hexavalent)	mg/kg	< 2	NONE				
Copper (Cu)	mg/kg	< 4	MCERTS				
Lead (Pb)	mg/kg	< 3	MCERTS				
Mercury (Hg)	mg/kg	< 1	MCERTS				
Nickel (Ni)	mg/kg	< 3	MCERTS				
Selenium (Se)	mg/kg	< 2	MCERTS				
Zinc (Zn)	mg/kg	< 3	MCERTS				

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C. The Method Description page describes if the test is performed on the dried or as-received portion  
 Subcontracted analysis (S)



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - Speciated PAHs						
DETS Report No: 22-05766	Date Sampled	30/06/22				
AGB Environmental Ltd	Time Sampled	None Supplied				
Site Reference: P4301.3 - Sheldon House, Teddington	TP / BH No	CP01				
Project / Job Ref: P4301.3	Additional Refs	ES1				
Order No: 009248	Depth (m)	0.30				
Reporting Date: 11/07/2022	DETS Sample No	603668				

Determinand	Unit	RL	Accreditation				
Naphthalene	mg/kg	< 0.1	MCERTS	< 0.1			
Acenaphthylene	mg/kg	< 0.1	MCERTS	< 0.1			
Acenaphthene	mg/kg	< 0.1	MCERTS	< 0.1			
Fluorene	mg/kg	< 0.1	MCERTS	< 0.1			
Phenanthrene	mg/kg	< 0.1	MCERTS	< 0.1			
Anthracene	mg/kg	< 0.1	MCERTS	< 0.1			
Fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1			
Pyrene	mg/kg	< 0.1	MCERTS	< 0.1			
Benzo(a)anthracene	mg/kg	< 0.1	MCERTS	< 0.1			
Chrysene	mg/kg	< 0.1	MCERTS	< 0.1			
Benzo(b)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1			
Benzo(k)fluoranthene	mg/kg	< 0.1	MCERTS	< 0.1			
Benzo(a)pyrene	mg/kg	< 0.1	MCERTS	< 0.1			
Indeno(1,2,3-cd)pyrene	mg/kg	< 0.1	MCERTS	< 0.1			
Dibenz(a,h)anthracene	mg/kg	< 0.1	MCERTS	< 0.1			
Benzo(ghi)perylene	mg/kg	< 0.1	MCERTS	< 0.1			
Total EPA-16 PAHs	mg/kg	< 1.6	MCERTS	< 1.6			



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



Soil Analysis Certificate - TPH CWG Banded					
<b>DETS Report No: 22-05766</b>	<b>Date Sampled</b>	30/06/22			
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied			
<b>Site Reference: P4301.3 - Sheldon House, Teddington</b>	<b>TP / BH No</b>	CP01			
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	ES1			
<b>Order No: 009248</b>	<b>Depth (m)</b>	0.30			
<b>Reporting Date: 11/07/2022</b>	<b>DETS Sample No</b>	603668			

Determinand	Unit	RL	Accreditation				
Aliphatic >C5 - C6 : HS 1D MS AL	mg/kg	< 0.01	NONE	< 0.01			
Aliphatic >C6 - C8 : HS 1D MS AL	mg/kg	< 0.05	NONE	< 0.05			
Aliphatic >C8 - C10 : EH 1D FID AL	mg/kg	< 2	MCERTS	< 2			
Aliphatic >C10 - C12 : EH 1D FID AL	mg/kg	< 2	MCERTS	< 2			
Aliphatic >C12 - C16 : EH 1D FID AL	mg/kg	< 3	MCERTS	< 3			
Aliphatic >C16 - C21 : EH 1D FID AL	mg/kg	< 3	MCERTS	< 3			
Aliphatic >C21 - C34 : EH 1D FID AL	mg/kg	< 10	MCERTS	< 10			
Aliphatic (C5 - C34) : EH 1D FID MS HS AL	mg/kg	< 21	NONE	< 21			
Aromatic >C5 - C7 : HS 1D MS AR	mg/kg	< 0.01	NONE	< 0.01			
Aromatic >C7 - C8 : HS 1D MS AR	mg/kg	< 0.05	NONE	< 0.05			
Aromatic >C8 - C10 : EH 1D FID AR	mg/kg	< 2	MCERTS	< 2			
Aromatic >C10 - C12 : EH 1D FID AR	mg/kg	< 2	MCERTS	< 2			
Aromatic >C12 - C16 : EH 1D FID AR	mg/kg	< 2	MCERTS	< 2			
Aromatic >C16 - C21 : EH 1D FID AR	mg/kg	< 3	MCERTS	< 3			
Aromatic >C21 - C35 : EH 1D FID AR	mg/kg	< 10	MCERTS	< 10			
Aromatic (C5 - C35) : EH 1D FID MS HS AR	mg/kg	< 21	NONE	< 21			
Total >C5 - C35 : EH_1D_FID_MS_HS_Total	mg/kg	< 42	NONE	< 42			



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Soil Analysis Certificate - BTEX / MTBE						
DETS Report No: 22-05766	Date Sampled	30/06/22				
AGB Environmental Ltd	Time Sampled	None Supplied				
Site Reference: P4301.3 - Sheldon House, Teddington	TP / BH No	CP01				
Project / Job Ref: P4301.3	Additional Refs	ES1				
Order No: 009248	Depth (m)	0.30				
Reporting Date: 11/07/2022	DETS Sample No	603668				

Determinand	Unit	RL	Accreditation				
Benzene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2			
Toluene : HS_1D_MS	ug/kg	< 5	MCERTS	< 5			
Ethylbenzene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2			
p & m-xylene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2			
o-xylene : HS_1D_MS	ug/kg	< 2	MCERTS	< 2			
MTBE : HS_1D_MS	ug/kg	< 5	MCERTS	< 5			



DETS Ltd  
Unit 1, Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Maidstone  
Kent ME17 2JN  
Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions	
DETS Report No: 22-05766	
AGB Environmental Ltd	
Site Reference: P4301.3 - Sheldon House, Teddington	
Project / Job Ref: P4301.3	
Order No: 009248	
Reporting Date: 11/07/2022	

DETS Sample No	TP / BH No	Additional Refs	Depth (m)	Moisture Content (%)	Sample Matrix Description
603668	CP01	ES1	0.30	8.9	Brown sandy clay with brick and concrete
603669	CP01	ES3	1.20	13.5	Light brown sandy clay
603670	CP01	ES	7.00	4.2	Brown sandy clay with stones
603671	CP01	ES	12.00	20.1	Brown clay
603672	CP01	ES	15.00	22.4	Brown clay
603673	CP01	ES	18.00	18.8	Brown clay
603674	CP01	ES	21.00	21.1	Brown clay
603675	CP01	ES	24.00	21.4	Brown clay

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample <sup>1/S</sup>

Unsuitable Sample <sup>U/S</sup>

<b>Soil Analysis Certificate - Methodology &amp; Miscellaneous Information</b>	
DETS Report No: 22-05766	
AGB Environmental Ltd	
Site Reference: P4301.3 - Sheldon House, Teddington	
Project / Job Ref: P4301.3	
Order No: 009248	
Reporting Date: 11/07/2022	

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphenylcarbazide followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 – C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	Fraction Organic Carbon (FOC)	Determination of TOC by combustion analyser.	E027
Soil	D	Organic Matter (SOM)	Determination of TOC by combustion analyser.	E027
Soil	D	TOC (Total Organic Carbon)	Determination of TOC by combustion analyser.	E027
Soil	AR	Exchangeable Ammonium	Determination of ammonium by discrete analyser.	E029
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCs	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

**D Dried**  
**AR As Received**

## List of HWOL Acronyms and Operators

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
_	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total

### Det - Acronym

Benzene - HS\_1D\_MS  
 Ethylbenzene - HS\_1D\_MS  
 MTBE - HS\_1D\_MS  
 TPH CWG - Aliphatic >C10 - C12 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C12 - C16 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C16 - C21 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C21 - C34 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C5 - C6 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C6 - C8 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C8 - C10 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic C5 - C34 - EH\_1D\_FID\_MS\_HS\_AL  
 TPH CWG - Aromatic >C10 - C12 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C12 - C16 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C16 - C21 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C21 - C35 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C5 - C35 - EH\_1D\_FID\_MS\_HS\_AR  
 TPH CWG - Aromatic >C5 - C7 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C7 - C8 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C8 - C10 - EH\_1D\_FID\_AR  
 TPH CWG - Total >C5 - C35 - EH\_1D\_FID\_MS\_HS\_Total  
 Toluene - HS\_1D\_MS  
 m & p-xylene - HS\_1D\_MS  
 o-Xylene - HS\_1D\_MS





Helen Gildersleeves  
AGB Environmental Ltd  
1 The Mill  
Copley Hill Business Park  
Abraham Road  
Cambridge  
CB22 3GN

**Derwentside Environmental Testing Services Ltd**  
Unit 1  
Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Kent  
ME17 2JN  
t: 01622 850410

## **DETS Report No: 22-05987**

**Site Reference:** Sheldon House, Teddington

**Project / Job Ref:** P4301.3

**Order No:** 009260

**Sample Receipt Date:** 13/07/2022

**Sample Scheduled Date:** 13/07/2022

**Report Issue Number:** 1

**Reporting Date:** 18/07/2022

**Authorised by:**

Dave Ashworth  
Technical Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**



**Water Analysis Certificate**

<b>DETS Report No: 22-05987</b>	<b>Date Sampled</b>	11/07/22				
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied				
<b>Site Reference: Sheldon House, Teddington</b>	<b>TP / BH No</b>	CP01 MON1				
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	P4301				
<b>Order No: 009260</b>	<b>Depth (m)</b>	4.15				
<b>Reporting Date: 18/07/2022</b>	<b>DETS Sample No</b>	604797				

Determinand	Unit	RL	Accreditation				
pH	pH Units	N/a	ISO17025	7.3			
Sulphate as SO <sub>4</sub>	mg/l	< 1	ISO17025	103			
Total Organic Carbon (TOC)	mg/l	< 0.1	NONE	7.1			
Arsenic (dissolved)	ug/l	< 5	ISO17025	< 5			
Cadmium (dissolved)	ug/l	< 0.4	ISO17025	0.4			
Chromium (dissolved)	ug/l	< 5	ISO17025	< 5			
Chromium (hexavalent)	ug/l	< 20	NONE	< 20			
Copper (dissolved)	ug/l	< 5	ISO17025	< 5			
Lead (dissolved)	ug/l	< 5	ISO17025	< 5			
Mercury (dissolved)	ug/l	< 0.05	ISO17025	< 0.05			
Nickel (dissolved)	ug/l	< 5	ISO17025	18			
Selenium (dissolved)	ug/l	< 5	ISO17025	< 5			
Zinc (dissolved)	ug/l	< 2	ISO17025	105			

Subcontracted analysis <sup>(S)</sup>  
 Insufficient sample <sup>I/S</sup>  
 Unsuitable Sample <sup>U/S</sup>



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**

Water Analysis Certificate - Speciated PAH						
DETS Report No: 22-05987	Date Sampled	11/07/22				
AGB Environmental Ltd	Time Sampled	None Supplied				
Site Reference: Sheldon House, Teddington	TP / BH No	CP01 MON1				
Project / Job Ref: P4301.3	Additional Refs	P4301				
Order No: 009260	Depth (m)	4.15				
Reporting Date: 18/07/2022	DETS Sample No	604797				

Determinand	Unit	RL	Accreditation				
Naphthalene	ug/l	< 0.01	NONE	< 0.01			
Acenaphthylene	ug/l	< 0.01	NONE	< 0.01			
Acenaphthene	ug/l	< 0.01	NONE	< 0.01			
Fluorene	ug/l	< 0.01	NONE	< 0.01			
Phenanthrene	ug/l	< 0.01	NONE	< 0.01			
Anthracene	ug/l	< 0.01	NONE	< 0.01			
Fluoranthene	ug/l	< 0.01	NONE	< 0.01			
Pyrene	ug/l	< 0.01	NONE	< 0.01			
Benzo(a)anthracene	ug/l	< 0.01	NONE	< 0.01			
Chrysene	ug/l	< 0.01	NONE	< 0.01			
Benzo(b)fluoranthene	ug/l	< 0.01	NONE	< 0.01			
Benzo(k)fluoranthene	ug/l	< 0.01	NONE	< 0.01			
Benzo(a)pyrene	ug/l	< 0.01	NONE	< 0.01			
Indeno(1,2,3-cd)pyrene	ug/l	< 0.01	NONE	< 0.01			
Dibenz(a,h)anthracene	ug/l	< 0.01	NONE	< 0.01			
Benzo(ghi)perylene	ug/l	0.008	NONE	< 0.008			
Total EPA-16 PAHs	ug/l	< 0.16	NONE	< 0.16			



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**

Water Analysis Certificate - TPH CWG Banded					
<b>DETS Report No: 22-05987</b>	<b>Date Sampled</b>	11/07/22			
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied			
<b>Site Reference: Sheldon House, Teddington</b>	<b>TP / BH No</b>	CP01 MON1			
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	P4301			
<b>Order No: 009260</b>	<b>Depth (m)</b>	4.15			
<b>Reporting Date: 18/07/2022</b>	<b>DETS Sample No</b>	604797			

Determinand	Unit	RL	Accreditation				
Aliphatic >C5 - C6 : HS 1D MS AL	ug/l	< 10	NONE	< 10			
Aliphatic >C6 - C8 : HS 1D MS AL	ug/l	< 10	NONE	< 10			
Aliphatic >C8 - C10 : EH 1D FID AL	ug/l	< 10	NONE	< 10			
Aliphatic >C10 - C12 : EH 1D FID AL	ug/l	< 10	NONE	< 10			
Aliphatic >C12 - C16 : EH 1D FID AL	ug/l	< 10	NONE	< 10			
Aliphatic >C16 - C21 : EH 1D FID AL	ug/l	< 10	NONE	< 10			
Aliphatic >C21 - C34 : EH 1D FID AL	ug/l	< 10	NONE	< 10			
Aliphatic (C5 - C34) : EH 1D FID MS HS AL	ug/l	< 70	NONE	< 70			
Aromatic >C5 - C7 : HS 1D MS AR	ug/l	< 10	NONE	< 10			
Aromatic >C7 - C8 : HS 1D MS AR	ug/l	< 10	NONE	< 10			
Aromatic >C8 - C10 : EH 1D FID AR	ug/l	< 10	NONE	< 10			
Aromatic >C10 - C12 : EH 1D FID AR	ug/l	< 10	NONE	< 10			
Aromatic >C12 - C16 : EH 1D FID AR	ug/l	< 10	NONE	< 10			
Aromatic >C16 - C21 : EH 1D FID AR	ug/l	< 10	NONE	< 10			
Aromatic >C21 - C35 : EH 1D FID AR	ug/l	< 10	NONE	< 10			
Aromatic (C5 - C35) : EH 1D FID MS HS AR	ug/l	< 70	NONE	< 70			
Total >C5 - C35 : EH_1D_FID_MS_HS_Total	ug/l	< 140	NONE	< 140			



DETS Ltd  
Unit 1, Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Maidstone  
Kent ME17 2JN  
Tel : 01622 850410



Water Analysis Certificate - BTEX / MTBE						
DETS Report No: 22-05987	Date Sampled	11/07/22				
AGB Environmental Ltd	Time Sampled	None Supplied				
Site Reference: Sheldon House, Teddington	TP / BH No	CP01 MON1				
Project / Job Ref: P4301.3	Additional Refs	P4301				
Order No: 009260	Depth (m)	4.15				
Reporting Date: 18/07/2022	DETS Sample No	604797				

Determinand	Unit	RL	Accreditation				
Benzene : HS_1D_MS	ug/l	< 1	ISO17025	< 1			
Toluene : HS_1D_MS	ug/l	< 5	ISO17025	< 5			
Ethylbenzene : HS_1D_MS	ug/l	< 5	ISO17025	< 5			
p & m-xylene : HS_1D_MS	ug/l	< 10	ISO17025	< 10			
o-xylene : HS_1D_MS	ug/l	< 5	ISO17025	< 5			
MTBE : HS_1D_MS	ug/l	< 10	ISO17025	< 10			

<b>Water Analysis Certificate - Methodology &amp; Miscellaneous Information</b>
DETS Report No: 22-05987
AGB Environmental Ltd
Site Reference: Sheldon House, Teddington
Project / Job Ref: P4301.3
Order No: 009260
Reporting Date: 18/07/2022

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Water	UF	Alkalinity	Determination of alkalinity by titration against hydrochloric acid using bromocresol green as the end point	E103
Water	F	Ammoniacal Nitrogen	Determination of ammoniacal nitrogen by discrete analyser.	E126
Water	UF	BTEX	Determination of BTEX by headspace GC-MS	E101
Water	F	Cations	Determination of cations by filtration followed by ICP-MS	E102
Water	UF	Chemical Oxygen Demand (COD)	Determination using a COD reactor followed by colorimetry	E112
Water	F	Chloride	Determination of chloride by filtration & analysed by ion chromatography	E109
Water	F	Chromium - Hexavalent	Determination of hexavalent chromium by acidification, addition of 1,5 diphenylcarbazide followed by	E116
Water	UF	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E115
Water	UF	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E115
Water	UF	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E115
Water	UF	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through liquid:liquid extraction with cyclohexane	E111
Water	F	Diesel Range Organics (C10 - C24)	Determination of liquid:liquid extraction with hexane followed by GC-FID	E104
Water	F	Dissolved Organic Content (DOC)	Determination of DOC by filtration followed by low heat with persulphate addition followed by IR dete	E110
Water	UF	Electrical Conductivity	Determination of electrical conductivity by electrometric measurement	E123
Water	F	EPH (C10 - C40)	Determination of liquid:liquid extraction with hexane followed by GC-FID	E104
Water	F	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of liquid:liquid extraction with hexane followed by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E104
Water	F	Fluoride	Determination of Fluoride by filtration & analysed by ion chromatography	E109
Water	F	Hardness	Determination of Ca and Mg by ICP-MS followed by calculation	E102
Leachate	F	Leachate Preparation - NRA	Based on National Rivers Authority leaching test 1994	E301
Leachate	F	Leachate Preparation - WAC	Based on BS EN 12457 Pt1, 2, 3	E302
Water	F	Metals	Determination of metals by filtration followed by ICP-MS	E102
Water	F	Mineral Oil (C10 - C40)	Determination of liquid:liquid extraction with hexane followed by GI-FID	E104
Water	F	Nitrate	Determination of nitrate by filtration & analysed by ion chromatography	E109
Water	UF	Monohydric Phenol	Determination of phenols by distillation followed by colorimetry	E121
Water	F	PAH - Speciated (EPA 16)	Determination of PAH compounds by concentration through SPE cartridge, collection in dichloromethane followed by GC-MS	E105
Water	F	PCB - 7 Congeners	Determination of PCB compounds by concentration through SPE cartridge, collection in dichloromethane	E108
Water	UF	Petroleum Ether Extract (PEE)	Gravimetrically determined through liquid:liquid extraction with petroleum ether	E111
Water	UF	pH	Determination of pH by electrometric measurement	E107
Water	F	Phosphate	Determination of phosphate by filtration & analysed by ion chromatography	E109
Water	UF	Redox Potential	Determination of redox potential by electrometric measurement	E113
Water	F	Sulphate (as SO4)	Determination of sulphate by filtration & analysed by ion chromatography	E109
Water	UF	Sulphide	Determination of sulphide by distillation followed by colorimetry	E118
Water	F	SVOC	Determination of semi-volatile organic compounds by concentration through SPE cartridge, collection in dichloromethane followed by GC-MS	E106
Water	UF	Toluene Extractable Matter (TEM)	Gravimetrically determined through liquid:liquid extraction with toluene	E111
Water	UF	Total Organic Carbon (TOC)	Low heat with persulphate addition followed by IR detection	E110
Water	F	TPH CWG (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of liquid:liquid extraction with hexane, fractionating with SPE followed by GC-FID for C8 to C35. C5 to C8 by headspace GC-MS	E104
Water	F	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of liquid:liquid extraction with hexane, fractionating with SPE followed by GC-FID for C8 to C44. C5 to C8 by headspace GC-MS	E104
Water	UF	VOCs	Determination of volatile organic compounds by headspace GC-MS	E101
Water	UF	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E101

Key

**F Filtered**  
**UF Unfiltered**

## List of HWOL Acronyms and Operators

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
_	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total

### Det - Acronym

Benzene - HS\_1D\_MS  
 Ethylbenzene - HS\_1D\_MS  
 MTBE - HS\_1D\_MS  
 TPH CWG - Aliphatic >C10 - C12 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C12 - C16 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C16 - C21 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C21 - C34 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C5 - C34 - EH\_1D\_FID\_MS\_HS\_AL  
 TPH CWG - Aliphatic >C5 - C6 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C6 - C8 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C8 - C10 - EH\_1D\_FID\_AL  
 TPH CWG - Aromatic >C10 - C12 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C12 - C16 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C16 - C21 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C21 - C35 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C5 - C7 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C7 - C8 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C8 - C10 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic C5 - C35 - EH\_1D\_FID\_MS\_HS\_AR  
 TPH CWG - Total >C5 - C35 - EH\_1D\_FID\_MS\_HS\_Total  
 Toluene - HS\_1D\_MS  
 m & p-xylene - HS\_1D\_MS  
 o-Xylene - HS\_1D\_MS



Natasha Masich  
AGB Environmental Ltd  
1 The Mill  
Copley Hill Business Park  
Abraham Road  
Cambridge  
CB22 3GN

**Derwentside Environmental Testing Services Ltd**  
Unit 1  
Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Kent  
ME17 2JN  
t: 01622 850410

## **DETS Report No: 22-06311**

**Site Reference:** Sheldon House, Teddington

**Project / Job Ref:** P4301.3

**Order No:** 009275

**Sample Receipt Date:** 25/07/2022

**Sample Scheduled Date:** 25/07/2022

**Report Issue Number:** 1

**Reporting Date:** 29/07/2022

**Authorised by:**

Dave Ashworth  
Technical Manager

Dates of laboratory activities for each tested analyte are available upon request.

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.





DETS Ltd  
Unit 1, Rose Lane Industrial Estate  
Rose Lane  
Lenham Heath  
Maidstone  
Kent ME17 2JN  
Tel : 01622 850410



Water Analysis Certificate						
DETS Report No: 22-06311	Date Sampled	21/07/22				
AGB Environmental Ltd	Time Sampled	None Supplied				
Site Reference: Sheldon House, Teddington	TP / BH No	CP01 MON2				
Project / Job Ref: P4301.3	Additional Refs	P4301				
Order No: 009275	Depth (m)	4.20				
Reporting Date: 29/07/2022	DETS Sample No	606204				

Determinand	Unit	RL	Accreditation	(hs)				
pH	pH Units	N/a	ISO17025	7.3				
Sulphate as SO <sub>4</sub>	mg/l	< 1	ISO17025	105				
Total Organic Carbon (TOC)	mg/l	< 0.1	NONE	7.2				
Arsenic (dissolved)	ug/l	< 5	ISO17025	< 5				
Cadmium (dissolved)	ug/l	< 0.4	ISO17025	< 0.4				
Chromium (dissolved)	ug/l	< 5	ISO17025	< 5				
Chromium (hexavalent)	ug/l	< 20	NONE	< 20				
Copper (dissolved)	ug/l	< 5	ISO17025	< 5				
Lead (dissolved)	ug/l	< 5	ISO17025	< 5				
Mercury (dissolved)	ug/l	< 0.05	ISO17025	< 0.05				
Nickel (dissolved)	ug/l	< 5	ISO17025	< 5				
Selenium (dissolved)	ug/l	< 5	ISO17025	< 5				
Zinc (dissolved)	ug/l	< 2	ISO17025	< 2				

Subcontracted analysis <sup>(S)</sup>

Insufficient sample <sup>1/S</sup>

Unsuitable Sample <sup>u/s</sup>

(hs) Please note deviating sample due to head space in container



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**

Water Analysis Certificate - Speciated PAH					
DETS Report No: 22-06311	Date Sampled	21/07/22			
AGB Environmental Ltd	Time Sampled	None Supplied			
Site Reference: Sheldon House, Teddington	TP / BH No	CP01 MON2			
Project / Job Ref: P4301.3	Additional Refs	P4301			
Order No: 009275	Depth (m)	4.20			
Reporting Date: 29/07/2022	DETS Sample No	606204			

Determinand	Unit	RL	Accreditation	(hs)				
Naphthalene	ug/l	< 0.01	NONE	< 0.01				
Acenaphthylene	ug/l	< 0.01	NONE	< 0.01				
Acenaphthene	ug/l	< 0.01	NONE	< 0.01				
Fluorene	ug/l	< 0.01	NONE	< 0.01				
Phenanthrene	ug/l	< 0.01	NONE	< 0.01				
Anthracene	ug/l	< 0.01	NONE	< 0.01				
Fluoranthene	ug/l	< 0.01	NONE	< 0.01				
Pyrene	ug/l	< 0.01	NONE	< 0.01				
Benzo(a)anthracene	ug/l	< 0.01	NONE	< 0.01				
Chrysene	ug/l	< 0.01	NONE	< 0.01				
Benzo(b)fluoranthene	ug/l	< 0.01	NONE	< 0.01				
Benzo(k)fluoranthene	ug/l	< 0.01	NONE	< 0.01				
Benzo(a)pyrene	ug/l	< 0.01	NONE	< 0.01				
Indeno(1,2,3-cd)pyrene	ug/l	< 0.01	NONE	< 0.01				
Dibenz(a,h)anthracene	ug/l	< 0.01	NONE	< 0.01				
Benzo(ghi)perylene	ug/l	0.008	NONE	< 0.008				
Total EPA-16 PAHs	ug/l	< 0.16	NONE	< 0.16				



**DETS Ltd**  
**Unit 1, Rose Lane Industrial Estate**  
**Rose Lane**  
**Lenham Heath**  
**Maidstone**  
**Kent ME17 2JN**  
**Tel : 01622 850410**

Water Analysis Certificate - TPH CWG Banded					
<b>DETS Report No: 22-06311</b>	<b>Date Sampled</b>	21/07/22			
<b>AGB Environmental Ltd</b>	<b>Time Sampled</b>	None Supplied			
<b>Site Reference: Sheldon House, Teddington</b>	<b>TP / BH No</b>	CP01 MON2			
<b>Project / Job Ref: P4301.3</b>	<b>Additional Refs</b>	P4301			
<b>Order No: 009275</b>	<b>Depth (m)</b>	4.20			
<b>Reporting Date: 29/07/2022</b>	<b>DETS Sample No</b>	606204			

Determinand	Unit	RL	Accreditation	(hs)				
Aliphatic >C5 - C6 : HS 1D MS AL	ug/l	< 10	NONE	< 10				
Aliphatic >C6 - C8 : HS 1D MS AL	ug/l	< 10	NONE	< 10				
Aliphatic >C8 - C10 : EH 1D FID AL	ug/l	< 10	NONE	< 10				
Aliphatic >C10 - C12 : EH 1D FID AL	ug/l	< 10	NONE	< 10				
Aliphatic >C12 - C16 : EH 1D FID AL	ug/l	< 10	NONE	< 10				
Aliphatic >C16 - C21 : EH 1D FID AL	ug/l	< 10	NONE	< 10				
Aliphatic >C21 - C34 : EH 1D FID AL	ug/l	< 10	NONE	< 10				
Aliphatic (C5 - C34) : EH 1D FID MS HS AL	ug/l	< 70	NONE	< 70				
Aromatic >C5 - C7 : HS 1D MS AR	ug/l	< 10	NONE	< 10				
Aromatic >C7 - C8 : HS 1D MS AR	ug/l	< 10	NONE	< 10				
Aromatic >C8 - C10 : EH 1D FID AR	ug/l	< 10	NONE	< 10				
Aromatic >C10 - C12 : EH 1D FID AR	ug/l	< 10	NONE	< 10				
Aromatic >C12 - C16 : EH 1D FID AR	ug/l	< 10	NONE	< 10				
Aromatic >C16 - C21 : EH 1D FID AR	ug/l	< 10	NONE	< 10				
Aromatic >C21 - C35 : EH 1D FID AR	ug/l	< 10	NONE	< 10				
Aromatic (C5 - C35) : EH 1D FID MS HS AR	ug/l	< 70	NONE	< 70				
Total >C5 - C35 : EH_1D_FID_MS_HS_Total	ug/l	< 140	NONE	< 140				

(hs) Please note deviating sample due to head space in container



DETS Ltd  
 Unit 1, Rose Lane Industrial Estate  
 Rose Lane  
 Lenham Heath  
 Maidstone  
 Kent ME17 2JN  
 Tel : 01622 850410



Water Analysis Certificate - BTEX / MTBE						
DETS Report No: 22-06311	Date Sampled	21/07/22				
AGB Environmental Ltd	Time Sampled	None Supplied				
Site Reference: Sheldon House, Teddington	TP / BH No	CP01 MON2				
Project / Job Ref: P4301.3	Additional Refs	P4301				
Order No: 009275	Depth (m)	4.20				
Reporting Date: 29/07/2022	DETS Sample No	606204				

Determinand	Unit	RL	Accreditation	(hs)			
Benzene : HS_1D_MS	ug/l	< 1	ISO17025	< 1			
Toluene : HS_1D_MS	ug/l	< 5	ISO17025	< 5			
Ethylbenzene : HS_1D_MS	ug/l	< 5	ISO17025	< 5			
p & m-xylene : HS_1D_MS	ug/l	< 10	ISO17025	< 10			
o-xylene : HS_1D_MS	ug/l	< 5	ISO17025	< 5			
MTBE : HS_1D_MS	ug/l	< 10	ISO17025	< 10			

(hs) Please note deviating sample due to head space in container

<b>Water Analysis Certificate - Methodology &amp; Miscellaneous Information</b>
DETS Report No: 22-06311
AGB Environmental Ltd
Site Reference: Sheldon House, Teddington
Project / Job Ref: P4301.3
Order No: 009275
Reporting Date: 29/07/2022

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Water	UF	Alkalinity	Determination of alkalinity by titration against hydrochloric acid using bromocresol green as the end point	E103
Water	F	Ammoniacal Nitrogen	Determination of ammoniacal nitrogen by discrete analyser.	E126
Water	UF	BTEX	Determination of BTEX by headspace GC-MS	E101
Water	F	Cations	Determination of cations by filtration followed by ICP-MS	E102
Water	UF	Chemical Oxygen Demand (COD)	Determination using a COD reactor followed by colorimetry	E112
Water	F	Chloride	Determination of chloride by filtration & analysed by ion chromatography	E109
Water	F	Chromium - Hexavalent	Determination of hexavalent chromium by acidification, addition of 1,5 diphenylcarbazide followed by	E116
Water	UF	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E115
Water	UF	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E115
Water	UF	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E115
Water	UF	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through liquid:liquid extraction with cyclohexane	E111
Water	F	Diesel Range Organics (C10 - C24)	Determination of liquid:liquid extraction with hexane followed by GC-FID	E104
Water	F	Dissolved Organic Content (DOC)	Determination of DOC by filtration followed by low heat with persulphate addition followed by IR dete	E110
Water	UF	Electrical Conductivity	Determination of electrical conductivity by electrometric measurement	E123
Water	F	EPH (C10 - C40)	Determination of liquid:liquid extraction with hexane followed by GC-FID	E104
Water	F	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of liquid:liquid extraction with hexane followed by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E104
Water	F	Fluoride	Determination of Fluoride by filtration & analysed by ion chromatography	E109
Water	F	Hardness	Determination of Ca and Mg by ICP-MS followed by calculation	E102
Leachate	F	Leachate Preparation - NRA	Based on National Rivers Authority leaching test 1994	E301
Leachate	F	Leachate Preparation - WAC	Based on BS EN 12457 Pt1, 2, 3	E302
Water	F	Metals	Determination of metals by filtration followed by ICP-MS	E102
Water	F	Mineral Oil (C10 - C40)	Determination of liquid:liquid extraction with hexane followed by GI-FID	E104
Water	F	Nitrate	Determination of nitrate by filtration & analysed by ion chromatography	E109
Water	UF	Monohydric Phenol	Determination of phenols by distillation followed by colorimetry	E121
Water	F	PAH - Speciated (EPA 16)	Determination of PAH compounds by concentration through SPE cartridge, collection in dichloromethane followed by GC-MS	E105
Water	F	PCB - 7 Congeners	Determination of PCB compounds by concentration through SPE cartridge, collection in dichloromethane	E108
Water	UF	Petroleum Ether Extract (PEE)	Gravimetrically determined through liquid:liquid extraction with petroleum ether	E111
Water	UF	pH	Determination of pH by electrometric measurement	E107
Water	F	Phosphate	Determination of phosphate by filtration & analysed by ion chromatography	E109
Water	UF	Redox Potential	Determination of redox potential by electrometric measurement	E113
Water	F	Sulphate (as SO4)	Determination of sulphate by filtration & analysed by ion chromatography	E109
Water	UF	Sulphide	Determination of sulphide by distillation followed by colorimetry	E118
Water	F	SVOC	Determination of semi-volatile organic compounds by concentration through SPE cartridge, collection in dichloromethane followed by GC-MS	E106
Water	UF	Toluene Extractable Matter (TEM)	Gravimetrically determined through liquid:liquid extraction with toluene	E111
Water	UF	Total Organic Carbon (TOC)	Low heat with persulphate addition followed by IR detection	E110
Water	F	TPH CWG (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of liquid:liquid extraction with hexane, fractionating with SPE followed by GC-FID for C8 to C35. C5 to C8 by headspace GC-MS	E104
Water	F	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of liquid:liquid extraction with hexane, fractionating with SPE followed by GC-FID for C8 to C44. C5 to C8 by headspace GC-MS	E104
Water	UF	VOCs	Determination of volatile organic compounds by headspace GC-MS	E101
Water	UF	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E101

Key

**F Filtered**  
**UF Unfiltered**

## List of HWOL Acronyms and Operators

Acronym	Description
HS	Headspace analysis
EH	Extractable Hydrocarbons - i.e. everything extracted by the solvent
CU	Clean-up - e.g. by florisil, silica gel
1D	GC - Single coil gas chromatography
2D	GC-GC - Double coil gas chromatography
Total	Aliphatics & Aromatics
AL	Aliphatics only
AR	Aromatics only
#1	EH_2D_Total but with humics mathematically subtracted
#2	EH_2D_Total but with fatty acids mathematically subtracted
_	Operator - underscore to separate acronyms (exception for +)
+	Operator to indicate cumulative eg. EH+HS_Total or EH_CU+HS_Total


### Det - Acronym

Benzene - HS\_1D\_MS  
 Ethylbenzene - HS\_1D\_MS  
 MTBE - HS\_1D\_MS  
 TPH CWG - Aliphatic >C10 - C12 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C12 - C16 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C16 - C21 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C21 - C34 - EH\_1D\_FID\_AL  
 TPH CWG - Aliphatic >C5 - C34 - EH\_1D\_FID\_MS\_HS\_AL  
 TPH CWG - Aliphatic >C5 - C6 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C6 - C8 - HS\_1D\_MS\_AL  
 TPH CWG - Aliphatic >C8 - C10 - EH\_1D\_FID\_AL  
 TPH CWG - Aromatic >C10 - C12 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C12 - C16 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C16 - C21 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C21 - C35 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic >C5 - C7 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C7 - C8 - HS\_1D\_MS\_AR  
 TPH CWG - Aromatic >C8 - C10 - EH\_1D\_FID\_AR  
 TPH CWG - Aromatic C5 - C35 - EH\_1D\_FID\_MS\_HS\_AR  
 TPH CWG - Total >C5 - C35 - EH\_1D\_FID\_MS\_HS\_Total  
 Toluene - HS\_1D\_MS  
 m & p-xylene - HS\_1D\_MS  
 o-Xylene - HS\_1D\_MS



**TEST REPORT**  
ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022



<b>Contract</b>	P4301 - Sheldon House, Teddington	
<b>Serial No.</b>	41057_1	
<b>Client:</b>	<p>AGB Environmental Ltd  341 Exning Road Newmarket Suffolk CB8 0AT</p>	<p><b><i>Soil Property Testing Ltd</i></b>  15, 16, 18 Halcyon Court, St Margaret's Way, Stukeley Meadows, Huntingdon, Cambridgeshire, PE29 6DG  Tel: 01480 455579 Email: <a href="mailto:enquiries@soilpropertytesting.com">enquiries@soilpropertytesting.com</a> Website: <a href="http://www.soilpropertytesting.com">www.soilpropertytesting.com</a></p>
<b>Samples Submitted By:</b> AGB Environmental Ltd	<b>Samples Labelled:</b> P4301 - Sheldon House, Teddington	<b>Approved Signatories:</b>  <input checked="" type="checkbox"/> <b>J.C. Garner B.Eng (Hons) FGS</b> Technical Director & Quality Manager  <input type="checkbox"/> <b>W. Johnstone</b> Materials Lab Manager  
<b>Date Received:</b> 06/07/2022	<b>Samples Tested Between:</b> 06/07/2022 and 19/07/2022	
<b>Remarks:</b> For the attention of Helen Gildersleeves Your Reference No: P4301 Your Order No: 9249		
<b>Notes:</b>	<ol style="list-style-type: none"><li>1 All remaining samples or remnants from this contract will be disposed of after 21 days from today, unless we are notified to the contrary.</li><li>2 Opinions and interpretations expressed herein are outside the scope of UKAS accreditation.</li><li>3 Tests marked "NOT UKAS ACCREDITED" in this test report are not included in the UKAS Accreditation Schedule for this testing laboratory.</li><li>4 This test report may not be reproduced other than in full except with the prior written approval of the issuing laboratory.</li><li>5 The results within this report only relate to the items tested or sampled.</li></ol>	



# TEST REPORT

**ISSUED BY SOIL PROPERTY TESTING LTD**  
**DATE ISSUED: 19/07/2022**



0998

<b>Contract</b>		<b>P4301 - Sheldon House, Teddington</b>															
<b>Serial No.</b>		<b>41057_1</b>										<b>Target Date</b>		<b>20/07/2022</b>			
<b>Scheduled By</b>		<b>AGB Environmental Ltd</b>															
<b>Schedule Remarks</b>																	
Bore Hole No.	Type	Sample Ref.	Top Depth	<div style="display: flex; justify-content: space-between; padding: 2px;"> <span>Particle Size Distribution (BS1377)</span> <span>Water Content (BS EN)</span> <span>Liquid/Plastic Limits</span> <span>Wet Sieve Preparation</span> <span>Triaxial Test</span> </div>													Sample Remarks
				1	2	3	4	5	6	7	8	9	10	11	12	13	
CP01	B	-	2.00	1													
CP01	B	-	4.00	1													
CP01	B	-	7.00	1													
CP01	D	-	8.00		1	1											
CP01	D	-	9.00		1	1											
CP01	U	1	10.50							1							
CP01	D	-	11.00		1	1											
CP01	D	-	13.00		1	1											
CP01	U	2	14.00							1							
CP01	D	-	15.00		1	1											
CP01	U	3	17.00							1							
CP01	D	-	18.00		1	1											
CP01	D	-	21.00		1	1											
CP01	U	4	21.00							1							
CP01	D	-	24.00		1	1											
TP03	D	-	1.30		1	1	1										
WS02	D	-	1.40		1	1	1										
<b>Totals</b>				<b>3</b>	<b>10</b>	<b>10</b>	<b>2</b>	<b>4</b>									
<b>End of Schedule</b>																	





**TEST REPORT**  
**ISSUED BY SOIL PROPERTY TESTING LTD**  
**DATE ISSUED: 19/07/2022**



0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

**SUMMARY OF WATER CONTENT, LIQUID LIMIT, PLASTIC LIMIT, PLASTICITY INDEX AND LIQUIDITY INDEX**

Borehole /Pit No.	Depth (m)	Type	Ref.	Water Content (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	Liquid-ity Index	Sample Preparation			Description	Class	
									Method	Ret'd 0.425mm (%)	Corr'd W/C <0.425mm			Curing Time (hrs)
CP01	8.00	D	-	25.2	63	23	40	0.06	From Natural	0 (A)		24	Stiff fissured dark grey CLAY	CH
CP01	9.00	D	-	24.2	61	23	38	0.03	From Natural	0 (A)		24	Stiff fissured dark grey CLAY	CH
CP01	11.00	D	-	24.0	61	22	39	0.05	From Natural	0 (A)		25	Stiff fissured dark grey CLAY	CH
CP01	13.00	D	-	27.4	68	26	42	0.03	From Natural	0 (A)		25	Stiff fissured dark grey CLAY	CH
CP01	15.00	D	-	33.7	73	25	48	0.18	From Natural	0 (A)		24	Stiff fissured dark grey CLAY	CV
CP01	18.00	D	-	28.1	71	25	46	0.07	From Natural	0 (A)		24	Stiff fissured dark grey CLAY	CV
CP01	21.00	D	-	25.0	70	24	46	0.02	From Natural	0 (A)		24	Stiff fissured dark grey CLAY	CH/CV
CP01	24.00	D	-	29.3	74	26	48	0.07	From Natural	0 (A)		24	Stiff fissured dark grey CLAY	CV

Method Of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2:1990:4.2  
Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2:1990:3.2, 4.4, 5.3, 5.4  
Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
Comments:

Table Notation: Ret'd 0.425mm: (A) = Assumed, (M) = Measured



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022



0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### SUMMARY OF WATER CONTENT, LIQUID LIMIT, PLASTIC LIMIT, PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole /Pit No.	Depth (m)	Type	Ref.	Water Content (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	Liquid-ity Index	Sample Preparation				Description	Class
									Method	Ret'd 0.425mm (%)	Corr'd W/C <0.425mm	Curing Time (hrs)		
TP03	1.30	D	-	10.1	29	14	15	-0.26	Wet Sieved	3 (M)	10.4*	25	Very stiff yellowish brown sandy silty CLAY with occasional recently active and decayed roots	CL
WS02	1.40	D	-	7.9	30	16	14	-0.58	Wet Sieved	32 (M)	11.5*	24	Hard yellowish brown slightly gravelly slightly sandy silty CLAY with occasional recently active and decayed roots. Gravel is fine to coarse angular and subangular chert	CL

Method Of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2:1990:4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2:1990:3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: \*Corrected water content assume material greater than 0.425mm is non-porous. See BS1377: Part 2: 1990 Clause 3 Note 1.  
 Table Notation: Ret'd 0.425mm: (A) = Assumed, (M) = Measured



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

## PLOT OF PLASTICITY INDEX AGAINST LIQUID LIMIT USING CASAGRANDE CLASSIFICATION CHART

Plasticity				
Low	Medium	High	Very High	Extremely High



Plasticity Chart BS5930: 2015: Figure 8

High	NHBC Volume Change Potential
Medium	
Low	

Method of Preparation:	BS 1377: Part 2: 1990: 4.2
Method of Test:	BS1377: Part 2: 3.2, 4.4, 5.3, 5.4
Type of Sample Key:	U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter
Comments:	Volume Change Potential: NHBC Standards Chapter 4.2 Unmodified Plasticity Index



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	8.00	D	-	25.2	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	63 %	
Method of preparation			From natural	Plastic Limit	23 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	40 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.06	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	24 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

## DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	9.00	D	-	24.2	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	61 %	
Method of preparation			From natural	Plastic Limit	23 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	38 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.03	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	24 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	11.00	D	-	24.0	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	61 %	
Method of preparation			From natural	Plastic Limit	22 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	39 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.05	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	25 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	13.00	D	-	27.4	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	68 %	
Method of preparation			From natural	Plastic Limit	26 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	42 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.03	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	25 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	15.00	D	-	33.7	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	73 %	
Method of preparation			From natural	Plastic Limit	25 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	48 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.18	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	24 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:





# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

## DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	18.00	D	-	28.1	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	71 %	
Method of preparation			From natural	Plastic Limit	25 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	46 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.07	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	24 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	21.00	D	-	25.0	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	70 %	
Method of preparation			From natural	Plastic Limit	24 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	46 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.02	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	24 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
CP01	24.00	D	-	29.3	Stiff fissured dark grey CLAY	

<b>PREPARATION</b>			Liquid Limit	74 %	
Method of preparation			From natural	Plastic Limit	26 %
Sample retained 0.425mm sieve	(Assumed)	0 %	Plasticity Index	48 %	
Corrected water content for material passing 0.425mm			Liquidity Index	0.07	
Sample retained 2mm sieve	(Assumed)	0 %	NHBC Modified (I'p)	n/a	
Curing time	24 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
TP03	1.30	D	-	10.1	Very stiff yellowish brown sandy silty CLAY with occasional recently active and decayed roots	

<b>PREPARATION</b>			Liquid Limit	29 %	
Method of preparation			Wet sieved over 0.425mm sieve	Plastic Limit	14 %
Sample retained 0.425mm sieve	(Measured)	3 %	Plasticity Index	15 %	
Corrected water content for material passing 0.425mm			10.4 %	Liquidity Index	-0.26
Sample retained 2mm sieve	(Measured)	<1 %	NHBC Modified (I'p)	15 %	
Curing time	25 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments: Corrected water content assume material greater than 0.425mm non-porous. See BS1377: Part2: 1990 Clause 3 Note 1  
 Volume Change Potential: NHBC Standards Chapter 4.2 Unmodified Plasticity Index  
 Note: Modified Plasticity Index I'p = Ip x (% less than 425microns/100)



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

### DETERMINATION OF WATER CONTENT, LIQUID LIMIT AND PLASTIC LIMIT AND DERIVATION OF PLASTICITY INDEX AND LIQUIDITY INDEX

Borehole / Pit No.	Depth m	Sample		Water Content (W) %	Description	Remarks
		Type	Reference			
WS02	1.40	D	-	7.9	Hard yellowish brown slightly gravelly slightly sandy silty CLAY with occasional recently active and decayed roots. Gravel is fine to coarse angular and subangular chert	

<b>PREPARATION</b>			Liquid Limit	30 %	
Method of preparation			Wet sieved over 0.425mm sieve	Plastic Limit	16 %
Sample retained 0.425mm sieve	(Measured)	32 %	Plasticity Index	14 %	
Corrected water content for material passing 0.425mm			11.5 %	Liquidity Index	-0.58
Sample retained 2mm sieve	(Measured)	21 %	NHBC Modified (I'p)	10 %	
Curing time	24 hrs	Clay Content	Not analysed	Derived Activity	Not analysed



Method of Preparation: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 4.2  
 Method of Test: BS EN ISO: 17892-1: 2014 & BS 1377: Part 2: 1990: 3.2, 4.4, 5.3, 5.4  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments: Corrected water content assume material greater than 0.425mm non-porous. See BS1377: Part2: 1990 Clause 3 Note 1  
 Volume Change Potential: NHBC Standards Chapter 4.2 Unmodified Plasticity Index  
 Note: Modified Plasticity Index I'p = Ip x (% less than 425microns/100)



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

## DETERMINATION OF PARTICLE SIZE DISTRIBUTION

Borehole / Pit No.	Depth (m)	Sample		Description	Remarks
		Type	Reference		
CP01	2.00	B	-	Black, brown and white subangular and subrounded slightly silty very sandy chert GRAVEL. Sand is yellowish brown	

Method of Test: **Wet Sieve**      Method of Pretreatment: **Not required**



CLAY	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	COBBLES	BOULDERS
	SILT			SAND			GRAVEL				

Hydrometer	Particle Size (mm)	Passing (%)	Silt by Dry Mass (%)	

		Clay by Dry Mass (%)

Sieve Size (mm)	Passing (%)	Sand By Dry Mass (%)
2.00	39	<b>36</b>
1.18	35	
0.600	27	
0.425	18	
0.300	8	
0.212	4	
0.150	4	
0.063	3	

Sieve Size (mm)	Passing (%)	2mm+ By Dry Mass (%)
300		<b>61</b>
125		
90		
63		
50	100	
37.5	97	
28	89	
20	79	
14	68	
10	58	
6.3	50	
5	47	

Fines By Dry Mass (%)	
<0.063mm	<b>3</b>

Method of Preparation: BS1377: Part 1: 2016: 8.3 & 8.4.5  
 Method of test: BS1377: Part 2: 1990: 9.2  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

## DETERMINATION OF PARTICLE SIZE DISTRIBUTION

Borehole / Pit No.	Depth (m)	Sample		Description	Remarks
		Type	Reference		
CP01	4.00	B	-	Black, brown and white subangular and subrounded slightly silty very sandy chert GRAVEL. Sand is yellowish brown	

Method of Test: **Wet Sieve**      Method of Pretreatment: **Not required**



CLAY	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	COBBLES	BOULDERS
	SILT			SAND			GRAVEL				

Hydrometer	Particle Size (mm)	Passing (%)	Silt by Dry Mass (%)	

		Clay by Dry Mass (%)

Sieve Size (mm)	Passing (%)	Sand By Dry Mass (%)
2.00	47	<b>44</b>
1.18	42	
0.600	35	
0.425	26	
0.300	15	
0.212	8	
0.150	5	
0.063	3	

Sieve Size (mm)	Passing (%)	2mm+ By Dry Mass (%)
300		<b>53</b>
125		
90		
63		
50		
37.5	100	
28	98	
20	93	
14	82	
10	74	
6.3	62	
5	59	

Fines By Dry Mass (%)	
<0.063mm	<b>3</b>

Method of Preparation: BS1377: Part 1: 2016: 8.3 & 8.4.5  
 Method of test: BS1377: Part 2: 1990: 9.2  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

## DETERMINATION OF PARTICLE SIZE DISTRIBUTION

Borehole / Pit No.	Depth (m)	Sample		Description	Remarks
		Type	Reference		
CP01	7.00	B	-	Yellowish brown slightly silty very gravelly SAND. Gravel is black, brown and white subangular and subrounded chert	

Method of Test: **Wet Sieve**      Method of Pretreatment: **Not required**



CLAY	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	COBBLES	BOULDERS
	SILT			SAND			GRAVEL				

Hydrometer	Particle Size (mm)	Passing (%)	Silt by Dry Mass (%)	

		Clay by Dry Mass (%)

Sieve Size (mm)	Passing (%)	Sand By Dry Mass (%)
2.00	65	<b>63</b>
1.18	61	
0.600	44	
0.425	22	
0.300	10	
0.212	5	
0.150	3	
0.063	2	

Fines By Dry Mass (%)	
<0.063mm	<b>2</b>

Sieve Size (mm)	Passing (%)	2mm+ By Dry Mass (%)
300		<b>35</b>
125		
90		
63		
50	100	
37.5	98	
28	94	
20	89	
14	79	
10	75	
6.3	70	
5	68	

Method of Preparation: BS1377: Part 1: 2016: 8.3 & 8.4.5  
 Method of test: BS1377: Part 2: 1990: 9.2  
 Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter  
 Comments:





# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022



0998

<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>

## DETERMINATION OF DENSITY, WATER CONTENT AND UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )	Lateral Pressure (kPa)	Deviator Stress (kPa)	Shear Stress (kPa)	Mohrs Circle Analysis		Description
										Cu (kPa)	Ø degrees	
CP01	10.50	U	1	27.1	2.01	1.58	206	241	121			Stiff (high strength) fissured dark grey CLAY
CP01	14.04	U	2	28.8	1.98	1.54	280	284	142			Stiff (high strength) fissured dark grey CLAY
CP01	17.03	U	3	29.8	1.99	1.53	340	297	149			Stiff (high strength) fissured dark grey CLAY
CP01	21.06	U	4	25.4	2.04	1.63	420	474	237			Very stiff (very high strength) fissured dark grey CLAY

Method of Preparation: BS 1377: Part 1: 1990: 7.4.2 & 8, Part 2: 1990: 7.2, Part 7: 1990: 8.3  
 Method of Test: BS 1377: Part 2: 1990:3 Determination of Moisture Content, Part2: 1990:7 Determination of Density, Part 7: 1990: 8 Undrained Shear Strength, 9 Multistage Loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments:  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998


<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>


## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
CP01	10.50	U	1	Stiff (high strength) fissured dark grey CLAY	

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>10.50</b>	184.8	102.6	3074	<b>27.1</b>	<b>2.01</b>	<b>1.58</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>206</b>	5.7	0.5	\	241	<b>121</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998


<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>


## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
CP01	14.00	U	2	Stiff (high strength) fissured dark grey CLAY	

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>14.04</b>	199.3	102.4	3256	<b>28.8</b>	<b>1.98</b>	<b>1.54</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>280</b>	9.0	0.6	\	284	<b>142</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998


<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>


## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
CP01	17.00	U	3	Stiff (high strength) fissured dark grey CLAY	Premature failure at 3.3% strain.

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>17.03</b>	199.4	102.8	3298	<b>29.8</b>	<b>1.99</b>	<b>1.53</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---



Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohrs Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>340</b>	3.3	0.3	\	297	<b>149</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C



# TEST REPORT

ISSUED BY SOIL PROPERTY TESTING LTD  
DATE ISSUED: 19/07/2022




0998


<b>Contract</b>	<b>P4301 - Sheldon House, Teddington</b>
<b>Serial No.</b>	<b>41057_1</b>


## DETERMINATION OF UNDRAINED SHEAR STRENGTH IN TRIAXIAL COMPRESSION WITHOUT MEASUREMENT OF PORE PRESSURE

Borehole /Pit No.	Depth (m)	Type	Reference	Description	Remarks
CP01	21.00	U	4	Very stiff (very high strength) fissured dark grey CLAY	

Initial Specimen	Height (mm)	Diameter (mm)	Weight (g)	Water Content (%)	Bulk Density (Mg/m <sup>3</sup> )	Dry Density (Mg/m <sup>3</sup> )
 Depth of Top of Specimen (m) <b>21.06</b>	199.3	102.4	3346	<b>25.4</b>	<b>2.04</b>	<b>1.63</b>

<b>TEST INFORMATION</b>	Rate of Strain <b>1.0</b> % per Min	Rubber Membrane Thickness <b>0.3</b> mm
-------------------------	-------------------------------------	---




Specimen at failure	Measured Cell Pressure, $\sigma_3$ (kPa)	Strain at Failure (%)	Stress Corrections (kPa)		Corrected Max. Deviator Stress, $(\sigma_1 - \sigma_3)_f$ (kPa)	Shear Stress $C_u$ , $\frac{1}{2}(\sigma_1 - \sigma_3)_f$ (kPa)	Mohr's Circle Analysis	
			Rubber Membrane	Piston Friction			$C_u$ (kPa)	$\phi$ (degrees)
	<b>420</b>	<b>6.3</b>	<b>0.5</b>	\	<b>474</b>	<b>237</b>		

Method of Preparation: BS 1377: Part 1: 1990  
 Method of Test: BS 1377: Part 7: 1990: 8 Definitive Method, 1990: 9 Multi-stage loading  
 Type of Sample Key: U = Undisturbed, B = Bulk, D = Disturbed, J = Jar, W = Water, SPT = Split Spoon Sample, C = Core Cutter  
 Comments: Tested in Vertical Condition  
 UKAS Calibration - loads from 0.2 to 10kN  
 Remarks to Include: Sample disturbance, loss of moisture, variation from test procedure, location and origin of test specimen within original sample, oven drying temperature if not 105-110°C

# Waste Classification Report

HazWasteOnline™ classifies waste as either **hazardous** or **non-hazardous** based on its chemical composition, related legislation and the rules and data defined in the current UK or EU technical guidance (Appendix C) (note that HP 9 Infectious is not assessed). It is the responsibility of the classifier named below to:

- a) understand the origin of the waste
- b) select the correct List of Waste code(s)
- c) confirm that the list of determinands, results and sampling plan are fit for purpose
- d) select and justify the chosen metal species (Appendix B)
- e) correctly apply moisture correction and other available corrections
- f) add the meta data for their user-defined substances (Appendix A)
- g) check that the classification engine is suitable with respect to the national destination of the waste (Appendix C)



UOERS-AVYJY-3F3FY

To aid the reviewer, the laboratory results, assumptions and justifications managed by the classifier are highlighted in pale yellow.

## Job name

P4301.3

## Description/Comments

## Project

Sheldon House

## Site

Sheldon House, Cromwell Road, Teddington, TW11 9EJ

## Classified by

Name: **Simon Pike**  
 Date: **03 Aug 2022 09:35 GMT**  
 Telephone: **01638 663 226**

Company: **AGB Environmental Ltd**  
**341 Exning Road**  
**Newmarket**  
**CB8 0AT**

HazWasteOnline™ provides a two day, hazardous waste classification course that covers the use of the software and both basic and advanced waste classification techniques. Certification has to be renewed every 3 years.

## HazWasteOnline™ Certification:

Course	Date
Hazardous Waste Classification	17 Sep 2015
3 year Refresher overdue	-

## Job summary

#	Sample name	Depth [m]	Classification Result	Hazard properties	Page
1	WS01	0.30	Non Hazardous		2
2	WS02	1.00	Non Hazardous		4
3	WS03	0.30	Non Hazardous		7
4	WS04	0.50	Non Hazardous		10
5	TP01	0.20	Non Hazardous		12
6	CP01	0.30	Non Hazardous		14

## Related documents

#	Name	Description
1	Example waste stream template for contaminated soils	waste stream template used to create this Job

## Report

Created by: Simon Pike

Created date: 03 Aug 2022 09:35 GMT

## Appendices

Appendix	Page
Appendix A: Classifier defined and non GB MCL determinands	16
Appendix B: Rationale for selection of metal species	17
Appendix C: Version	17

Classification of sample: WS01

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

Sample details

Sample name:	WS01	LoW Code:	
Sample Depth:	0.30 m	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Moisture content:	4.6% (no correction)	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)

Hazard properties

None identified

Determinands

Moisture content: 4.6% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				13 mg/kg	1.32	17.164 mg/kg	0.00172 %		
	033-003-00-0	215-481-4	1327-53-3							
2	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0							
3	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				14 mg/kg	1.462	20.462 mg/kg	0.00205 %		
		215-160-9	1308-38-9							
4	chromium in chromium(VI) compounds { chromium(VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex }				<2 mg/kg	2.27	<4.54 mg/kg	<0.000454 %		<LOD
	024-017-00-8									
5	copper { dicopper oxide; copper (I) oxide }				18 mg/kg	1.126	20.266 mg/kg	0.00203 %		
	029-002-00-X	215-270-7	1317-39-1							
6	lead { lead chromate }			1	77 mg/kg	1.56	120.106 mg/kg	0.0077 %		
	082-004-00-2	231-846-0	7758-97-6							
7	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
8	nickel { nickel chromate }				14 mg/kg	2.976	41.668 mg/kg	0.00417 %		
	028-035-00-7	238-766-5	14721-18-7							
9	selenium { nickel selenate }				<3 mg/kg	2.554	<7.662 mg/kg	<0.000766 %		<LOD
	028-031-00-5	239-125-2	15060-62-5							
10	zinc { zinc sulphate }				40 mg/kg	2.469	98.772 mg/kg	0.00988 %		
	030-006-00-9	231-793-3 [1] 231-793-3 [2]	7446-19-7 [1] 7733-02-0 [2]							
11	TPH (C6 to C40) petroleum group				<42 mg/kg		<42 mg/kg	<0.0042 %		<LOD
			TPH							
12	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4							
13	benzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2							
14	toluene				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3							
15	ethylbenzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4							

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
16	xylene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-022-00-9	202-422-2 [1]	95-47-6 [1]							
		203-396-5 [2]	106-42-3 [2]							
		203-576-3 [3]	108-38-3 [3]							
		215-535-7 [4]	1330-20-7 [4]							
17	pH				8.4 pH		8.4 pH	8.4 pH		
			PH							
18	naphthalene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3							
19	acenaphthylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8							
20	acenaphthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9							
21	fluorene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7							
22	phenanthrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8							
23	anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7							
24	fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-912-4	206-44-0							
25	pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-927-3	129-00-0							
26	benzo[a]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-033-00-9	200-280-6	56-55-3							
27	chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9							
28	benzo[b]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-034-00-4	205-911-9	205-99-2							
29	benzo[k]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9							
30	benzo[a]pyrene; benzo[def]chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-032-00-3	200-028-5	50-32-8							
31	indeno[123-cd]pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-893-2	193-39-5							
32	dibenz[a,h]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3							
33	benzo[ghi]perylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-883-8	191-24-2							
Total:								0.0349 %		

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- ND** Not detected
- CLP: Note 1 Only the metal concentration has been used for classification



Classification of sample: WS02

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

Sample details

Sample name:	LoW Code:
<b>WS02</b>	Chapter: 17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry: 17 05 04 (Soil and stones other than those mentioned in 17 05 03)
<b>1.00 m</b>	
Moisture content:	
<b>5.5%</b>	
(no correction)	

Hazard properties

None identified

Determinands

Moisture content: 5.5% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number									
1	arsenic { arsenic trioxide }				12	mg/kg	1.32	15.844	mg/kg	0.00158 %		
	033-003-00-0	215-481-4	1327-53-3									
2	cadmium { cadmium oxide }				0.3	mg/kg	1.142	0.343	mg/kg	0.0000343 %		
	048-002-00-0	215-146-2	1306-19-0									
3	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				13	mg/kg	1.462	19	mg/kg	0.0019 %		
		215-160-9	1308-38-9									
4	chromium in chromium(VI) compounds { chromium (VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex }				<2	mg/kg	2.27	<4.54	mg/kg	<0.000454 %		<LOD
	024-017-00-8											
5	copper { dicopper oxide; copper (I) oxide }				23	mg/kg	1.126	25.895	mg/kg	0.00259 %		
	029-002-00-X	215-270-7	1317-39-1									
6	lead { lead chromate }			1	137	mg/kg	1.56	213.695	mg/kg	0.0137 %		
	082-004-00-2	231-846-0	7758-97-6									
7	mercury { mercury dichloride }				<1	mg/kg	1.353	<1.353	mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7									
8	nickel { nickel chromate }				11	mg/kg	2.976	32.739	mg/kg	0.00327 %		
	028-035-00-7	238-766-5	14721-18-7									
9	selenium { nickel selenate }				<3	mg/kg	2.554	<7.662	mg/kg	<0.000766 %		<LOD
	028-031-00-5	239-125-2	15060-62-5									
10	zinc { zinc sulphate }				70	mg/kg	2.469	172.851	mg/kg	0.0173 %		
	030-006-00-9	231-793-3 [1] 231-793-3 [2]	7446-19-7 [1] 7733-02-0 [2]									
11	TPH (C6 to C40) petroleum group				171	mg/kg		171	mg/kg	0.0171 %		
			TPH									
12	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
13	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
14	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
15	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
16	xylene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-022-00-9	202-422-2 [1]	95-47-6 [1]							
		203-396-5 [2]	106-42-3 [2]							
		203-576-3 [3]	108-38-3 [3]							
		215-535-7 [4]	1330-20-7 [4]							
17	pH				7.9 pH		7.9 pH	7.9 pH		
			PH							
18	naphthalene				0.12 mg/kg		0.12 mg/kg	0.000012 %		
	601-052-00-2	202-049-5	91-20-3							
19	acenaphthylene				1.15 mg/kg		1.15 mg/kg	0.000115 %		
		205-917-1	208-96-8							
20	acenaphthene				0.35 mg/kg		0.35 mg/kg	0.000035 %		
		201-469-6	83-32-9							
21	fluorene				1.65 mg/kg		1.65 mg/kg	0.000165 %		
		201-695-5	86-73-7							
22	phenanthrene				18 mg/kg		18 mg/kg	0.0018 %		
		201-581-5	85-01-8							
23	anthracene				4.44 mg/kg		4.44 mg/kg	0.000444 %		
		204-371-1	120-12-7							
24	fluoranthene				28.7 mg/kg		28.7 mg/kg	0.00287 %		
		205-912-4	206-44-0							
25	pyrene				25.1 mg/kg		25.1 mg/kg	0.00251 %		
		204-927-3	129-00-0							
26	benzo[a]anthracene				13.3 mg/kg		13.3 mg/kg	0.00133 %		
	601-033-00-9	200-280-6	56-55-3							
27	chrysene				11 mg/kg		11 mg/kg	0.0011 %		
	601-048-00-0	205-923-4	218-01-9							
28	benzo[b]fluoranthene				11.5 mg/kg		11.5 mg/kg	0.00115 %		
	601-034-00-4	205-911-9	205-99-2							
29	benzo[k]fluoranthene				4.24 mg/kg		4.24 mg/kg	0.000424 %		
	601-036-00-5	205-916-6	207-08-9							
30	benzo[a]pyrene; benzo[def]chrysene				12.6 mg/kg		12.6 mg/kg	0.00126 %		
	601-032-00-3	200-028-5	50-32-8							
31	indeno[123-cd]pyrene				7.38 mg/kg		7.38 mg/kg	0.000738 %		
		205-893-2	193-39-5							
32	dibenz[a,h]anthracene				2.07 mg/kg		2.07 mg/kg	0.000207 %		
	601-041-00-2	200-181-8	53-70-3							
33	benzo[ghi]perylene				6.37 mg/kg		6.37 mg/kg	0.000637 %		
		205-883-8	191-24-2							
Total:								0.0752 %		

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- ND** Not detected
- CLP: Note 1 Only the metal concentration has been used for classification

Supplementary Hazardous Property Information

**HP 3(i): Flammable** "flammable liquid waste: liquid waste having a flash point below 60°C or waste gas oil, diesel and light heating oils having a flash point > 55°C and <= 75°C"

Force this Hazardous property to non hazardous because Soil matrix no free phase product

Hazard Statements hit:

**Flam. Liq. 3; H226** "Flammable liquid and vapour."



---

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 0.0171%)

Classification of sample: WS03

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

Sample details

Sample name:	LoW Code:	
<b>WS03</b>	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
<b>0.30 m</b>		
Moisture content:		
<b>6.4%</b> (no correction)		

Hazard properties

None identified

Determinands

Moisture content: 6.4% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number									
1	arsenic { arsenic trioxide }				26	mg/kg	1.32	34.328	mg/kg	0.00343 %		
	033-003-00-0	215-481-4	1327-53-3									
2	cadmium { cadmium oxide }				0.5	mg/kg	1.142	0.571	mg/kg	0.0000571 %		
	048-002-00-0	215-146-2	1306-19-0									
3	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				14	mg/kg	1.462	20.462	mg/kg	0.00205 %		
		215-160-9	1308-38-9									
4	chromium in chromium(VI) compounds { chromium (VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex }				<2	mg/kg	2.27	<4.54	mg/kg	<0.000454 %		<LOD
	024-017-00-8											
5	copper { dicopper oxide; copper (I) oxide }				63	mg/kg	1.126	70.931	mg/kg	0.00709 %		
	029-002-00-X	215-270-7	1317-39-1									
6	lead { lead chromate }			1	635	mg/kg	1.56	990.483	mg/kg	0.0635 %		
	082-004-00-2	231-846-0	7758-97-6									
7	mercury { mercury dichloride }				<1	mg/kg	1.353	<1.353	mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7									
8	nickel { nickel chromate }				16	mg/kg	2.976	47.62	mg/kg	0.00476 %		
	028-035-00-7	238-766-5	14721-18-7									
9	selenium { nickel selenate }				<3	mg/kg	2.554	<7.662	mg/kg	<0.000766 %		<LOD
	028-031-00-5	239-125-2	15060-62-5									
10	zinc { zinc sulphate }				589	mg/kg	2.469	1454.416	mg/kg	0.145 %		
	030-006-00-9	231-793-3 [1] 231-793-3 [2]	7446-19-7 [1] 7733-02-0 [2]									
11	TPH (C6 to C40) petroleum group				42	mg/kg		42	mg/kg	0.0042 %		
			TPH									
12	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4									
13	benzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2									
14	toluene				<5	mg/kg		<5	mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3									
15	ethylbenzene				<2	mg/kg		<2	mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4									

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
16	xylene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-022-00-9	202-422-2 [1]	95-47-6 [1]							
		203-396-5 [2]	106-42-3 [2]							
		203-576-3 [3]	108-38-3 [3]							
		215-535-7 [4]	1330-20-7 [4]							
17	pH				6.7 pH		6.7 pH	6.7 pH		
			PH							
18	naphthalene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3							
19	acenaphthylene				0.2 mg/kg		0.2 mg/kg	0.00002 %		
		205-917-1	208-96-8							
20	acenaphthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9							
21	fluorene				0.12 mg/kg		0.12 mg/kg	0.000012 %		
		201-695-5	86-73-7							
22	phenanthrene				2.39 mg/kg		2.39 mg/kg	0.000239 %		
		201-581-5	85-01-8							
23	anthracene				0.48 mg/kg		0.48 mg/kg	0.000048 %		
		204-371-1	120-12-7							
24	fluoranthene				6.38 mg/kg		6.38 mg/kg	0.000638 %		
		205-912-4	206-44-0							
25	pyrene				6.04 mg/kg		6.04 mg/kg	0.000604 %		
		204-927-3	129-00-0							
26	benzo[a]anthracene				3.63 mg/kg		3.63 mg/kg	0.000363 %		
	601-033-00-9	200-280-6	56-55-3							
27	chrysene				2.37 mg/kg		2.37 mg/kg	0.000237 %		
	601-048-00-0	205-923-4	218-01-9							
28	benzo[b]fluoranthene				3.28 mg/kg		3.28 mg/kg	0.000328 %		
	601-034-00-4	205-911-9	205-99-2							
29	benzo[k]fluoranthene				1.1 mg/kg		1.1 mg/kg	0.00011 %		
	601-036-00-5	205-916-6	207-08-9							
30	benzo[a]pyrene; benzo[def]chrysene				3.3 mg/kg		3.3 mg/kg	0.00033 %		
	601-032-00-3	200-028-5	50-32-8							
31	indeno[123-cd]pyrene				2 mg/kg		2 mg/kg	0.0002 %		
		205-893-2	193-39-5							
32	dibenz[a,h]anthracene				0.44 mg/kg		0.44 mg/kg	0.000044 %		
	601-041-00-2	200-181-8	53-70-3							
33	benzo[ghi]perylene				1.71 mg/kg		1.71 mg/kg	0.000171 %		
		205-883-8	191-24-2							
Total:								0.237 %		

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- ND** Not detected
- CLP: Note 1 Only the metal concentration has been used for classification

Supplementary Hazardous Property Information

**HP 3(i): Flammable** "flammable liquid waste: liquid waste having a flash point below 60°C or waste gas oil, diesel and light heating oils having a flash point > 55°C and <= 75°C"

Force this Hazardous property to non hazardous because Soil matrix no free phase product

Hazard Statements hit:

**Flam. Liq. 3; H226** "Flammable liquid and vapour."

---

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 0.0042%)

Classification of sample: WS04

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

Sample details

Sample name:	LoW Code:
<b>WS04</b>	Chapter: 17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry: 17 05 04 (Soil and stones other than those mentioned in 17 05 03)
<b>0.50 m</b>	
Moisture content:	
<b>4.9%</b>	
(no correction)	

Hazard properties

None identified

Determinands

Moisture content: 4.9% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				9 mg/kg	1.32	11.883 mg/kg	0.00119 %		
	033-003-00-0	215-481-4	1327-53-3							
2	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0							
3	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				15 mg/kg	1.462	21.923 mg/kg	0.00219 %		
		215-160-9	1308-38-9							
4	chromium in chromium(VI) compounds { chromium(VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex }				<2 mg/kg	2.27	<4.54 mg/kg	<0.000454 %		<LOD
	024-017-00-8									
5	copper { dicopper oxide; copper (I) oxide }				7 mg/kg	1.126	7.881 mg/kg	0.000788 %		
	029-002-00-X	215-270-7	1317-39-1							
6	lead { lead chromate }			1	16 mg/kg	1.56	24.957 mg/kg	0.0016 %		
	082-004-00-2	231-846-0	7758-97-6							
7	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
8	nickel { nickel chromate }				11 mg/kg	2.976	32.739 mg/kg	0.00327 %		
	028-035-00-7	238-766-5	14721-18-7							
9	selenium { nickel selenate }				<3 mg/kg	2.554	<7.662 mg/kg	<0.000766 %		<LOD
	028-031-00-5	239-125-2	15060-62-5							
10	zinc { zinc sulphate }				40 mg/kg	2.469	98.772 mg/kg	0.00988 %		
	030-006-00-9	231-793-3 [1] 231-793-3 [2]	7446-19-7 [1] 7733-02-0 [2]							
11	TPH (C6 to C40) petroleum group				<42 mg/kg		<42 mg/kg	<0.0042 %		<LOD
			TPH							
12	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4							
13	benzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2							
14	toluene				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3							
15	ethylbenzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4							

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
16	xylene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-022-00-9	202-422-2 [1]	95-47-6 [1]							
		203-396-5 [2]	106-42-3 [2]							
		203-576-3 [3]	108-38-3 [3]							
	215-535-7 [4]	1330-20-7 [4]								
17	pH				7.6 pH		7.6 pH	7.6 pH		
			PH							
18	naphthalene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3							
19	acenaphthylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8							
20	acenaphthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9							
21	fluorene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7							
22	phenanthrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8							
23	anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7							
24	fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-912-4	206-44-0							
25	pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-927-3	129-00-0							
26	benzo[a]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-033-00-9	200-280-6	56-55-3							
27	chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9							
28	benzo[b]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-034-00-4	205-911-9	205-99-2							
29	benzo[k]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9							
30	benzo[a]pyrene; benzo[def]chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-032-00-3	200-028-5	50-32-8							
31	indeno[123-cd]pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-893-2	193-39-5							
32	dibenz[a,h]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3							
33	benzo[ghi]perylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-883-8	191-24-2							
Total:								0.0263 %		

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- ND** Not detected
- CLP: Note 1 Only the metal concentration has been used for classification



**Classification of sample: TP01**

**Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

**Sample details**

Sample name:	LoW Code:
<b>TP01</b>	Chapter: 17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry: 17 05 04 (Soil and stones other than those mentioned in 17 05 03)
<b>0.20 m</b>	
Moisture content:	
<b>4.9%</b>	
(no correction)	

**Hazard properties**

None identified

**Determinands**

Moisture content: 4.9% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				11 mg/kg	1.32	14.524 mg/kg	0.00145 %		
	033-003-00-0	215-481-4	1327-53-3							
2	cadmium { cadmium oxide }				0.2 mg/kg	1.142	0.228 mg/kg	0.0000228 %		
	048-002-00-0	215-146-2	1306-19-0							
3	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				16 mg/kg	1.462	23.385 mg/kg	0.00234 %		
		215-160-9	1308-38-9							
4	chromium in chromium(VI) compounds { chromium(VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex }				<2 mg/kg	2.27	<4.54 mg/kg	<0.000454 %		<LOD
	024-017-00-8									
5	copper { dicopper oxide; copper (I) oxide }				25 mg/kg	1.126	28.147 mg/kg	0.00281 %		
	029-002-00-X	215-270-7	1317-39-1							
6	lead { lead chromate }			1	214 mg/kg	1.56	333.8 mg/kg	0.0214 %		
	082-004-00-2	231-846-0	7758-97-6							
7	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
8	nickel { nickel chromate }				12 mg/kg	2.976	35.715 mg/kg	0.00357 %		
	028-035-00-7	238-766-5	14721-18-7							
9	selenium { nickel selenate }				<3 mg/kg	2.554	<7.662 mg/kg	<0.000766 %		<LOD
	028-031-00-5	239-125-2	15060-62-5							
10	zinc { zinc sulphate }				106 mg/kg	2.469	261.745 mg/kg	0.0262 %		
	030-006-00-9	231-793-3 [1] 231-793-3 [2]	7446-19-7 [1] 7733-02-0 [2]							
11	TPH (C6 to C40) petroleum group				<42 mg/kg		<42 mg/kg	<0.0042 %		<LOD
			TPH							
12	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4							
13	benzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2							
14	toluene				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3							
15	ethylbenzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4							

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
16	xylene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-022-00-9	202-422-2 [1]	95-47-6 [1]							
		203-396-5 [2]	106-42-3 [2]							
		203-576-3 [3]	108-38-3 [3]							
		215-535-7 [4]	1330-20-7 [4]							
17	pH				8 pH		8 pH	8pH		
			PH							
18	naphthalene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3							
19	acenaphthylene				0.11 mg/kg		0.11 mg/kg	0.000011 %		
		205-917-1	208-96-8							
20	acenaphthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9							
21	fluorene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7							
22	phenanthrene				1.25 mg/kg		1.25 mg/kg	0.000125 %		
		201-581-5	85-01-8							
23	anthracene				0.26 mg/kg		0.26 mg/kg	0.000026 %		
		204-371-1	120-12-7							
24	fluoranthene				3.23 mg/kg		3.23 mg/kg	0.000323 %		
		205-912-4	206-44-0							
25	pyrene				2.86 mg/kg		2.86 mg/kg	0.000286 %		
		204-927-3	129-00-0							
26	benzo[a]anthracene				1.67 mg/kg		1.67 mg/kg	0.000167 %		
	601-033-00-9	200-280-6	56-55-3							
27	chrysene				1.37 mg/kg		1.37 mg/kg	0.000137 %		
	601-048-00-0	205-923-4	218-01-9							
28	benzo[b]fluoranthene				1.7 mg/kg		1.7 mg/kg	0.00017 %		
	601-034-00-4	205-911-9	205-99-2							
29	benzo[k]fluoranthene				0.52 mg/kg		0.52 mg/kg	0.000052 %		
	601-036-00-5	205-916-6	207-08-9							
30	benzo[a]pyrene; benzo[def]chrysene				1.6 mg/kg		1.6 mg/kg	0.00016 %		
	601-032-00-3	200-028-5	50-32-8							
31	indeno[123-cd]pyrene				1.04 mg/kg		1.04 mg/kg	0.000104 %		
		205-893-2	193-39-5							
32	dibenz[a,h]anthracene				0.28 mg/kg		0.28 mg/kg	0.000028 %		
	601-041-00-2	200-181-8	53-70-3							
33	benzo[ghi]perylene				0.93 mg/kg		0.93 mg/kg	0.000093 %		
		205-883-8	191-24-2							
Total:								0.0666 %		

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- ND** Not detected
- CLP: Note 1 Only the metal concentration has been used for classification

Classification of sample: CP01

✔ **Non Hazardous Waste**  
Classified as **17 05 04**  
in the List of Waste

Sample details

Sample name:	LoW Code:
<b>CP01</b>	Chapter: 17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry: 17 05 04 (Soil and stones other than those mentioned in 17 05 03)
<b>0.30 m</b>	
Moisture content:	
<b>8.9%</b>	
(no correction)	

Hazard properties

None identified

Determinands

Moisture content: 8.9% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				11 mg/kg	1.32	14.524 mg/kg	0.00145 %		
	033-003-00-0	215-481-4	1327-53-3							
2	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg	<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0							
3	chromium in chromium(III) compounds { chromium(III) oxide (worst case) }				19 mg/kg	1.462	27.77 mg/kg	0.00278 %		
		215-160-9	1308-38-9							
4	chromium in chromium(VI) compounds { chromium(VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex }				<2 mg/kg	2.27	<4.54 mg/kg	<0.000454 %		<LOD
	024-017-00-8									
5	copper { dicopper oxide; copper (I) oxide }				36 mg/kg	1.126	40.532 mg/kg	0.00405 %		
	029-002-00-X	215-270-7	1317-39-1							
6	lead { lead chromate }			1	241 mg/kg	1.56	375.915 mg/kg	0.0241 %		
	082-004-00-2	231-846-0	7758-97-6							
7	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg	<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
8	nickel { nickel chromate }				13 mg/kg	2.976	38.691 mg/kg	0.00387 %		
	028-035-00-7	238-766-5	14721-18-7							
9	selenium { nickel selenate }				<3 mg/kg	2.554	<7.662 mg/kg	<0.000766 %		<LOD
	028-031-00-5	239-125-2	15060-62-5							
10	zinc { zinc sulphate }				121 mg/kg	2.469	298.785 mg/kg	0.0299 %		
	030-006-00-9	231-793-3 [1] 231-793-3 [2]	7446-19-7 [1] 7733-02-0 [2]							
11	TPH (C6 to C40) petroleum group				<42 mg/kg		<42 mg/kg	<0.0042 %		<LOD
			TPH							
12	tert-butyl methyl ether; MTBE; 2-methoxy-2-methylpropane				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	603-181-00-X	216-653-1	1634-04-4							
13	benzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-020-00-8	200-753-7	71-43-2							
14	toluene				<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
	601-021-00-3	203-625-9	108-88-3							
15	ethylbenzene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-023-00-4	202-849-4	100-41-4							

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
16	xylene				<2 mg/kg		<2 mg/kg	<0.0002 %		<LOD
	601-022-00-9	202-422-2 [1]	95-47-6 [1]							
		203-396-5 [2]	106-42-3 [2]							
		203-576-3 [3]	108-38-3 [3]							
		215-535-7 [4]	1330-20-7 [4]							
17	pH				9.7 pH		9.7 pH	9.7 pH		
			PH							
18	naphthalene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3							
19	acenaphthylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8							
20	acenaphthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9							
21	fluorene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7							
22	phenanthrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8							
23	anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7							
24	fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-912-4	206-44-0							
25	pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-927-3	129-00-0							
26	benzo[a]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-033-00-9	200-280-6	56-55-3							
27	chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9							
28	benzo[b]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-034-00-4	205-911-9	205-99-2							
29	benzo[k]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9							
30	benzo[a]pyrene; benzo[def]chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-032-00-3	200-028-5	50-32-8							
31	indeno[123-cd]pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-893-2	193-39-5							
32	dibenz[a,h]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3							
33	benzo[ghi]perylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-883-8	191-24-2							
Total:								0.0735 %		

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- ND** Not detected
- CLP: Note 1 Only the metal concentration has been used for classification

## Appendix A: Classifier defined and non GB MCL determinands

- **chromium(III) oxide (worst case)** (EC Number: 215-160-9, CAS Number: 1308-38-9)

Description/Comments: Data from C&L Inventory Database  
Data source: <https://echa.europa.eu/information-on-chemicals/cl-inventory-database/-/discli/details/33806>  
Data source date: 17 Jul 2015  
Hazard Statements: Acute Tox. 4; H332, Acute Tox. 4; H302, Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315, Resp. Sens. 1; H334, Skin Sens. 1; H317, Repr. 1B; H360FD, Aquatic Acute 1; H400, Aquatic Chronic 1; H410

- **TPH (C6 to C40) petroleum group** (CAS Number: TPH)

Description/Comments: Hazard statements taken from WM3 1st Edition 2015; Risk phrases: WM2 3rd Edition 2013  
Data source: WM3 1st Edition 2015  
Data source date: 25 May 2015  
Hazard Statements: Flam. Liq. 3; H226, Asp. Tox. 1; H304, STOT RE 2; H373, Muta. 1B; H340, Carc. 1B; H350, Repr. 2; H361d, Aquatic Chronic 2; H411

- **ethylbenzene** (EC Number: 202-849-4, CAS Number: 100-41-4)

GB MCL index number: 601-023-00-4  
Description/Comments:  
Additional Hazard Statement(s): Carc. 2; H351  
Reason for additional Hazards Statement(s):  
20 Nov 2021 - Carc. 2; H351 hazard statement sourced from: IARC Group 2B (77) 2000

- **pH** (CAS Number: PH)

Description/Comments: Appendix C4  
Data source: WM3 1st Edition 2015  
Data source date: 25 May 2015  
Hazard Statements: None.

- **acenaphthylene** (EC Number: 205-917-1, CAS Number: 208-96-8)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 17 Jul 2015  
Hazard Statements: Acute Tox. 4; H302, Acute Tox. 1; H330, Acute Tox. 1; H310, Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315

- **acenaphthene** (EC Number: 201-469-6, CAS Number: 83-32-9)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 17 Jul 2015  
Hazard Statements: Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315, Aquatic Acute 1; H400, Aquatic Chronic 1; H410, Aquatic Chronic 2; H411

- **fluorene** (EC Number: 201-695-5, CAS Number: 86-73-7)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 06 Aug 2015  
Hazard Statements: Aquatic Acute 1; H400, Aquatic Chronic 1; H410

- **phenanthrene** (EC Number: 201-581-5, CAS Number: 85-01-8)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 06 Aug 2015  
Hazard Statements: Acute Tox. 4; H302, Eye Irrit. 2; H319, STOT SE 3; H335, Carc. 2; H351, Skin Sens. 1; H317, Aquatic Acute 1; H400, Aquatic Chronic 1; H410, Skin Irrit. 2; H315

- **anthracene** (EC Number: 204-371-1, CAS Number: 120-12-7)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 17 Jul 2015  
Hazard Statements: Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315, Skin Sens. 1; H317, Aquatic Acute 1; H400, Aquatic Chronic 1; H410

- **fluoranthene** (EC Number: 205-912-4, CAS Number: 206-44-0)

Description/Comments: Data from C&L Inventory Database  
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>  
Data source date: 21 Aug 2015  
Hazard Statements: Acute Tox. 4; H302, Aquatic Acute 1; H400, Aquatic Chronic 1; H410

▫ **pyrene** (EC Number: 204-927-3, CAS Number: 129-00-0)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 2014

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 21 Aug 2015

Hazard Statements: Skin Irrit. 2; H315 , Eye Irrit. 2; H319 , STOT SE 3; H335 , Aquatic Acute 1; H400 , Aquatic Chronic 1; H410

▫ **indeno[123-cd]pyrene** (EC Number: 205-893-2, CAS Number: 193-39-5)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 06 Aug 2015

Hazard Statements: Carc. 2; H351

▫ **benzo[ghi]perylene** (EC Number: 205-883-8, CAS Number: 191-24-2)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 28/02/2015

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 23 Jul 2015

Hazard Statements: Aquatic Acute 1; H400 , Aquatic Chronic 1; H410

## Appendix B: Rationale for selection of metal species

### arsenic {arsenic trioxide}

Reasonable case CLP species based on hazard statements/molecular weight and most common (stable) oxide of arsenic. Industrial sources include: smelting; main precursor to other arsenic compounds (edit as required)

### cadmium {cadmium oxide}

Reasonable case CLP species based on hazard statements/molecular weight, very low solubility in water. Industrial sources include: electroplating baths, electrodes for storage batteries, catalysts, ceramic glazes, phosphors, pigments and nematocides. (edit as required) Worst case compounds in CLP: cadmium sulphate, chloride, fluoride & iodide not expected as either very soluble and/or compound's industrial usage not related to site history (edit as required)

### chromium in chromium(III) compounds {chromium(III) oxide (worst case)}

Reasonable case species based on hazard statements/molecular weight. Industrial sources include: tanning, pigment in paint, inks and glass (edit as required)

### chromium in chromium(VI) compounds {chromium (VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex}

Worst case species based on hazard statements/molecular weight (edit as required)

### copper {dicopper oxide; copper (I) oxide}

Reasonable case CLP species based on hazard statements/molecular weight and insolubility in water. Industrial sources include: oxidised copper metal, brake pads, pigments, antifouling paints, fungicide. (edit as required) Worst case copper sulphate is very soluble and likely to have been leached away if ever present and/or not enough soluble sulphate detected. (edit as required)

### lead {lead chromate}

Worst case CLP species based on hazard statements/molecular weight (edit as required)

### mercury {mercury dichloride}

Worst case CLP species based on hazard statements/molecular weight (edit as required)

### nickel {nickel chromate}

Worst case CLP species based on hazard statements/molecular weight (edit as required)

### selenium {nickel selenate}

Worst case CLP species based on hazard statements/molecular weight (edit as required)

### zinc {zinc sulphate}

Insufficient chromium for Zinc Chromate

## Appendix C: Version

HazWasteOnline Classification Engine: WM3 1st Edition v1.2.GB - Oct 2021

HazWasteOnline Classification Engine Version: 2022.192.5237.9831 (11 Jul 2022)

HazWasteOnline Database: 2022.192.5237.9831 (11 Jul 2022)

This classification utilises the following guidance and legislation:

**WM3 v1.2.GB - Waste Classification** - 1st Edition v1.2.GB - Oct 2021

**CLP Regulation** - Regulation 1272/2008/EC of 16 December 2008

**1st ATP** - Regulation 790/2009/EC of 10 August 2009

**2nd ATP** - Regulation 286/2011/EC of 10 March 2011

**3rd ATP** - Regulation 618/2012/EU of 10 July 2012

**4th ATP** - Regulation 487/2013/EU of 8 May 2013

**Correction to 1st ATP** - Regulation 758/2013/EU of 7 August 2013

**5th ATP** - Regulation 944/2013/EU of 2 October 2013

**6th ATP** - Regulation 605/2014/EU of 5 June 2014

**WFD Annex III replacement** - Regulation 1357/2014/EU of 18 December 2014

**Revised List of Waste 2014** - Decision 2014/955/EU of 18 December 2014

**7th ATP** - Regulation 2015/1221/EU of 24 July 2015

**8th ATP** - Regulation (EU) 2016/918 of 19 May 2016

**9th ATP** - Regulation (EU) 2016/1179 of 19 July 2016

**10th ATP** - Regulation (EU) 2017/776 of 4 May 2017

**HP14 amendment** - Regulation (EU) 2017/997 of 8 June 2017

**13th ATP** - Regulation (EU) 2018/1480 of 4 October 2018

**14th ATP** - Regulation (EU) 2020/217 of 4 October 2019

**15th ATP** - Regulation (EU) 2020/1182 of 19 May 2020

**The Chemicals (Health and Safety) and Genetically Modified Organisms (Contained Use)(Amendment etc.) (EU Exit)**

**Regulations 2020** - UK: 2020 No. 1567 of 16th December 2020

**The Waste and Environmental Permitting etc. (Legislative Functions and Amendment etc.) (EU Exit) Regulations 2020** - UK:

2020 No. 1540 of 16th December 2020

**GB MCL List** - version 1.1 of 09 June 2021

# Appendix 5      CSM Risk Evaluation Methodology

---



**Classification of Consequence**

The classifications of consequence (severity) are taken from R&D Publication 66 (NHBC and Environment Agency, 2008). agb Environmental has chosen to apply the classifications to a broad range of development scenarios.

It should be noted that the categories of pollution incident have no relation to the categories of significant possibility of significant harm to human health or significant possibility of significant pollution of controlled waters in respect of the Part 2A Statutory Guidance.

Classification	Definition
Severe	<p>Highly elevated concentrations likely to result in “significant harm” to human health as defined by the EPA 1990, Part 2A, if exposure occurs.</p> <p>Equivalent to EA Category 1 pollution incident including persistent and/or extensive effects on water quality; leading to closure of a potable abstraction point; major impact on amenity value or major damage to agriculture or commerce.</p> <p>Major damage to aquatic or other ecosystems, which is likely to result in a substantial adverse change in its functioning or harm to a species of special interest that endangers the long-term maintenance of the population.</p> <p>Catastrophic damage to crops, buildings or property.</p>
Medium	<p>Elevated concentrations which could result in “significant harm” to human health as defined by the EPA 1990, Part 2A if exposure occurs.</p> <p>Equivalent to EA Category 2 pollution incident including significant effect on water quality; notification required to abstractors; reduction in amenity value or significant damage to agriculture or commerce.</p> <p>Significant damage to aquatic or other ecosystems, which may result in a substantial adverse change in its functioning or harm to a species of special interest that may endanger the long-term maintenance of the population.</p> <p>Significant damage to crops, buildings or property.</p>
Mild	<p>Exposure to human health unlikely to lead to “significant harm”.</p> <p>Equivalent to EA Category 3 pollution incident including minimal or short lived effect on water quality; marginal effect on amenity value, agriculture or commerce.</p> <p>Minor or short lived damage to aquatic or other ecosystems, which is unlikely to result in a substantial adverse change in its functioning or harm to a species of special interest that would endanger the long-term maintenance of the population.</p> <p>Minor damage to crops, buildings or property.</p>
Minor	<p>No measurable effect on humans.</p> <p>Equivalent to insubstantial pollution incident with no observed effect on water quality or ecosystems.</p> <p>Repairable effects of damage to buildings, structure and services.</p>

**Classification of Probability**

The classifications of probability are taken from R&D Publication 66 (NHBC and Environment Agency, 2008). agb Environmental has chosen to apply the classifications to a broad range of development scenarios.

It should be noted that the categories of pollution incident have no relation to the categories of significant possibility of significant harm to human health or significant possibility of significant pollution of controlled waters in respect of the Part 2A Statutory Guidance. Also, in the Part 2A Statutory Guidance “pollutant linkage” is now termed “contaminant linkage”, although it is noted that the terms are effectively synonymous.

Category	Definition
High Likelihood	There is pollutant linkage and an event would appear very likely in the short-term and almost inevitable over the long-term, or there is evidence at the receptor of harm or pollution.
Likely	There is pollutant linkage and all the elements are present and in the right place which means that it is probable that an event will occur. Circumstances are such that an event is not inevitable, but possible in the short-term and likely over the long-term.
Low likelihood	There is pollutant linkage and circumstances are possible under which an event could occur. However, it is by no means certain that even over a long period such an event would take place, and is less likely in the shorter term.
Unlikely	There is pollutant linkage but circumstances are such that it is improbable that an event would occur even in the very long-term.

**Categorisation of Risk**

		Consequence (Severity)			
		Severe	Medium	Mild	Minor
Probability (Likelihood)	High Likelihood	Very high risk	High risk	Moderate risk	Moderate/low risk
	Likely	High risk	Moderate risk	Moderate/low risk	Low risk
	Low Likelihood	Moderate risk	Moderate/low risk	Low risk	Very low risk
	Unlikely	Moderate/low risk	Low risk	Very low risk	Very low risk

**Description of Risk Levels and Likely Action Required**

Term	Description
Very high risk	There is a high probability that severe harm could arise to a designated receptor from an identified hazard at the site without appropriate remediation action <u>or</u> there is evidence that severe harm to a designated receptor is already occurring. Realisation of that risk is likely to present a substantial liability to be site owner or occupier. Investigation is required as a matter of urgency and remediation works likely to follow in the short-term.
High risk	Harm is likely to arise to a designated receptor from an identified hazard at the site without appropriate remediation action. Realisation of the risk is likely to present a substantial liability to the site owner or occupier. Investigation is required as a matter of urgency to clarify the risk. Remediation works may be necessary in the short-term and are likely over the longer term.
Moderate risk	It is possible that without appropriate remediation action, harm would arise to a designated receptor. It is relatively unlikely that any such harm would be severe, and if any harm were to occur it is more likely that the harm would be relatively mild. Further investigative work is normally required to clarify the risk and to determine the potential liability to site owner/occupier. Some remediation works may be required in the longer term.
Low risk	It is possible that harm could arise to a designated receptor from identified hazard. It is likely that, at worst, if any harm was realised any effects would be mild. It is unlikely that the site owner/or occupier would face substantial liabilities from such a risk. Further investigative work (which is likely to be limited) to clarify the risk may be required. Any subsequent remediation works are likely to be relatively limited.
Very low risk	It is a low possibility that harm could arise to a designated receptor, but it is likely at worst, that this harm if realised would normally be mild or minor.

**Summary of Definitions**

<b>Term</b>	<b>Description</b>
Hazard	A property or situation which in certain circumstances could lead to harm. (The properties of different hazards must be assessed in relation to their potential to affect the various different receptors).
Consequences	The adverse effects (or harm) arising from a defined hazard which impairs the quality of the environment or human health in the short or longer term.
Probability	The mathematical expression of the chance of a particular event in a given period of time (e.g. probability of 0.2 is equivalent to 20% or a 1 in 5 chance).
Likelihood	Probability; the state of face of being likely.
Risk	A combination of the probability or frequency of the occurrences of a defined hazard AND the magnitude of the consequences of that occurrence.
Contaminant linkage	An identified pathway is capable of exposing a receptor to a contaminant and that contaminant is capable of harming the receptor. In the Part 2A Statutory Guidance the terms "contaminant", "pollutant" and "substance" have the same meaning, and some non-statutory technical guidance relevant to land contamination uses alternative terms such as "pollutant", "substance" and associated terms in effect to mean the same thing.