

Tree Works Report - 9827

RIVER GROUND

- 28 London plane (*Platanus × hispanica*) Remove south codominant stem.
- 32 Holly (*Ilex aquifolium*) Remove stem growing towards tennis court. Raise crown to give 2.5m clearance.
- 111 Laburnam (*Laburnum anagyroides*) Fell to ground level, remove all arisings.
- 113 Lime (*Tilia x europa*) Crown lift over new trees, cutting right back to suitable growth / pruning points
- 139 Indian Horse Chestnut (*Aesculus indica*) Remove minor subordinate stem to west
- 158 Horse Chestnut (*Aesculus hippocastanum*) Remove east stem. Remove minor stems / establishing epicormic at base

AVENUE GROUND

- 271 Common Lime (*Tilia x europaea*) Raise crown to give 3m clearance.
- 300 Common Lime (*Tilia x europaea*) Reduce away from Paulonia to give 2m clearance.
- 302 London plane (*Platanus × hispanica*) Raise crown on north side to benefit new planting shrubs.

LAKE GROUND

- 424 Holly (*Ilex aquifolium*) Fell to ground level and remove all arisings.
- 433 Black Mulberry (*Morus Nigra*) Re-Pollard back to previous pollard points removing approximately 4m of new growth. Final height 3m and spread 4m. Retain largest stem from low limb and remove all other minor stems.
- 483 Holly (*Ilex aquifolium*) Reduce to main fork at 2.5m to significantly reduce overhang to make
- 486 Wild Cherry (*Prunus avium*) Fell to ground level, remove all arisings and poison stump with EcoPlugs.

- 504 Variagated Holly (*Ilex aquifolium* 'Varigata') Reduce by around 1m to shape and contain.
- 508 London plane (*Platanus × hispanica*) Remove low limb at 5m to west. Remove deadwood - 2 branches at 5 and 8m to west
- 536 Yew (*Taxus baccata*) Prune and reduce to 4M to make hedge
- 628 English Oak (*Quercus robur*) Remove large low limb over lake, at 3.5m to east. Remove self seeded Oak on bank, 2.5m to east of base.
- 648 Ash (*Fraxinus excelsior*) Fell to ground level, remove all arisings and poison stump with EcoPlugs. Fell low understory around base.
- 688 Elm (*Ulmus* spp) Fell to ground level, remove all arisings and poison stump with EcoPlugs. Also fell saplings and suckers within 3m of base (retain middling size Elm 3m north of Oak)
- 709 Holm Oak - Evergreen Oak (*Quercus ilex*) Fell to ground level and remove all arisings.
- 737 Holly (*Ilex aquifolium*) Reduce height to union (elbowed junction) at 4m.
- 860 Elm (*Ulmus* spp) Fell to ground level, remove all arisings and poison stump with EcoPlugs.