

SCHEDULE OF WORKS

1. Existing open roof rafters to be retained and re-used as substrate for the green roof system.
2. 18mm marine ply decking fixed to existing rafters to provide adequate substrate for the green roof system.
3. 100 x 12mm external grade timber fascia board fixed to perimeter of 18mm marine plywood to provide surround structure for the green roof system.
4. Waterproof layer applied within newly formed tray.
5. Premium S-Pod System installed by Sedium Green Roof.