Arborícultural Report



Relating to:

8 Harrey Drive, Hampton TW12 2FB

Tree Survey	✓
Arboricultural Impact Assessment	✓
Arboricultural Method Statement	✓

All to BS5837:2012 - Trees in relation to design, demolition and construction - Recommendations

Produced For:

Gentjan Kapllani

Ref: APA/AP/2024/076

Date: 5th July 2024

Prepared By:

Andrew Pinchin BSc (Hons), Dip Arb (RFS), FArborA

Tel. 01932 450104

www.aparboriculture.co.uk

Contents Section

Ir	troduction	1
-	Overview	1.1
-	Key Issues for Implementation	1.2
-	Contact Details	1.3
-	Key Terms and Abbreviations	1.4
-	The Proposal/Relevant Planning History	1.5
-	Brief and Purpose	1.6
-	Scope	1.7
-	Documents Supplied and Used	1.8
-	Site Details	1.9
T	ree Survey	2
-	Survey Method	2.1
-	Tree Details	2.2
-	Legal Protection Status of Trees	2.3
A	rboricultural Impact Assessment	3
-	Overview of Arboricultural Impact	3.1
-	Tree works	3.2
-	Incursions Within RPAs	3.3
-	Light and Proximity Issues	3.4
-	Mitigation	3.5
-	Conclusion	3.6
A	rboricultural Method Statement	4
-	Introduction	4.1
-	Pre-Commencement Meeting	4.2
-	Sequencing and Inspection/Supervision	4.3
-	General Site Precautions	4.4
-	Carrying out of Tree Works	4.5
-	Tree Protective Fencing and Ground Protection	4.6
-	Site Access and Hard Surfacing	4.7
-	Demolition	4.8
-	Underground Services	4.9
-	Foundations and Construction	4.10
-	Fencing and Landscaping	4.11
_	Amendments	4.12

Appendices

Appendix 1 – Tree Survey Schedule to BS5837:2012

Appendix 2 – Tree Protection Plan - Scale 1:200 at A3

Appendix 3 – BS5837 Categorisation System

BS 5837:2012



Trees in relation to design, demolition and construction – Recommendations

BS5837: 2012 compliant report, supplied electronically as pdf document

This report is for the exclusive use of the client and those involved in the submission and approval of the planning application to which the report relates and the implementation of any consented works. It may not be sold, lent, hired out or divulged to any third party not directly involved in the subject matter without the express consent of APArboriculture

Introduction

1.1 Overview

- The proposal is to erect a single storey rear extension following demolition of the existing conservatory
- A planning application is being submitted to London Borough of Richmond upon Thames for these works
- 6 trees have been surveyed
- 2 trees are to be removed
- 1 tree is to be pruned
- There are no incursions within the RPAs of retained trees
- A pre-commencement meeting is to be convened on site prior to any works commencing

1.2 Key Issues for Implementation

If the proposed development works are implemented, these are the key issues that the project manager/builder will need to be aware of:

- A pre-commencement meeting needs to be convened on site prior to any construction related activity starting (Section 4.2)
- The tree protective fencing and ground protection need to be in place prior to any demolition or construction related activity starting (specifications given in Section 4.6)

4

1.3 Contact Details

Contact	Name	Company/LPA	Tel. / E-mail address	Sent report
Client	Gentjan Kapllani	-	-	✓
Architect/Planning Agent	Elaine Kimber	Fluent Architectural Design Services Ltd	01932 629523 elainekimber@fluent-ads.co.uk	✓
Arboricultural Consultant	Andrew Pinchin	APArboriculture	01932 450104 aparboriculture@gmail.com	
LPA Tree Officer	Craig Ruddick	London Borough of Richmond upon Thames	08456 122 660 craigruddick@richmond.gov.uk	

1.4 Key Terms and Abbreviations

Arboricultural Impact Assessment - An assessment of arboricultural impact	AIA
Arboricultural Method Statement - Contains the tree protection information	AMS
British Standard 5837 2012: Trees in Relation to Design, Demolition and Construction – Recommendations – the relevant British Standard	The BS
Root Protection Area - The volume of soil a tree needs to stay healthy	RPA
Local Planning Authority - The Council	LPA
Tree Preservation Order - A legal document that is used by the LPA to protect trees	TPO

5

1.5 The Proposal/Relevant Planning History

The proposal is to erect a single storey rear extension following demolition of the existing conservatory.

A planning application is being submitted to London Borough of Richmond upon Thames for these works.

1.6 Brief and Purpose

This report has been commissioned by Gentjan Kapllani to;

- Survey the trees in the vicinity of the proposed works in accordance with the BS.
- Assess the arboricultural impact of the proposed project.
- Present an effective tree protection strategy for the duration of the development works.
- Provide the necessary arboricultural information for a planning application to be validated and determined by London Borough of Richmond upon Thames.

1.7 Scope

The trees on the site have been surveyed in accordance with the BS. Trees with a stem diameter over 75mm have been included.

The report is designed to fulfil the recommended criteria for the provision of arboricultural information in relation to the validation of planning applications (ref. Department for Communities and Local Government Circular 02/2008 and the associated guidance document entitled 'Validation of Planning Applications'.)

In addition to providing the necessary arboricultural information to enable the submitted planning application to be validated and determined, the report is intended to be used as a working document for site personnel to inform and guide the tree protection process throughout the development works.

A full hazard assessment of the trees (including the assessment of decay or defects and their implications), has not been undertaken as this is considered beyond the scope of this report. Detailed ecological considerations are also beyond the scope of this report.

1.8 Documents Supplied/Used

Document	Obtained From	Format/Ref
Existing and proposed plans	Fluent Architectural Design Services Ltd	PDF & Dwg

1.9 Site Details

The site in question is within the administrative jurisdiction of London Borough of Richmond upon Thames. It lies in Harvey Drive in Hampton.

In terms of levels, the site is essentially level with no inclines of significance from an arboricultural perspective.

Site Education Flam

Site Location Plan

7

2 Tree Survey

2.1 Survey Method

The trees were surveyed on 1st July 2024.

The locations of the trees were plotted with a laser using triangulation and trilateration techniques.

The trees were inspected from ground level using widely accepted Visual Tree Assessment techniques. No climbing inspections were undertaken. No samples of soil, tree tissue or suspected pests/pathogens were taken.

Heights of the trees were estimated by eye. Crown spreads at each of the four cardinal points were measured using a laser measuring device. The diameters of the trees were measured at a height of 1.5m above ground level (using a diameter tape) as per Annexe C of The BS.

Photographs were taken on site using a digital camera.


2.2 Tree Details


Full details of the surveyed trees and proposed works are given in the Tree Survey Schedule (Appendix 1). The locations of the trees are shown on the Tree Protection Plan (Appendix 2). The trees have been surveyed in accordance with the BS categorisation system, which can be summarised as follows:


- Category A trees of high quality and value with a life expectancy of more than 40 years
- Category B


 trees of moderate quality and value, with a life expectancy of more than 20 years
- Category C trees of low quality and value, with a life expectancy of more than
 10 years
- Category U trees for removal, with a life expectancy of less than 10 years
 - See Appendix 3 for more details on the BS5837 Categorisation System

An overview of the surveyed tree stock is as follows:









APArboriculture


The RPAs of the trees have all been calculated in accordance with Annexe D of the BS and are given in the Tree Survey Schedule.

For single stemmed trees, the RPA radius is derived by multiplying the diameter of the tree at 1.5m above ground level by 12. For multi-stemmed trees, the RPA radius is derived by multiplying an equivalent stem diameter by 12. The formulae for calculating the equivalent stem diameters are as follows:

Equivalent stem diameter calculations for trees with multiple stems:

Trees with 2-5 stems: $\sqrt{\text{(stem diameter 1)}^2 + (\text{stem diameter 2)}^2 ... + (\text{stem diameter 5)}^2}$

Trees with 5+ stems: $\sqrt{\text{(mean stem diameter)}^2 \times \text{number of stems}}$



All stems measured at 1.5m above ground level.

RPA radius derived by multiplying equivalent stem diameter by 12

As for single stemmed trees, shape may under some circumstances be modified (with sound arboricultural justification) as long as total area remains the same

The RPA is the area (given in m²) that contains sufficient rooting volume for a tree to survive and remain healthy. Disturbance within this area has the potential to impact significantly upon tree health and vitality.

Sections 4.6.2 and 4.6.3 of the BS provide for the shape of the RPA to be modified from the starting point of a circle where rooting patterns are likely to be eccentric, subject to the total area remaining the same.

APArboriculture


No RPAs have been modified in this instance and the RPAs of the retained trees are all shown as nominal circles on the Tree Protection Plan at Appendix 2.


2.3 Legal Protection Status of Trees


The legal protection status of the trees has not at the time of writing of this report been formally ascertained (this information is not currently available on the Council's website).

3 Arboricultural Impact Assessment

3.1 Overview of Arboricultural Impact







Number of trees with incursions within RPAs - 0

3.2 Tree Works

2 small Category C Apple trees are to be removed (G2). 1 small Category C tree is to be pruned (T3).

These works will not have significant public amenity implications.

3.3 Incursions within RPAs

Incursions may be fully invasive (where a degree of root disturbance is considered acceptable) or low invasive (where specialist methods are used to limit the degree of disturbance). In this instance, there are no incursions within the RPAs of the retained trees.

3.4 Light and Proximity Issues

Section 5.3 of the BS is concerned with the proximity of structures to trees and recommends that buildings are sited at distances from trees that allow for future growth without significant problems being experienced. Issues referred to include shading of buildings and open spaces, seasonal nuisances (dropping of leaves and fruits etc.) and concerns over safety.

These issues can lead to pressure to heavily prune or remove trees in the future and LPAs will be mindful of this potential pressure when considering whether proposals for development in proximity to trees are acceptable.

The proposed single storey rear extension is considered to be situated at an acceptable distance from the retained trees and no particular problems relating to proximity to trees are anticipated in this instance.

3.5 Mitigation

There are no specific proposals for landscaping/new tree planting in connection with the project at the time of writing of this report. The Council will be able to attach a landscaping condition to any forthcoming planning consent if it is felt that some landscaping/tree planting would be desirable following completion of the development works.

APArboriculture

3.6 Conclusion

In terms of arboricultural impact, 2 small Category C trees are to be removed and 1 small Category C tree is to be pruned.

There are no incursions within the RPAs of retained trees and all of the retained trees are to be afforded an adequate degree of physical protection throughout the development process as detailed in the AMS.

In summary, the proposal is considered supportable from an arboricultural perspective.

4 Arboricultural Method Statement

4.1 Introduction

To safeguard the retained trees on and immediately adjacent to the site during the development process, the tree protection measures set out below will be adhered to. These will protect the rooting systems and aerial parts of the trees.

The essential principle is that the area inside the tree protective fencing and where ground protection has been used is to be protected for the duration of the works.

A copy of this AMS will be maintained on site at all times and made available to all site personnel.

All site personnel will be made aware of the key implications of this AMS. The Arboricultural Consultant can give a 'tool-box talk' to site personnel if required to ensure that the tree protection details are fully understood.

As of 2005, Local Planning Authorities have powers to serve Temporary Stop Notices if agreed tree protection measures are not carried out. Adhering to this AMS will ensure that such costly and time consuming action is avoided.

4.2 Pre-Commencement Meeting

A pre-commencement site meeting, involving the Site Manager, the Arboricultural Consultant and the LPA Tree Officer will be held to ensure that all aspects of the tree protection process are understood and agreed. Any potential problems can be discussed at this stage, along with the exact sequencing of events and the level of arboricultural inspection/supervision required. The Arboricultural Consultant will communicate a record of the meeting to all parties by e-mail.

Matters to be discussed at Pre-Commencement Meeting

- Timing and sequencing of works
- Exact locations and specifications for tree protective fencing & ground protection
- Any other arboricultural issues

It will also be useful for all parties to exchange current contact details at the meeting

4.3 Sequencing and Inspection/Supervision

Sequencing of events and effective arboricultural inspection/supervision are important elements of the tree protection process.

In this instance, as there are no incursions within the RPAs of the retained trees, it is not proposed that any of the works be directly supervised on site.

The appointed arboricultural consultant will, however, maintain telephone contact with the site manager/building company to ensure that compliance with the AMS is being achieved.

The appointed Arboricultural Consultant will make a record of any visits to the site and will communicate details of each visit to the Client and the LPA. This will provide evidence of compliance and ultimately enable the LPA to discharge the tree related planning condition.

Key Stages with suggested sequencing of works:

- AMS issued to Site Manager/Building Company
- AMS read by all site personnel to ensure full understanding of implications. Any queries addressed by appointed Arboricultural Consultant
- Pre-commencement meeting convened
- Tree works carried out (removal of 2 trees and pruning of 1 tree)
- Tree protective fencing erected and ground protection installed as per Tree Protection Plan
- Demolition and construction works carried out
- Tree protective fencing and ground protection removed
- Landscaping works carried out (if any)

Summary of Required Arboricultural Inspection/Supervision:

Activity	Level of monitoring/supervision required
Erection of tree protective fencing and installation of ground protection	Inspection of tree protective fencing and ground protection by appointed arboricultural consultant

4.4 General Site Precautions

The following points will be observed at all times:

- No fires will be lit within 10m of the canopies of retained trees.
- Notice boards, telephone cables or other services will not be attached to any parts of retained trees.
- Site operations will be planned to avoid damage to the aerial parts of trees.
 Particular care will be taken when using piling rigs and plant with booms, jibs and counterweights.
- Materials that contaminate the soil (e.g. concrete mixings, diesel oil, builders' sand and vehicle washings) will not be permitted to enter the RPAs of retained trees.

4.5 Carrying out of Tree Works

All works will be carried out in accordance with BS 3998: 2010 'Recommendations for Tree Work' and to current arboricultural best practice. Tree works will be carried out by a suitably qualified and experienced arboricultural contractor holding the necessary insurance cover.

A list of such contractors is available from the Arboricultural Association at www.trees.org.uk. Lists of reputable local tree contractors are also available on many Local Authority websites. APArboriculture can provide advice on enlisting the services of tree contractors where required.


4.6 Tree Protective Fencing and Ground Protection

Tree protective fencing and ground protection are used to ensure that the RPAs of retained trees are safeguarded.

The required tree protective fencing is shown on the Tree Protection Plan at Appendix 2. The fencing will remain in position for the duration of the development and will only be moved/altered as agreed in writing by the LPA following arboricultural advice.

The tree protective fencing will be 2.0m Heras fencing as specified in the BS. The fencing will be supported by a scaffold framework with supporting struts firmed into the ground on the side of the trees. The purpose of the supports is to prevent the fencing being moved during the development. Clear signs will be attached to the fencing (e.g. Tree Protection Area – Keep Out!).

Tree Protective Fencing Default Specification - BS5837: 2012



Braced Heras Tree Protective Fencing in situ – BS5837: 2012








It may *in some cases* be acceptable (e.g. on smaller sites) for rubber or concrete 'feet' at the base of heras fencing to be pinned to the ground or for short outriggers to attached to the fencing and pinned to the ground in lieu of a full scaffold framework. The exact specification of fencing that will be acceptable in this instance can be discussed at the pre-commencement meeting.

Ground protection has also been specified to protect the RPAs of retained trees as shown on the Tree Protection Plan at Appendix 2. To accord with the BS, the specification for the ground protection will be as follows:

- A geotextile membrane on the ground
- 100-150mm depth of a compressible layer (e.g. woodchips)
- Side butting scaffold boards or plywood on top

Schematic of ground protection & example on site





Nb. The above ground protection specification is suitable for loadings up to 2 metric tonnes (2000kg). For wheeled or tracked construction traffic of over 2 tonnes in weight (gross), more substantial ground protection will be required (e.g. Eve Trakway or a similar proprietary system). In this instance, the above specification is likely to be sufficient.

4.7 Site Access and Hard Surfacing.

No hard surfacing is to be removed or installed within the RPAs of retained trees.

4.8 Demolition

No demolition works are to take place within the RPAs of retained trees.

4.9 Underground Services

It will not be necessary to install any new underground services within the RPAs of retained trees.

4.10 Foundations and Construction

No new foundations are to be installed within the RPAs of retained trees.

4.11 Fencing and Landscaping

During the landscaping phase of the project (if any landscaping works take place), the following precautions will be observed:

- Soil within the RPAs of retained trees (and where new tree planting is proposed)
 will not be compacted. This will preclude the use of heavy plant within RPAs
 unless suitable ground protection is used
- There will be no changes in ground levels within the RPAs of retained trees
- Unwanted vegetation within the RPAs of retained trees will be removed manually or using contact herbicides that will not damage tree roots
- No underground irrigation or drainage pipes will be installed within the RPAs of retained trees

APArboriculture

 Care will be taken when carrying out planting works not to damage the roots of retained trees. All planting pits within RPAs will be dug by hand and hedging will not be trench-planted

If any fence posts are installed within the RPAs of retained trees/hedges, excavation will be carried out using hand tools. Posts will be re-positioned if roots in excess of 25mm in diameter are encountered. Post holes will be lined with heavy gauge polythene where concrete is used to safeguard the rooting systems of the trees from the potentially toxic effects of leaching concrete.

4.12 Amendments

Issues may arise on projects of this nature that require amendments to the previously agreed tree protection details. Any amendments to this AMS will be approved in writing by the LPA prior to being implemented. Copies of paperwork relating to any amendments will be communicated by the Arboricultural Consultant to the Client and LPA.

Appendix 1 Tree Survey Schedule



APArboriculture www.aparboriculture.co.uk



Tree Survey Schedule

Page 1

Tel. 01932 450104

BS5837: 2012 compliant survey by:

Andrew Pinchin

Ref. APA/AP/2024/076

Site: 8 Harvey Drive, Hampton TW12 2FB LPA: London Borough of Richmond upon Thames Date of Survey: 1st July 2024

Tree Ref	Common N	Name	Height	Crown Spread	Crown Height	Age Class	No. of Stems	Stem Diameter	RPA Radius	Vigour	Structural Condition	Landscape Value	BS Cat	Useful Life	Notes & Observations
T1	Hawthorn	1	5	1 1 1 1	2	Υ	1	50	0.6	Normal	Fair	Low	C1	40+	Young recently planted Hawthorn still with stakes & ties; technically sub-BS survey size
Recomm	nended Works: s for Works:	No works N/A	proposed												
G2	Apple 2		3	1 1 1 1	1.5	Y	1	75 m	0.9	Normal	Fair	Low	C1, C2	40+	2 small Prunus trees of modest landscape significance
Recomm	nended Works: s for Works:	Remove To facilitat	e propose	d developm	ent works	;									
Т3	Laburnum	1	6	2 2 2 2	2.5	SM	3	130 e	1.6	Normal	Fair	Low	C1	40+	Off-site tree; triple-stemmed
	rees: 1 nended Works: s for Works:			ouild by up t d developm											
T4	Holly rees: 1		6	3 2 2 3	2	EM	8	320	3.8	Normal	Fair	Low	C1	20+	Multi-stemmed at base; trimmed to a compact shape; of modest quality & landscape significance
	nended Works: s for Works:	No works N/A	proposed												
T5	Cordyline	;	4	1 1 1 1	2.5	SM	1	110 e	1.3	Normal	Fair	Low	C1	20+	Off-site tree; typical of species
No. of tr		Normal		ı											
	nended Works: s for Works:	No works N/A	proposed												

Key to Tree Survey Schedule (*BS5837: 2012*)

Tree Ref. – Consecutive numbering. T = Individual Tree: G = Tree Group: H = Hedge

Species – Common or Latin name for tree

Height – Height of tree in metres

Crown Spread – Radial crown spread in metres at the four cardinal points (N E S W)

Crown Height – Height of lowest parts of crown above ground level in metres

Age Class - Young, Semi-Mature, Early-Mature, Mature, Over-Mature

No. of Stems – Number of stems over 75mm in diameter at 1.5m above ground level

Stem Diameter – Diameter of stem in mm at 1.5m above ground for single stemmed trees. For multi-stemmed trees, equivalent diameter figure calculated as per the BS (e= estimated value; m = mean value)

RPA Radius – The radius of the Root Protection Area of the tree (from the tree centre) in metres

Vigour – An indication of the physiological condition/health of the tree: Normal, Moderate, Poor, Dead

Structural Condition – An assessment of the overall structural condition of the tree: Good, Fair, Poor

Landscape Value – High, Medium, Low


BS Cat – BS5837: 2012 Category. A- High, B- Moderate, C- Low, U-Remove. For full description of categories see Table 1 of BS5837:2012


Useful Life - Estimated remaining contribution to the landscape in years

Notes and Observations – miscellaneous notes where it is considered that these may be useful

(Recommended works and reasons for works also given in Tree Survey Schedule).


Appendix 2 Tree Protection Plan






LPA - London Borough of Richmond upon Thames

Proposal: Erect single storey rear extension following demolition of existing conservatory





















Plan to be printed in colour and to scale

Tree Protection Plan

8 Harvey Drive Hampton **TW12 2FB**

1:200 (A3) 05.07.24

TPP/APA/AP/2024/076

APArboriculture

15 Church Street Weybridge Surrey KT13 8NA


Tel: 01932 450104



aparboriculture@gmail.com

www.aparboriculture.co.uk

Appendix 3 BS5837 Categorisation System



BS5837:2012 Categorisation System (Abbreviated)

Category A	£ 3	Trees of high quality with an estimated remaining life expectancy of at least 40 years. Particularly good specimens (A1); Trees, groups or woodlands of particular landscape significance (A2); Trees, groups or woodlands of significant conservation, historical or commemorative value (A3)
Category B	E CONTRACTOR OF THE PROPERTY O	Trees of moderate quality with an estimated remaining life expectancy of at least 20 years. Trees of slightly lower individual quality (B1); Trees of collective value but of lesser overall landscape significance than Category A trees (B2); Trees with material conservation or cultural value (B3)
Category C		Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150mm. Unremarkable trees of limited merit (C1); Trees, groups or woodlands of low landscape value (C2); Trees with no material conservation or cultural value (C3)
Category U		Trees in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years (dead, declining and diseased trees etc.) It will normally be recommended that these trees be removed (unless they have particular conservation/ecological value)

- Category A, B and C trees should be considered for retention
- Although Category C trees are generally of lower overall quality and landscape significance, they may still constitute a material planning constraint
- Category U trees are usually unsuitable for retention



Tree to be removed (Category U trees and other trees where justification can be presented within context of development works being proposed)

The legal protection status of the trees will also be an important consideration regarding retention or otherwise of trees (see Section 2.3 of report)