



DO NOT SCALE FROM THIS DRAWING

- NOTES
1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE
 2. ALL LEVELS ARE IN METRES AOD UNLESS NOTED OTHERWISE.
 3. FOR PAVEMENT DETAILS REFER TO DRAWING A123043-TGEE-ZZ-XX-DR-C-0021.
 4. PILING SPECIFICATION TO BE ICE SPERW 3rd EDITION WITH NORMAL TOLERANCE.
 5. WORKMANSHIP TO BE IN ACCORDANCE WITH MCHW AND BEST PRACTICE.
 6. ALL STEELWORK TO BE EXC 2 TO BS EN 1090-2 U.N.O.
 7. ALL SHEET PILES TO BE GRADE S270GP OR GREATER TO BS EN 10248-1.
 8. GEOTECHNICAL PROPERTIES BASED ON RAW DATA FROM GI REPORT "GROUND INVESTIGATION INTERPRETIVE REPORT" (WYG, SEPTEMBER 2015).
 9. ALL PAVED AREAS CONSIDERED WITH A 10kPa GENERAL SURCHARGE.



LAYOUT PLAN
SCALE 1:5000



REV.	BY	CHKD	APPD	DATE	DESCRIPTION
C01	JJF	JJF	APM	20/10/23	FOR CONSTRUCTION

CODE	DRAWING STATUS
A5	FOR CONSTRUCTION

Tony Gee and Partners LLP
8th Floor, International House
Dover Place,
Ashford, Kent.
TN23 1HU
Tel: 01233 639787
www.tonygee.com
Consulting Engineers

ON BEHALF OF

LAND & WATER
Innovation. Inspiration. Results.

THAMES YOUNG MARINERS

PROPOSED GENERAL ARRANGEMENT PLAN

WORKING AT HEIGHT	CONTRACTOR TO ENSURE SAFETY MEASURES ARE IN PLACE FOR WORKING AT HEIGHT
WORKING IN/NEAR WATER	CONTRACTOR TO ENSURE SAFE WORKING AND EMERGENCY PROCEDURES ARE IN PLACE FOR WORKING NEAR WATER
RISING WATER LEVELS	CONTRACTOR TO MONITOR WEATHER CONDITIONS THROUGHOUT THE DURATION OF THE WORKS TO ENSURE NO EXPECTED RISE IN WATER LEVELS
SITE AREA IS OPEN TO PUBLIC	CONTRACTOR TO ENSURE SAFETY MEASURES ARE IN PLACE TO INFORM AND RESTRICT PUBLIC ACCESS
THE SITE SLOPE DOWNS FROM TOP EMBANKMENT TO THE MARINA	CONTRACTOR TO ENSURE SAFE ACCESS AND MOVEMENT IS MAINTAINED ON SITE. CONTRACTOR NOT TO LOAD TOP OF SLOPE UNTIL SHEET PILES ARE INSTALLED.
STABILITY OF EMBANKMENT SLOPE	WORKS TO CEASE AND ADVICE TO BE SOUGHT IF EVIDENCE OF MOVEMENT DETECTED
PLANT OPERATION	WEST SECTION OF WORKS (SECTION D-D & E-E) DESIGNED FOR 20kPa TO PERMIT INSTALLATION OF SHEETS FROM LAND.
FAILURE OF GROUND ANCHORS	PROOF LOADED TO DEMONSTRATE CAPACITY
FAILURE OF ANCHOR DURING TESTING	ONLY OPERATIVES WITH SPECIFIC TRAINING TO UNDERTAKE TESTING
RESIDUAL HAZARD	SUGGESTED CONTROL MEASURE

SIGNIFICANT RESIDUAL HAZARDS

NOTE: The above hazards do not include every hazard or assumption, but identify significant residual construction hazards that are not likely to be obvious to a competent contractor and those that could be difficult to manage effectively. Refer also to the designer's risk documentation.

DRAWING No.		
A123043-TGEE-ZZ-XX-DR-C-0005		
DRAWN : JHB	DESIGNED : MHG	REVISION
SCALE : 1:200	ORIGINAL SIZE : A1	C01