
 DAMAGED TILES  
 TILES EXIST WITH LATEX LEVELING SCREED OVER

**FLOOR CLEANING**

WHOLE CERAMIC FLOOR AREA TO BE CLEANED WITH THE FOLLOWING APPLICATION:

WHOLE FLOOR TO BE CLEANED FOLLOWING APPLICATION.

SOFTENING AND REMOVING LATEX SCREEDING.

CHEMICALLY TREATING AREAS TO REMOVE GLUE RESIDUE AND PAINT SPLASHES.

HAND WASHING AND SCRUBBING WITH HAND STEAM CLEANERS.

# ENTRANCE HALL TILING DAMAGE SURVEY

0 500mm 2500mm Scale 1:25

**Butler Hegarty Architects**  
 Unit 3.3, Islington Studios, 159-163 Marlborough Road, London, N19 4NF  
 tel: 020 72638933 email: mail@butlerhegartyarchitects.co.uk

Rev A Scale altered Nov 24  
**16 St. Peters Road**  
 Title: Entrance Hall Damage Survey  
 Drawing No: 0122823-Su20A Scale 1:25 @ A3