

Strawberry Hill House, Waldegrave Road, Twickenham TW1 4ST
Installation of additional security cameras

Schedule of work

Clear area of obstructions, protect ground below site of camera installation with ground sheets. Erect tower or ladders to give safe access to location of cameras.

Supply and fix cameras to external walls of the house as set out in manufacturer's instructions.

Make good surrounding wall surfaces if necessary.

Remove tower and ladders, clean up and remove all waste and packaging for recycling where possible.

Test and adjust cameras and leave full instructions with staff of the house.

January 2025